



Scale 1"=50'

BASIS OF BEARINGS

Survey No. 1440

LEGEND

- Found Grant County Surveyor brass cap set in concrete.
- Found 5/8" iron pin.
- Set 5/8"x30" iron pin with attached red plastic cap marked CORNERSTONE SURVEYING, INC.
- x-X Fence Line
- Deed record bearing and distance.
- Survey No. 354 record bearing and distance.
- Survey No. 1440 record bearing and distance.
- Found monument, see record map of survey number shown in box.

NARRATIVE

This survey was performed at the request of Klaus Hoehna. The purpose of this survey was to establish the property corners as described in Instrument No. 992216, deeds of Grant County, Oregon.

A search was made of the available records pertaining to this survey. I found and accepted the monuments of Survey No. 354 as shown hereon. I extended the easterly right of way line of Main Street which is shown on Survey No. 354 and used the deed record distance to establish the monuments along Main Street. I used the deed record distances and ran the east—west boundaries parallel to the north line of Cochran's Additions and the easterly boundaries parallel to Main Street.



CORNERSTONE SURVEYING, Inc. 233 S. Canyon Blvd., John Day, Oregon 97845

(541) 575-1813

MAP OF SURVEY SITUATED IN THE NE1/4 OF SECTION 1 T9S, R27E, W.M. TOWN OF MONUMENT

GRANT COUNTY, OREGON

SURVEYED FOR: Klaus Hoehna

SURVEYED BY : Jack Watson Date: 8/3/2006

DRAWN BY : Jack Watson

RECEIVED AND FILED

