



BASIS OF BEARINGS

RECORD MAP OF SURVEY NO. 956 AS SHOWN

REFERENCES

RECORD MAP OF SURVEY NO.'S 245, 467, 956, 1034 & 1187 DEED RECORD INSTRUMENT NO.'S 201458 & 041171

DEED RECORD BOOK 39 PAGE 74 DEED RECORD BOOK 85 PAGE 100 DEED RECORD BOOK 88 PAGE 114

O.D.O.T. HIGHWAY DRAWING NO. 8B-18-25

NARRATIVE

THIS SURVEY WAS PERFORMED AT THE REQUEST OF ERICH TIMKO AND ARLEN VANNICE. THE PURPOSE OF THIS SURVEY WAS TO LOCATE AND MONUMENT THE PROPOSED PROPERTY LINE ADJUSTMENT BETWEEN THE TIMKO PROPERTY AND VANNICE PROPERTY LOCATED IN GOVERNMENT LOT 4, T.15S., R.31E., W.M., AS SHOWN HEREON.

A SEARCH WAS MADE OF THE AVAILABLE RECORDS PERTAINING TO THIS SURVEY. WE MADE FIELD MEASUREMENTS TO LOCATE CONTROLLING MONUMENTS SHOWN ON RECORD MAP OF SURVEY NO.'S 245, 467, 956, 1034 AND 1187. I ACCEPT THE APPURTENANT MONUMENTS FROM THESE SURVEYS, AS SHOWN HEREON.

RECORD BEARINGS FROM O.D.O.T. HIGHWAY DRAWING NO. 8B-18-25 WERE ROTATED 00°03'10" COUNTERCLOCKWISE TO MATCH THE EXISTING CENTERLINE.

WE SET NEW MONUMENTS AT POSITIONS APPROVED BY THE TIMKOS AND THE VANNICES AND ACCORDING TO THE EVIDENCE FOUND, AS SHOWN HEREON.

PROFESSIONAL LAND SURVEYOR

OREGON

JULY 9, 2002 MICHAEL C. SPRINGER #70918 EXPIRES: 6/30/2008 Oct. 10, 2006
OFFICE OF COUNTY SURVEYOR

Colert D. Bayett

TEST: Jan 2 Hayling

RECEIVED AND

LEGEND

- FOUND 1½" GALV. IRON PIPE WITH ATTACHED GRANT COUNTY SURVEYOR BRASS CAP SEE CORNER RESTORATION RECORDS
- FOUND 5/8" IRON PIN WITH NO CAP
- O SET 5/8"X30" IRON PIN WITH ATTACHED YELLOW PLASTIC CAP MARKED BGB SURVEY MARKER
-] RECORD BEARING AND DISTANCE FROM RECORD SURVEY NO. 245
- 1[] RECORD BEARING AND DISTANCE FROM RECORD SURVEY NO. 956
- 2[] RECORD BEARING AND DISTANCE FROM RECORD SURVEY NO. 1034
- 3[] RECORD BEARING AND DISTANCE FROM O.D.O.T.
 HIGHWAY DRAWING NO. 8B-18-25
- FOUND MONUMENT FROM RECORDED SURVEY NO. SURVEY NO. APPEARS IN BOX
- -----X FENCE LINE



MAP OF SURVEY

PROPOSED PROPERTY LINE ADJUSTMENT SITUATED IN GOV'T LOT 4, T.15S., R.31E., W.M., GRANT COUNTY, OREGON

SURVEYED FOR ERICH TIMKO & ARLEN VANNICE

SURVEYED BY MCS & JLH 10/6/2006

Scale: 1"=50' Drawn by: JLH