


**SURVEY OF THE WEST LINE
OF SECTION 4, T.13S., R.31E., W.M.
GRANT COUNTY, OREGON
Survey Completed March 2005**

Ferguson Surveying



Engineering

P.O. BOX 519, 210 E. MAIN
MT. VERNON, OR 97865
PHONE (541)932-4520
FAX (541)932-4430
EMAIL DFSE@ORTELCO.NET



NARRATIVE

THIS SURVEY WAS PERFORMED AT THE REQUEST OF RICK PAGE TO LOCATE THE WEST LINE OF SECTION 4, T.13S., R.31E., W.M.

RECORD MONUMENTS ARE FOUND AND TIED AS SHOWN HEREON AT THE NW CORNER OF SECTION 4, THE S1/4 OF SECTION 5 AND THE SW CORNER OF SECTION 9.

A DILIGENT SEARCH IS MADE FOR THE SW CORNER OF SECTION 4. NO EVIDENCE OF THE ORIGINAL GLO CORNER IS FOUND. THE SEARCH AREA FALLS NEAR A N-S AND EAST FENCE CORNER.

WE THEN LOOK FOR THE ORIGINAL MONUMENTS AT THE W1/4, THE S1/4 AND THE SE CORNER OF SECTION 4. NO EVIDENCE IS RECOVERED AT THESE CORNERS. WE THEN SEARCH FOR THE S1/4 OF SECTION 3 AND THE SE CORNER OF SECTION 3. WE FIND NO EVIDENCE OF THE ORIGINAL GLO CORNERS AT ANY OF THESE LOCATIONS. AT THE SE CORNER OF SECTION 3, WE FIND AN OLD N-S AND W FENCE CORNER.

A DOUBLE PROPORTIONATE POSITION IS CALCULATED FOR THE SW CORNER OF SECTION 4 BASED ON THE FOUND MONUMENTS AT THE S1/4 OF SECTION 5, THE NW CORNER OF SECTION 4, THE SW CORNER OF SECTION 9 AND OLD FENCE CORNER AT THE SE CORNER OF SECTION 3.

WE FIND THE DOUBLE PROPORTIONATE POSITION TO BE N10°45'18"W, 12.48 FT. FROM THE OLD FENCE CORNER. WE THEN ACCEPT THE OLD FENCE AT THE SW CORNER OF SECTION 4 AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER POSITION.

AT THE REQUEST OF MR. PAGE, WE SET A PIN ON THE WEST LINE OF SECTION 4, 440 FEET NORTH OF THE SW CORNER, MARKING THE SOUTH 440 FEET OF SECTION 5 AS DESCRIBED IN DEED INSTRUMENT 031036 OF THE GRANT COUNTY DEED RECORDS.

RECEIVED AND
FILED

JAN 12, 2007
OFFICE OF COUNTY SURVEYOR
Attest: *[Signature]*

GRANT COUNTY MAP OF SURVEY NO. 1789

