



NARRATIVE

THE PURPOSE OF THIS SURVEY IS TO SET AN IRON PIN AT THE CORRECT LOCATION AS SHOWN ON RECORD MAP OF SURVEY NO. 410. WE MADE FIELD MEASUREMENTS TO LOCATE APPURTENANT MONUMENTS SHOWN ON RECORD MAP OF SURVEY NO. 410, 436 AND 448, AS SHOWN.

I CONDUCTED SURVEY NO. 410 IN JULY 1976. DURING THAT SURVEY, I INADVERTENTLY SET THE WESTERN MOST PIN OUT OF POSITION. THIS CAME TO MY ATTENTION WHILE WE WERE RETRACING THE LINE LABELED S.56°04'58\"/>

WE BEGAN THE RETRACEMENT ON THE EAST END OF THIS LINE AT DOG CREEK ROAD. IT BECAME APPARENT THAT THE PIN AT THE WEST END OF THE LINE WAS NOT IN RECORD POSITION.

UPON A REVIEW OF MY FIELD NOTES FROM SURVEY NO 410, I DISCOVERED THAT I MADE A COMPUTING ERROR IN REDUCING THE VERTICAL ANGLE THAT I TURNED FROM MY CONTROL POINT TO SET THIS PIN. THIS VERIFIED THE LOCATION OF WHERE WE FOUND THE PIN.

I ALSO SET AN IRON PIN ON THIS RECORD LINE IN MAY 1977, AS SHOWN ON RECORD MAP OF SURVEY NO. 448. DURING THIS CURRENT RETRACEMENT, WE FOUND THAT THIS PIN WAS SET IN THE CORRECT POSITION.

I HELD THE PIN FOUND AT THE NORTH POINT MOS 410 AND THE FOUND PIN AT THE NE CORNER OF THE TRACT SHOWN ON MOS 448 FOR LINE AND HELD THE RECORD DISTANCE OF 575.00 FROM RECORD SURVEY NO. 448 ALONG THIS LINE TO SET THE NEW PIN.

WE FOUND THE PIN AT THE ANGLE POINT IN THE WEST LINE SHOWN ON RECORD SURVEY NO. 410 IN GOOD CONDITION, ACCEPTED.

WE FOUND THE PIN FROM RECORD SURVEY NO. 436, AT THE SE CORNER OF THE TRACT SHOWN ON MOS 448 IN GOOD CONDITION, ACCEPTED.

WE FOUND THE PIN AT THE SW CORNER OF THE TRACT SHOWN ON RECORD SURVEY NO. 448 DISTURBED AT A FENCE CORNER, AS SHOWN HEREON.

BASIS OF BEARINGS

RECORD SURVEY NO. 410
AS SHOWN

LEGEND

- FOUND 5/8" IRON PIN - NO CAP FROM SURVEY NO. 410 UNLESS OTHERWISE NOTED
- SET 5/8"x30" IRON PIN WITH ATTACHED YELLOW PLASTIC CAP MARKED BGB SURVEY MARKER
- [] RECORD BEARING AND DISTANCE FROM SURVEY NO. 410
- 1[] RECORD BEARING AND DISTANCE FROM SURVEY NO. 436
- 2[] RECORD BEARING AND DISTANCE FROM SURVEY NO. 448
- FOUND MONUMENT FROM RECORDED SURVEY NO. □ SURVEY NO. APPEARS IN BOX
- X—X FENCE LINE

RECEIVED AND FILED

DEC. 28, 2007
OFFICE OF COUNTY SURVEYOR

Robert D. Baggett
ATTEST: *James L. Blackford*

REGISTERED PROFESSIONAL LAND SURVEYOR

Robert D. Baggett
OREGON
JULY 12, 1963
ROBERT D. BAGETT
598

Renewal Date 12/31/09

BAGETT, GRIFFITH & BLACKMAN
217 N. Canyon Blvd. John Day, Oregon

MAP OF SURVEY
CORRECTION SURVEY
SITUATED IN THE NE1/4 SECTION 30,
T.13S., R.32E., W.M.,
GRANT COUNTY, OREGON

SURVEYED FOR	THE RECORD	
SURVEYED BY	RDB, MCS & JLH	12/12/2007
Scale: 1"=200'	Drawn by: MCS	

RECORD MAP OF SURVEY NO. 1804