



Scale 1"=500'

### BASIS OF BEARINGS

Survey No. 1536

### LEGEND

- Found 2" galv. iron pipe with attached 2½" 1939 GLO brass cap.
  - ⊙ Found 1½" galv. iron pipe with attached 2½" Grant County Surveyor brass cap.
  - ⊙ Found 2½" alum. pipe with attached 3½" alum. cap, See Survey No. 1536.
  - Found 5/8" iron pin with attached red plastic cap, See Survey No. 1536.
  - Set 5/8"x30" iron pin with attached red plastic cap marked CORNERSTONE SURVEYING, INC.
- 1( ) 1880 GLO record bearing and distance.
- 2( ) 1939 GLO record bearing and distance.
- 3( ) Map of Survey No. 1536 record bearing and distance.
- Found monument, see record map of survey number shown in box.

### NARRATIVE

This survey was performed at the request of Roger Lang. The purpose of this survey was to establish the SW corner of Mr. Lang's property and flag the property lines.

A search was made of the available records pertaining to this survey. Field measurements were made to locate the monuments shown, to establish the SW corner of the E1/2SW1/4 of Section 8 and to flag the property lines. Section 8 was subdivided in 1999, see Survey No. 1536. The SW corner of the E1/2SW1/4 was established at the mid point and on line between the found monuments at the S1/4 corner and the SW corner of Section 8. I accepted the monuments shown.

RECEIVED AND  
FILED

JUNE 8, 2007  
OFFICE OF COUNTY SURVEYOR  
Attest: *[Signature]*

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

OREGON  
SEPT 19, 1995  
JACK L. WATSON  
2734

Renewal Date 6/30/2008



**CORNERSTONE SURVEYING, Inc.**

233 S. Canyon Blvd., John Day, Oregon 97845  
(541) 575-1813

MAP OF SURVEY  
SUBDIVISION OF SECTION 8  
T14S, R32E, W.M.

GRANT COUNTY, OREGON

SURVEYED FOR: **Roger Lang**

SURVEYED BY : Jack Watson

Date: 5/11/2007

DRAWN BY : Jack Watson

MAP OF SURVEY NO. 1806