

THE SW1/4SW1/4SW1/4 OF SECTION 26
T9S, R35E, WM, GRANT COUNTY, OREGON

THE PURPOSE OF THIS SURVEY WAS TO SET THE NORTHERLY CORNERS OF THE SW1/4SW1/4SW1/4 OF SECTION 26, T9S, R35E, WM, IN GRANT COUNTY, OREGON, AT THE REQUEST OF DAVID JENNINGS.

THIS SECTION WAS SURVEYED IN 1982 BY A US FOREST SERVICE CONTRACT AND RECORDED AS MAP OF SURVEY No. 746. I FOUND ALL THE CORNERS THAT HAD BEEN SET AROUND THE W1/2SW1/4SW1/4 TO CHECK OUT FAIRLY WELL WITH THAT SURVEY MAP EXCEPT THE MONUMENT AT THE MIDPOINT OF THE NORTH LINE. THAT MONUMENT IS AROUND 15 FEET OUT OF THE CALLED POSITION. I DID FIND EVIDENCE OF THE TWO BEARING TREES AT THE RECORD BEARINGS AND DISTANCES, SO IT IS FAIRLY EVIDENT THAT THE MONUMENT HAD NOT BEEN MOVED. I ATTEMPTED TO MAKE CONTACT WITH JAMES PROCHNAU, PLS 1305, TO TELL HIM ABOUT THIS PROBLEM, BUT RECEIVED NO ANSWER FROM HIM. I DELAYED RECORDING THIS PLAT WITH A HOPE THAT HE OR AN ASSOCIATE WOULD CONTACT ME AND THE PROBLEM COULD BE RESOLVED ON THIS PLAT. THIS CORNER WAS NOT USED TO DETERMINE THE BOUNDARY FOR THIS SURVEY, BUT IS SHOWN FOR INFORMATION

THE TWO MONUMENTS THAT WERE PREVIOUSLY SET BY SURVEY No. 746 AT THE INTERSECTIONS OF MINERAL SURVEY No. 595 WITH THE LINE BETWEEN SECTIONS 26 AND 27 ARE IN AN AREA WITH A HEAVY DOWNFALL OF TREES AND THERE IS A GOOD POSSIBILITY THAT THESE MONUMENTS HAVE BEEN SLIGHTLY DISTURBED. THEY WERE NOT USED TO DETERMINE THE POSITION OF THE NW CORNER OF THE PROPERTY BEING SURVEYED, BUT ARE SHOWN AS FOUND DURING THIS SURVEY.

I, LELAND LEE MYERS, A PROFESSIONAL LAND SURVEYOR REGISTERED IN THE STATE OF OREGON, 587 E AUBURN STREET, PO BOX 99, SUMPTER, OREGON 97877, COMPLETED THIS SURVEY ON JUNE 1, 2007, DO HEREBY CERTIFY THAT I HAVE CORRECTLY SURVEYED AND MARKED WITH PROPER MONUMENTS IN ACCORDANCE WITH ORS CHAPTER 209 THE LANDS AS REPRESENTED AND THAT THE INFORMATION SHOWN ON THIS MAP IS CORRECT TO THE BEST OF MY KNOWLEDGE.

FOUND 2 1/2" BRASS CAP ON
2" GALV PIPE BY PLS 1305
UNLESS OTHERWISE NOTED

Renewal Date 1/1/09

JAN. 22, 2008
OFFICE OF COUNTY SURVEYOR
Attest: James H. Hays

MAP OF SURVEY No. 1832