



**LEGEND**

- Found 1½" iron pipe with attached 2½" Grant County Surveyor brass cap.
- Set 5/8"x30" iron pin with attached red plastic cap marked CORNERSTONE SURVEYING, INC.
- X—X Fence Line

**NARRATIVE**

This survey was performed at the request of Don Capon. The purpose of this survey was to survey and monument an existing fence line for a proposed boundary adjustment.

This survey was performed using static GPS receivers and Electronic Total Station. The bearings for this survey are based on the GPS survey. The GPS survey was made in NAD 83 state plane coordinates, Oregon north zone. The state plane bearings were rotated clockwise 00°44'35" to true north at the SE corner of Section 35, T8S, R27E, W.M.. All bearings are relative to this local north meridian.

A search was made of the available records pertaining to this survey. Monuments were established at the major angle points of the existing fence along the north and west boundaries. The fence lines were located as shown. An existing road was also located through the property for future access.

In the interest of economy no effort was made to locate the section or subdivision of section lines during this survey.

**CORNERSTONE SURVEYING, Inc.**  
 233 S. Canyon Blvd., John Day, Oregon 97845  
 (541) 575-1813

RECEIVED AND FILED  
 FEB. 5, 2008  
 OFFICE OF COUNTY SURVEYOR  
 Attest: *[Signature]*

REGISTERED  
**PROFESSIONAL  
 LAND SURVEYOR**  
*[Signature]*  
**OREGON**  
 SEPT. 19, 1995  
 JACK L. WATSON  
 2734  
 Renewal Date 6/30/2008

MAP OF SURVEY PROPOSED BOUNDARY ADJUSTMENT SITUATED IN THE SE1/4 OF SECTION 35, T8S, R27E, W.M. AND IN THE NE1/4 OF SECTION 3, T9S, R27E, W.M.	
GRANT COUNTY, OREGON	
SURVEYED FOR: <b>Don Capon</b>	
SURVEYED BY : Jack Watson	Date: 01/11/2008
DRAWN BY : Jack Watson	