



Scale 1"=300'

BASIS OF BEARINGS

Survey No. 300

LEGEND

- Found 3 1/2" iron pipe with attached 3 1/2" BLM brass cap of record.
- Found 1 1/2" iron pipe with attached 2 1/2" Grant County Surveyor brass cap, see Survey No. 300.
- Found 2 1/2" iron pipe with attached 2 1/2" brass cap, see Survey No. 649.
- Set 5/8"x30" iron pin with attached red plastic cap marked CORNERSTONE SURVEYING, INC.
- x—x Fence Line
- 1() Survey No. 300 record bearing and distance.
- 2() Survey No. 649 record bearing and distance.
- 3() Land Partition No. 2007-08 record bearing and distance.
- 4() Highway Drawing No. 5B-33-19 record bearing and distance.

NARRATIVE

This partition was performed at the request of Ernest Shultz. The purpose of this survey was to monument the corners of Parcel 2 of Land Partition No. 2007-08, which is recorded in the Grant County Clerks office.

A search was made of the available records pertaining to this survey. Partition Plat No. 2007-08, Survey No. 300, Survey No. 649 and Highway Drawing No. 5B-33-19 are appurtenant. I held the boundary calls given on Partition Plat No. 2007-08 for Parcel 2. I found and accepted the monuments shown hereon. I located the existing highway center line stripe which agrees very closely with Highway Drawing No. 5B-33-19. I rotated the bearings given on the highway drawing, counterclockwise 00°03'00" to fit the existing highway center line.

RECEIVED AND
FILED

APRIL 2, 2008
OFFICE OF COUNTY SURVEYOR
JACK L. WATSON
2734

REGISTERED
PROFESSIONAL
LAND SURVEYOR
JACK L. WATSON
SEPT 19, 1995
2734
Renewal Date 6/30/2008



CORNERSTONE SURVEYING, Inc.
233 S. Canyon Blvd., John Day, Oregon 97845
(541) 575-1813

MAP OF SURVEY
PARCEL 2 OF LAND PARTITION NO. 2007-08
SITUATED IN THE SE1/4 OF SECTION 29 AND IN THE
NE1/4 OF SECTION 32, T7S, R31E, W.M.
GRANT COUNTY, OREGON
SURVEYED FOR: Ernest Shultz
SURVEYED BY: Jack Watson
SURVEY COMPLETED: 3/13/2008

MAP OF SURVEY NO. 1838