

Wilson Street

Point being 273.53 ft. South and 986.68 ft. West of the C1/4 corner of Section 1, T9S, R27E. The C1/4 corner is monumented with a Grant County Surveyor brass cap monument set in concrete.

N86°13'42"E 86.83

Proposed Boundary Adjustment Line  
N00°28'24"E 132.36

BASIS OF BEARINGS  
(N00°42'00"W 160.00)  
S00°42'00"E 160.00

N86°13'42"E 61.61  
(S86°13'42"W 61.61)

Proposed Boundary Adjustment Line  
N00°53'27"E 138.99

Proposed Boundary Adjustment Line  
S00°11'33"W 118.51

S89°01'39"W 152.95

Proposed Boundary Adjustment Line



Scale 1"=20'

### BASIS OF BEARINGS

Survey No. 1825

### LEGEND

- Found 5/8" iron pin with attached red plastic cap. See Survey No. 1825.
- Set 5/8"x30" iron pin with attached red plastic cap marked CORNERSTONE SURVEYING, INC.
- X—X Fence Line
- ( ) Record Survey No. 1825.

### NARRATIVE

This survey was performed at the request of Philip Merricks. The purpose of this survey was to establish the proposed boundary adjustment lines as shown.

A search was made of the available records pertaining to this survey. Field measurements were made to locate the existing monuments and the fence lines.

I accepted the monuments shown as found from Survey No. 1825. The adjacent land owners have agreed to the placement of the proposed boundary adjustment lines shown hereon.

RECEIVED AND  
FILED

OCT 20, 2008

OFFICE OF COUNTY SURVEYOR  
Attest: *[Signature]*

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*[Signature]*  
OREGON  
SEPT 19, 1995  
JACK L. WATSON  
2734

Renewal Date 6/30/2010



CORNERSTONE SURVEYING, Inc.

233 S. Canyon Blvd., John Day, Oregon 97845  
(541) 575-1813

MAP OF SURVEY  
PROPOSED BOUNDARY ADJUSTMENT LINES  
IN LOTS 3 & 4, BLOCK 2, TOWN OF MONUMENT  
SITUATED IN THE SW1/4 OF SECTION 1, T9S, R27E, W.M.  
TOWN OF MONUMENT  
GRANT COUNTY, OREGON

SURVEYED FOR: Philip Merricks

SURVEYED BY: Jack Watson

SURVEY COMPLETED: 10/09/2008

MAP OF SURVEY NO. 1849