

Point being 631.95 south  
and 1960.08 east of the  
N1/4 corner of Section 26  
which is a Grant County Surveyor  
brass cap set in concrete.

### BASIS OF BEARINGS

(N83°36'32"W 342.11)  
1(N83°36'32"W 342.11)  
N83°36'32"W 341.96

(S06°23'28"W 75.00)  
1(S06°23'28"W 75.00)  
S06°23'27"W 74.98

N06°12'55"E 54.97  
(N06°23'28"E 55.00)  
1(N06°23'28"E 55)

S83°36'32"E 290.06  
(S83°36'32"E 290)  
1(S83°36'32"E 290.00)

N00°57'28"E  
20.14  
(N00°57'28"E 20.09)  
1(N00°57'28"E 20.09)

S83°33'49"E 53.98  
(S83°36'32"E 54.00 1/2)  
1(S83°36'32"E 54.00)

U.S Highway No. 26

Scale 1"=20'

### BASIS OF BEARINGS

Survey No. 468

### LEGEND

- Set 5/8"x30" iron pin with attached red plastic cap marked CORNERSTONE SURVEYING, INC. over a found 5/8" iron pin from Survey No. 468.
- x—x Fence Line
- ( ) Deed record bearing and distance  
See Inst. No. 043169.
- 1( ) Survey No. 468 record bearing and distance.

### NARRATIVE

This survey was performed at the request of Ken Smith. The purpose of this survey was to locate the monuments of this tract which were established and shown on Grant County Survey No. 468.

Field measurements were made to locate the existing monuments. All the monuments marking the boundaries of this tract were recovered. These monuments have been covered by as much as 2 feet of fill. Mr. Smith asked me to set monuments that were visible at the ground surface. The original monuments are still in place and I have set another monument over them flush with the existing ground.

RECEIVED AND  
FILED

December 28, 2009

OFFICE OF COUNTY SURVEYOR  
Attest: *[Signature]*

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*[Signature]*  
OREGON  
SEPT 19, 1995  
JACK L. WATSON  
2734

Renewal Date 6/30/2010



**CORNERSTONE SURVEYING, Inc.**  
233 S. Canyon Blvd., John Day, Oregon 97845  
(541) 575-1813

MAP OF SURVEY  
SITUATED IN THE NE1/4 OF SECTION 26  
T13S, R31E, W.M.  
CITY OF JOHN DAY  
GRANT COUNTY, OREGON

SURVEYED FOR: Ken Smith

SURVEYED BY: Jack Watson

SURVEY COMPLETED: 12/22/2009

MAP OF SURVEY NO. 1886