






















SURVEY OF OCHOCO NATIONAL FOREST BOUNDARY LINES IN THE SW 1/4 OF SECTION 14, IN THE NE 1/4 OF SECTION 19, IN THE NW 1/4 OF SECTION 20, IN THE SE 1/4 OF SECTION 27, IN THE E 1/2 OF SECTION 28, IN THE W 1/2 OF SECTION 31 AND IN THE NE 1/4 OF SECTION 34, TOWNSHIP 16 SOUTH, RANGE 26 EAST, W.M., GRANT COUNTY, OREGON W.O. 09-3921 WILLOW CADASTRAL SURVEY CON. NO. AG-04NO-D-09-0012

REGISTERED
PROFESSIONAL
LAND SURVEYOR

David B. Armstrong

9/30/10 OREGON
AUGUST 22, 1973
DAVID B. ARMSTRONG
1026

Renewed 12/31/11

CAP MARKINGS CORNER INDEX NO. MONUMENT ORIGIN	CORNER EVIDENCE FOUND CORNER MONUMENTATION	CORNER ACCESSORIES	CAP MARKINGS CORNER INDEX NO. MONUMENT ORIGIN	CORNER EVIDENCE FOUND CORNER MONUMENTATION	CORNER ACCESSORIES
J-19 BLM P 15 	MONUMENT: FOUND 2-1/2 INS. GALV. PIPE WITH 3-1/4 INS. DIAM. BRASS CAP 16 INS. ABOVE GRND., LEANING OVER TO NW IN CENTER 5 FT. DIAM. STONE MOUND. MONUMENTATION: RESET FOUND MONUMENT AT ORIG. POSITION OF BASE 16 INS. ABOVE GRND., RAISED STONE MOUND 4 FT. DIAM. TO CAP. SET AP 5 FT. S W/SIGN 54-9 FACING CAP. LATITUDE: 44°11'26.07669" N LONGITUDE: 119°34'01.02807" W	BT'S FOUND: 13 INS. X 16 INS. X 24 INS. TRIPLE JUN., N48-1/2°E, 117.1 FT., OPEN FACE V.S.-1/4 S11 BT. BT'S MARKED: 10 INS. X 48 INS. DOUBLE JUN., S85°E, 247.0 FT., SCRIBED -1/4 S14 BT; 18 INS. JUN., S06°W, 361.5 FT., SCRIBED -1/4 S14 XBT-TREE IN N-S WIRE FENCE LINE; 8 INS. JUN., N63°W, 227.3 FT., SCRIBED -X-@BH-BT.	O-5 BLM P 35 	MONUMENT: FOUND 2-1/2 INS. GALV. PIPE WITH 3-1/4 INS. DIAM. BRASS CAP 14 INS. ABOVE GRND., IN 6 FT. DIAM. STONE MOUND. MONUMENTATION: REBUILT STONE MOUND 4 FT. DIAM. TO CAP. SET AP 5 FT. E W/SIGNS 54-2 AND 54-9 FACING CAP. LATITUDE: 44°10'22.29163" N LONGITUDE: 119°38'15.48814" W	BT'S FOUND: 18 INS. JUN., N17-1/2°E, 44.6 FT., V.S. -N1/16 S20 BT; 16 INS. JUN., N75-1/2°W, 76.1 FT., HEALED FACE.
L-17 BLM P 13 	MONUMENT: FOUND 2-1/2 INS. GALV. PIPE WITH 3-1/4 INS. DIAM. BRASS CAP 4 INS. ABOVE GRND., IN 3 FT. DIAM. STONE MOUND. MONUMENTATION: SET AP 3 FT. W W/SIGNS 54-2 AND 54-9 FACING CAP. LATITUDE: 44°11'02.05451" N LONGITUDE: 119°34'37.85888" W	BT'S FOUND: 21 INS. POND. PINE, S17°E, 26.2 FT., HEALED FACE; 20 INS. POND. PINE, N62°W, 17.3 FT., HEALED FACE.	O-7 CS67 P 37 	MONUMENT: FOUND 2-1/2 INS. GALV. IRON PIPE WITH 2-1/2 INS. DIAM. BRASS CAP 12 INS. ABOVE GRND., IN 2 FT. DIAM. STONE MOUND. MONUMENTATION: REBUILT STONE MOUND 2 FT. DIAM. TO CAP. SET AP 5 FT. N W/SIGNS 54-2 AND 54-9 FACING CAP. LATITUDE: 44°10'24.06145" N LONGITUDE: 119°37'39.43230" W	BT'S MARKED: 9 INS. POND. PINE, S80-1/2°E, 67.8 FT., SCRIBED -CN1/16 S20 BT; 6 INS. JUN., N02-1/2°W, 52.8 FT., SCRIBED -X-@BH-BT.
L-19 CS67 P 12 	MONUMENT: FOUND 2-1/2 INS. GALV. PIPE WITH 2-1/2 INS. DIAM. BRASS CAP 10 INS. ABOVE GRND., IN 2 FT. DIAM. STONE MOUND. MONUMENTATION: REBUILT 2 FT. DIAM. STONE MOUND TO CAP. SET AP 5 FT. S W/SIGNS 54-2 AND 54-9 FACING CAP. LATITUDE: 44°11'00.09242" N LONGITUDE: W119°34'01.37121" W	BT'S MARKED: 10 INS. POND. PINE, N60°E, 44.9 FT., SCRIBED -C1/4 S14 BT; 19 INS. POND. PINE, S53°E, 90.7 FT., SCRIBED -C1/4 S14X BT; 26 INS. POND. PINE, S58°W, 10.2 FT., SCRIBED -C1/4 S14 BTX; 13 INS. POND. PINE, N12°W, 33.7 FT., SCRIBED -X-@BH-BT.	P-1 BLM P 41 	MONUMENT: FOUND 2-1/2 INS. GALV. PIPE WITH 3-1/4 INS. DIAM. BRASS CAP 7 INS. ABOVE GRND. IN 4 FT. DIAM. STONE MOUND. MONUMENTATION: SET AP 5 FT. N W/SIGN 54-9 FACING CAP. LATITUDE: 44°10'11.60531" N LONGITUDE: 119°39'25.83559" W	BT'S FOUND: 16 INS. JUN., S45°E, 14.9 FT., V.S. -1/4 S19 BT; 14 INS. JUN., N03°E, 19.4 FT., HEALED FACE.
L-21 BLM P 17 	MONUMENT: FOUND 2-1/2 INS. GALV. PIPE WITH 3-1/4 INS. DIAM. BRASS CAP 4 INS. ABOVE GRND., IN 3 FT. DIAM. STONE MOUND. MONUMENTATION: SET AP 1-1/2 FT. N W/SIGNS 54-2 AND 54-9 FACING CAP. LATITUDE: 44°10'57.83304" N LONGITUDE: W119°33'24.83152" W	BT'S FOUND: 13 INS. POND. PINE, N72°E, 10.3 FT., HEALED FACE; 11 INS. POND. PINE, N24-1/2°W, 21.8 FT., HEALED FACE.	P-3 CS67 P 40 	MONUMENT: FOUND 2-1/2 INS. GALV. PIPE WITH 2-1/2 INS. DIAM. BRASS CAP 21 INS. ABOVE GRND., LEANING OVER TO SOUTH IN CENTER OF 4 FT. DIAM. STONE MOUND. RECOVERED ORIGINAL CORNER POSITION AT BASE OF MONUMENT. MONUMENTATION: RESET FOUND MONUMENT AT ORIG. POSITION OF BASE W/CAP 6 INS. ABOVE GRND., REBUILT STONE MOUND 3 FT. DIAM. TO CAP. SET AP 5 FT. N W/SIGN 54-9 FACING CAP. LATITUDE: 44°10'10.45184" N LONGITUDE: W119°38'51.40909" W	BT'S MARKED: 6 INS. JUN., N51°E, 26.7 FT., SCRIBED -X-@BH-BT; 20 INS. JUN., S65°E, 112.5 FT., SCRIBED -C1/4 S19 BT; 10 INS. JUN., S57°W, 33.6 FT., SCRIBED -C1/4 S19 BTX; 14 INS. JUN., N56°W, 20.3 FT., SCRIBED -C1/4 S19X BT.
M-17 BLM P 14 	MONUMENT: FOUND 2-1/2 INS. GALV. PIPE WITH 3-1/4 INS. DIAM. BRASS CAP 8 INS. ABOVE GRND., NO STONE MOUND PRESENT. MONUMENTATION: RAISED 2 FT. DIAM. STONE MOUND TO CAP. RESET SP 5 FT. E W/SIGNS 54-2 AND 54-9 FACING CAP. LATITUDE: 44°10'48.90651" N LONGITUDE: 119°34'37.93593" W	BT'S FOUND: 25 INS. POND. PINE, S35°E, 187.4 FT., HEALED FACE. BT'S MARKED: 13 INS. POND. PINE, N60-1/2°E, 135.0 FT., SCRIBED -X-@BH-BT.	P-4 CS67 P 33 	MONUMENT: FOUND 2-1/2 INS. GALV. PIPE WITH 2-1/2 INS. DIAM. BRASS CAP 18 INS. ABOVE GRND. IN 3 FT. DIAM. STONE MOUND. MONUMENTATION: SET AP 5-1/2 FT. E W/SIGNS 54-2 AND 54-9 FACING CAP; SET AP 4 FT. N W/SIGNS 54-2 AND 54-9 FACING CAP. LATITUDE: 44°10'09.84429" N LONGITUDE: 119°38'33.31827" W	BT'S MARKED: 9 INS. POND. PINE, N15°E, 9.9 FT., SCRIBED -X-@BH-BT; 11 INS. POND. PINE, S68-1/2°W, 44.8 FT., SCRIBED -CE1/16 S19 BT.
M-19 CS 67 P 16 	MONUMENT: FOUND 2-1/2 INS. GALV. PIPE WITH 2-1/2 INS. DIAM. BRASS CAP REMOVED 12 INS. ABOVE GRND., IN 2 FT. DIAM. STONE MOUND. MONUMENTATION: SET 5/8 INS. X 30 INS. LONG IRON ROD W/ 3-1/4 INS. DIAM. ALUM. CAP MARKED AS SHOWN IN CENTER OF EXISTING IRON PIPE. REBUILT 2 FT. DIAM. STONE MOUND TO CAP. SET AP 5 FT. N W/SIGNS 54-2 AND 54-9 FACING CAP. SET AP 5 FT. W W/SIGNS 54-2 AND 54-9 FACING CAP. LATITUDE: 44°10'46.96546" N LONGITUDE: 119°34'01.55265" W	BT'S MARKED: 8 INS. WHITE FIR, S78-1/2°E, 22.6 FT., SCRIBED -CS1/16 S14 BT; 10 INS. POND. PINE, S08°W, 38.0 FT., SCRIBED -X-@BH-BT.	P-5 BLM P 34 	MONUMENT: FOUND 2-1/2 INS. GALV. PIPE WITH 3-1/4 INS. DIAM. BRASS CAP 5 INS. ABOVE GRND., IN 3-1/2 FT. DIAM. STONE MOUND. MONUMENTATION: SET AP 5 FT. N W/SIGNS 54-2 AND 54-9 FACING CAP. LATITUDE: 44°10'09.23078" N LONGITUDE: 119°38'15.22124" W	BT'S FOUND: 15 INS. JUNIPER, S60-1/2°E, 19.7 FT., V.S. -1/4 S20 BT; 18 INS. JUNIPER, N89°W, 46.3 FT., HEALED FACE.
N-3 BLM P 39 	MONUMENT: FOUND 2-1/2 INS. GALV. PIPE WITH 3-1/4 INS. DIAM. BRASS CAP 6 INS. ABOVE GRND., IN 2-1/2 FT. DIAM. STONE MOUND. MONUMENTATION: SET AP 5 FT. N W/SIGN 54-9 FACING CAP. LATITUDE: 44°10'36.53632" N LONGITUDE: 119°38'51.33541" W	BT'S FOUND: 26 INS. POND. PINE, DEAD & DOWN, S65°W, 74.0 FT. TO STUMP HOLE, LYING ON FACE; 26 INS. POND. PINE, DEAD & DOWN, N26°W, 91.6 FT. TO STUMP HOLE. ROTTEN FACE. BT'S MARKED: 10 INS. POND. PINE, N70-1/2°E, 5.8 FT., SCRIBED -1/4 S18 BTX; 5 INS. X 5 INS. DOUBLE POND. PINE, S36-1/2°E, 40.5 FT., SCRIBED -1/4 S19 BT; 10 INS. JUN., S41°W, 120.6 FT., SCRIBED -X-@BH-BT; 10 INS. POND. PINE, N13°W, 66.9 FT., SCRIBED -1/4 S18 BT.	P-7 CS67 P 43 	MONUMENT: FOUND 2-1/2 INS. GALV. PIPE WITH 2-1/2 INS. DIAM. BRASS CAP 6 INS. ABOVE GRND. WITH A SINGLE STONE N OF CAP. MONUMENTATION: SET AP 5 FT. N W/SIGN 54-9 FACING CAP. LATITUDE: 44°10'10.84229" N LONGITUDE: 119°37'39.38648" W	BT'S MARKED: 15 INS. POND. PINE, N44°E, 25.9 FT., SCRIBED -C1/4 S20 X BT; 7 INS. POND. PINE, S60°E, 25.6 FT., SCRIBED -C1/4 S20 BT; 5 INS. WHITE FIR, S33-1/2°W, 31.7 FT., SCRIBED -X-@BH-BT; 8 INS. POND. PINE, N33-1/2°W, 24.3 FT., SCRIBED -C1/4 S20 BTX.
N-4 BLM P 48 	MONUMENT: FOUND 2-1/2 INS. GALV. PIPE WITH 3-1/4 INS. DIAM. BRASS CAP 4 INS. ABOVE GRND., IN 2-1/2 FT. DIAM. STONE MOUND. MONUMENTATION: SET AP 3-1/2 FT. S W/SIGNS 54-2 AND 54-9 FACING CAP. LATITUDE: 44°10'35.94274" N LONGITUDE: 119°38'33.55063" W	BT'S FOUND: 20 INS. POND. PINE, S56°W, 4.8 FT., HEALED FACE; 17 INS. POND. PINE, N16-1/2°W, 18.5 FT., HEALED FACE.	P-9 BLM P 38 	MONUMENT: FOUND 2-1/2 INS. GALV. PIPE WITH 3-1/4 INS. DIAM. BRASS CAP 6 INS. ABOVE GRND. MONUMENTATION: SET AP 5 FT. N W/SIGN 54-9 FACING CAP. LATITUDE: 44°10'12.43520" N LONGITUDE: 119°37'03.21961" W	BT'S FOUND: 14 INS. POND. PINE, N51°E, 6.0 FT., HEALED FACE; 9 INS. POND. PINE, S11-1/2°W, 33.9 FT., NEARLY HEALED FACE, PORTIONS OF SCRIBING VISIBLE.
N-5 BLM P 36 	MONUMENT: FOUND 2-1/2 INS. GALV. PIPE WITH 3-1/4 INS. DIAM. BRASS CAP 5 INS. ABOVE GRND., IN 5 FT. DIAM. STONE MOUND. MONUMENTATION: SET AP 5 FT. W W/SIGNS 54-2 AND 54-9 FACING CAP. LATITUDE: 44°10'35.34331" N LONGITUDE: 119°38'15.75974" W	BT'S FOUND: 16 INS. POND. PINE, N32°E, 121.6 FT., HEALED FACE; 34 INS. JUN., S69°E, 33.2 FT., V.S.-T16S R26E S20 BT; 15 INS. JUN., S15°W, 126.4 FT., V.S.-T16S R26E S19 BT; 21 INS. JUN., N41°W, 49.4 FT., V.S.-T16S R26E S18 BT.	R-3 BLM P 42 	MONUMENT: FOUND 2-1/2 INS. GALV. PIPE WITH 3-1/4 INS. DIAM. BRASS CAP 22 INS. ABOVE GRND. LEANING OVER TO N IN 5 FT. DIAM. STONE MOUND. RECOVERED ORIGINAL CORNER POSITION AT BASE OF MONUMENT. MONUMENTATION: RESET FOUND MONUMENT AT ORIG. POSITION OF BASE 20 INS. ABOVE GRND. REBUILT 4 FT. DIAM. STONE MOUND TO CAP. SET AP 5 FT. N W/SIGN 54-9 FACING CAP. LATITUDE: 44°09'44.59327" N LONGITUDE: 119°38'51.58198" W	BT'S FOUND: 32 INS. POND. PINE, S61°E, 90.9 FT., V.S. -1/4 S30 BT; 21 INS. POND. PINE, STANDING DEAD, N07°W, 118.9 FT., PARTIALLY HEALED FACE, V.S.- 1/4 S19 BT. BT'S MARKED: 9 INS. JUNIPER, N43-1/2°E, 49.9 FT., SCRIBED -X-@BH-BT; 7 INS. POND. PINE, S44-1/2°W, 47.7 FT., SCRIBED -1/4 S30 BTX; 13 INS. POND. PINE, N51°W, 23.7 FT., SCRIBED -1/4 S19 BTX.
N-7 BLM P 49 	MONUMENT: FOUND 2-1/2 INS. GALV. PIPE WITH 3-1/4 INS. DIAM. BRASS CAP 5 INS. BELOW GRND., NO STONE MOUND PRESENT. MONUMENTATION: RAISED BRASS CAP UP TO FLUSH WITH GRND. AND RAISED 2 FT. DIAM. STONE MOUND TO CAP. SET AP 5 FT. W W/SIGN 54-2 AND 54-9 FACING CAP. LATITUDE: 44°10'37.27045" N LONGITUDE: 119°37'39.49610" W	BT'S FOUND: 34 INS. POND. PINE, N23°E, 74.9 FT., HEALED FACE; 38 INS. POND. PINE, STANDING DEAD, S14-1/2°E, 89.1 FT., V.S.-1/4 S20 BT. BT'S MARKED: 11 INS. POND. PINE, S45°E, 132.2 FT., SCRIBED -1/4 S20 BT; 7 INS. POND. PINE, S41-1/2°W, 138.3 FT., SCRIBED -X-@BH-BT; 14 INS. POND. PINE, N48°W, 49.9 FT., SCRIBED -1/4 S17 BT.	R-7 BLM P 44 	MONUMENT: FOUND 2-1/2 INS. GALV. PIPE WITH 3-1/4 INS. DIAM. BRASS CAP 4 INS. ABOVE GRND., IN 2 FT. DIAM. STONE MOUND. MONUMENTATION: SET AP 5 FT. N W/SIGN 54-9 FACING CAP. LATITUDE: 44°09'44.72975" N LONGITUDE: 119°37'39.37360" W	BT'S FOUND: 38 INS. POND. PINE, S55°W, 28.1 FT., V.S.-S29 BT; 10 INS. POND. PINE, STANDING DEAD, N11°W, 45.6 FT., HEALED FACE. BT'S MARKED: 15 INS. POND. PINE, N45°E, 27.9 FT., SCRIBED -1/4 S20 BT; 6 INS. POND. PINE, S33°E, 6.3 FT., SCRIBED -X-@BH-BT; 9 INS. POND. PINE, N38°W, 35.0 FT., SCRIBED -1/4 S20 BTX.
N-19 BLM P 18 	MONUMENT: FOUND 2-1/2 INS. GALV. PIPE WITH 3-1/4 INS. DIAM. BRASS CAP 7 INS. ABOVE GRND., IN 2-1/2 FT. DIAM. STONE MOUND. MONUMENTATION: SET AP 3 FT. S W/SIGN 54-9 FACING CAP. LATITUDE: 44°10'33.81792" N LONGITUDE: 119°34'01.74889" W	BT'S FOUND: 17 INS. WHITE FIR, N22°E, 4.6 FT., HEALED FACE; 7 INS. WHITE FIR, S57-1/2°W, 3.8 FT., HEALED FACE.			

ARMSTRONG
surveying & engineering, inc.
established 1977

SHEET 5 OF 7
DRG. NO. 10-3921.DWG
W.O. 09-3921

GRANT COUNTY SURVEY 1899