




















*SURVEY OF OCHOCO NATIONAL FOREST BOUNDARY LINES IN THE SW 1/4 OF SECTION 14, IN THE NE 1/4 OF SECTION 19, IN THE NW 1/4 OF SECTION 20, IN THE SE 1/4 OF SECTION 27, IN THE E 1/2 OF SECTION 28, IN THE W 1/2 OF SECTION 31 AND IN THE NE 1/4 OF SECTION 34, TOWNSHIP 16 SOUTH, RANGE 26 EAST, W.M., GRANT COUNTY, OREGON
W.O. 09-3921 WILLOW CADASTRAL SURVEY CON. NO. AG-04NO-D-09-0012*

CAP MARKINGS CORNER INDEX NO. MONUMENT ORIGIN	CORNER EVIDENCE FOUND CORNER MONUMENTATION	CORNER ACCESSORIES	CAP MARKINGS CORNER INDEX NO. MONUMENT ORIGIN	CORNER EVIDENCE FOUND CORNER MONUMENTATION	CORNER ACCESSORIES
R-11 BLM P 20 	MONUMENT: FOUND 2-1/2 INS. GALV. PIPE WITH 3-1/4 INS. DIAM. BRASS CAP UP 9 INS. ABOVE GRND., NO STONE MOUND PRESENT. MONUMENTATION: SET AP 5 FT. N W/SIGN 54-9 FACING CAP. LATITUDE: 44°09'45.40453" N LONGITUDE: 119°36'27.23264" W	BT'S FOUND: 15 INS. POND. PINE, STANDING DEAD W/ TOP BROKEN OUT, S01°E, 21.6 FT., HEALED FACE; 15 INS. POND PINE, N22°W, 7.1 FT., HEALED FACE. BT'S MARKED: 11 INS. POND PINE, N45-1/2°E, 36.4 FT., SCRIBED -1/4 S21 XBT; 7 INS. POND. PINE, S42-1/2°E, 61.3 FT., SCRIBED -1/4 S28 BT; 12 INS. POND PINE, S49-1/2°W, 34.2 FT. SCRIBED -X-@-BH-BT.	U-13 BLM P 25 	MONUMENT: FOUND 2-1/2 INS. GALV. PIPE WITH 3-1/4 INS. DIAM. BRASS CAP 14 INS. ABOVE GRND., LEANING NORTH IN 3-1/2 FT. DIAM. STONE MOUND. N-S-W FENCE CORNER IS N47°W, 5.7 FT.. MONUMENTATION: RESET FOUND MONUMENT AT ORIG. POSITION OF BASE 14 INS. ABOVE GRND. REBUILT STONE MOUND 4 FT. DIAM. TO CAP. SET AP 5 FT. N W/SIGNS 54-2 AND 54-9 FACING CAP. LATITUDE: 44°09'05.24524" N LONGITUDE: 119°35'49.94371" W	BT'S FOUND: 24 INS. FORKED JUN., N61-1/2°E, 184.0 FT., SCRIBED -S1/16 S27 BT; 18 INS. POND. PINE, N36°W, 168.6 FT., HEALED FACE.
R-15 BLM P 28 	MONUMENT: FOUND 2-1/2 INS. GALV. PIPE WITH 3-1/4 INS. DIAM. BRASS CAP 12 INS. ABOVE GRND., IN 6 FT. DIAM. STONE MOUND. MONUMENTATION: SET AP 5 FT. N W/SIGN 54-9 FACING CAP. LATITUDE: 44°09'44.35132" N LONGITUDE: 119°35'15.10863" W	BT'S FOUND: 25 INS. JUN., N57-1/2°E, 176.0 FT., V.S. -1/4 S22 BT. BT'S MARKED: 11 INS. JUN., S82°E, 319.1 FT., SCRIBED -1/4 S27 BT; 4 INS. JUN., S39°W, 28.2 FT., SCRIBED -X-@-BH-BT; 14 INS. JUN., N82°W, 281.6 FT., SCRIBED -1/4 S22 BT.	U-15 CS62 P 31 	MONUMENT: FOUND 2-1/2 INS. GALV. PIPE WITH 2-1/2 INS. DIAM. BRASS CAP 11 INS. ABOVE GRND., IN 2-1/2 FT. DIAM. STONE MOUND. MONUMENTATION: SET AP 2-1/2 FT. S W/SIGNS 54-2 AND 54-9 FACING CAP. LATITUDE: 44°09'04.62440" N LONGITUDE: 119°35'13.33259" W	BT'S MARKED: 13 INS. JUN., N61-1/2°E, 32.1 FT., SCRIBED -CS1/16 S27 BT; 12 INS. JUN., N51°W, 47.3 FT., SCRIBED -X-@BH-BT.
S-11 CS62 P 19 	MONUMENT: FOUND 2-1/2 INS. GALV. PIPE WITH 2-1/2 INS. DIAM. BRASS CAP 9 INS. ABOVE GRND., IN 5 FT. DIAM. STONE MOUND. MONUMENTATION: SET AP 5 FT. E W/SIGNS 54-2 AND 54-9 FACING CAP. SET AP 3-1/2 FT. S W/SIGNS 54-2 AND 54-9 FACING CAP. LATITUDE: 44°09'32.08845" N LONGITUDE: 119°36'27.02604" W	BT'S MARKED: 26 INS. POND. PINE, S83-1/2°W, 106.9 FT., SCRIBED -X-@-BH-BT; 14 INS. POND. PINE, N10-1/2°W, 56.6 FT., SCRIBED -CN1/16 S28 BT.	U-17 BLM P 45 	MONUMENT: FOUND 2-1/2 INS. GALV. PIPE WITH 3-1/4 INS. DIAM. BRASS CAP 6 INS. ABOVE GRND., IN 1-1/2 FT. DIAM. STONE MOUND. MONUMENT IS NE AND ADJACENT TO ROCK JACK FENCE CORNER, FENCES W AND S. MONUMENTATION: SET AP 5 FT. S W/SIGN 54-9 FACING CAP. LATITUDE: 44°09'04.02577" N LONGITUDE: 119°34'36.71175" W	BT'S FOUND: 33 INS. POND. PINE, N60-1/2°E, 36.0 FT., HEALED FACE; 22 INS. POND. PINE, S73-1/2°W, 11.3 FT., HEALED FACE.
S-13 BLM P 27 	MONUMENT: FOUND 2-1/2 INS. GALV. PIPE WITH 3-1/4 INS. DIAM. BRASS CAP 20 INS. ABOVE GRND., LEANING OVER TO E IN CENTER 4-1/2 FT. DIAM. STONE MOUND. RECOVERED ORIG. CORNER POSITION AT BASE OF MONUMENT. MONUMENTATION: RESET FOUND MONUMENT AT ORIG. POSITION OF BASE 20 INS. ABOVE GRND. REBUILT 4-1/2 FT. STONE MOUND TO CAP. SET AP 2 FT. S W/SIGNS 54-2 AND 54-9 FACING CAP. LATITUDE: 44°09'31.82851" N LONGITUDE: 119°35'50.71828" W	BT'S FOUND: 19 INS. JUN., N17°E, 147.4 FT., HEALED FACE; 15 INS. JUN., N22°W, 215.0 FT., HEALED FACE.	V-25/ V-1 BLM P 62 	MONUMENT: FOUND 2-1/2 INS. GALV. PIPE WITH 3-1/4 INS. DIAM. BRASS CAP FLUSH WITH GROUND IN 2 FT. DIAM. STONE MOUND. N-S WIRE FENCE LIES 9.0 FT. E. MONUMENTATION: SET AP 5 FT. S W/SIGNS 54-2 AND 54-9 FACING CAP. LATITUDE: 44°08'52.79458" N LONGITUDE: 119°39'25.90061" W	BT'S FOUND: 18 INS. POND. PINE, N23°E, 44.9 FT., HEALED FACE; 25 INS. POND. PINE, S7°E, 34.2 FT., HEALED FACE; 12 INS. POND. PINE, S26-1/2°W, 17.4 FT., HEALED FACE; 18 INS. POND. PINE, N26°W, 44.0 FT., HEALED FACE.
T-9 BLM P 22 	MONUMENT: FOUND 2-1/2 INS. GALV. PIPE WITH 3-1/4 INS. DIAM. BRASS CAP 24 INS. ABOVE GRND., LEANING OVER TO NE IN CENTER 6 FT. DIAM. STONE MOUND. RECOVERED ORIG. POSITION AT BASE OF MONUMENT. MONUMENTATION: RESET FOUND MONUMENT AT ORIG. POSITION OF BASE 20 INS. ABOVE GRND. REBUILT 6 FT. DIAM. STONE MOUND TO CAP. SET AP 5 FT. S W/SIGN 54-9 FACING CAP. LATITUDE: 44°09'19.04937" N LONGITUDE: 119°37'03.34462" W	BT'S FOUND: 15 INS. POND. PINE, STANDING DEAD, N53-1/2°E, 68.0 FT., HEALED FACE. NO EVIDENCE OF SOUTHWEST BT FOUND. BT'S MARKED: 7 INS. JUN., N50°E, 124.0 FT., SCRIBED -X-@BH-BT; 16 INS. POND. PINE, S39°E, 138.0 FT., SCRIBED -1/4 S28 BT; 11 INS. JUN., S35-1/2°W, 216.6 FT., SCRIBED -1/4 S29 BT; 14 INS. X 12 INS. DOUBLE JUN., N30°W, 412.9 FT. SCRIBED -1/4 S29 XBT.	V-11 BLM P 24 	MONUMENT: FOUND 2-1/2 INS. GALV. PIPE WITH 3-1/4 INS. DIAM. BRASS CAP 8 INS. ABOVE GRND., IN 3 FT. DIAM. STONE MOUND. MONUMENTATION: SET AP 5 FT. N W/SIGN 54-9 FACING CAP. LATITUDE: 44°08'52.11308" N LONGITUDE: 119°36'26.44691" W	BT'S FOUND: 13 INS. POND. PINE, S08°W, 94.1 FT., HEALED FACE; 11 INS. POND. PINE, DEAD AND DOWN, N34°W, 66.6 FT., HEALED FACE. BT'S MARKED: 8 INS. POND. PINE, N44°E, 31.9 FT., SCRIBED -X-@BH-BT; 8 INS. POND. PINE, S42°E, 15.3 FT., SCRIBED -1/4 S33 XBT; 6 INS. POND PINE, N52-1/2°W, 8.1 FT., SCRIBED -1/4 S28 BT.
T-11 CS62 P 21 	MONUMENT: FOUND 2-1/2 INS. GALV. PIPE WITH 2-1/2 INS. DIAM. BRASS CAP 11 INS. ABOVE GRND., IN 4 FT. DIAM. STONE MOUND. N-S WIRE FENCE IS 5-1/2 FT. E. MONUMENTATION: SET AP 5 FT. N W/SIGNS 54-2 AND 54-9 FACING CAP. LATITUDE: 44°09'18.75737" N LONGITUDE: 119°36'26.82538" W	BT'S MARKED: 15 INS. POND. PINE, N51-1/2°E, 56.7 FT., SCRIBED -C1/4 S28 XBT; 14 INS. POND. PINE, S43-1/2°E, 23.7 FT., SCRIBED -C1/4 S28 BT; 11 INS. POND PINE, S55-1/2°W, 48.5 FT., SCRIBED -X-@BH-BT; 13 INS. POND. PINE, N42-1/2°W, 29.4 FT., SCRIBED -C1/4 S28 BTX.	V-15 BLM P 32 	MONUMENT: FOUND 2-1/2 INS. GALV. PIPE WITH 3-1/4 INS. DIAM. BRASS CAP 5 INS. ABOVE GRND., IN 3 FT. DIAM. STONE MOUND. MONUMENTATION: SET AP 5 FT. N W/SIGNS 54-2 AND 54-9 FACING CAP. LATITUDE: 44°08'51.25076" N LONGITUDE: 119°35'12.87628" W	BT'S FOUND: 13 INS. POND. PINE, N61°E, 24.1 FT., HEALED FACE; 20 INS. POND. PINE, S07-1/2°W, 25.1 FT., HEALED FACE.
T-13 BLM P 26 	MONUMENT: FOUND 2-1/2 INS. GALV. PIPE WITH 3-1/4 INS. DIAM. BRASS CAP 8 INS. ABOVE GRND., IN 2 FT. DIAM. STONE MOUND. N-S WIRE FENCE IS 9 FT. W. MONUMENTATION: SET AP 5 FT. N W/SIGNS 54-2 AND 54-9 FACING CAP. LATITUDE: 44°09'18.52087" N LONGITUDE: 119°35'50.34343" W	BT'S FOUND: 28 INS. POND. PINE, S69-1/2°E, 83.8 FT., HEALED FACE; 23 INS. POND. PINE, S22°W, 24.0 FT., HEALED FACE.	V-16 BLM P 47 	MONUMENT: FOUND 2-1/2 INS. GALV. PIPE WITH 3-1/4 INS. DIAM. BRASS CAP 3 INS. ABOVE GRND., IN 3 FT. DIAM. STONE MOUND. MONUMENT IS NE AND ADJACENT TO ROCK JACK FENCE CORNER, FENCES E AND S. MONUMENTATION: SET AP 5 FT. E W/SIGN 54-9 FACING CAP. LATITUDE: 44°08'51.10430" N LONGITUDE: 119°34'54.31610" W	BT'S FOUND: 16 INS. WHITE FIR, S62°W, 20.8 FT., HEALED FACE. NO EVIDENCE OF NORTHEAST BT FOUND. BT'S MARKED: 8 INS. WHITE FIR, N37°E, 18.2 FT., SCRIBED -E1/16 S27 BT.
T-15 CS62 P 29 	MONUMENT: FOUND 2-1/2 INS. GALV. PIPE WITH 2-1/2 INS. DIAM. BRASS CAP 20 INS. ABOVE GRND., LEANING NORTH IN 5-1/2 FT. DIAM. STONE MOUND. MONUMENTATION: RESET FOUND MONUMENT AT ORIG. POSITION OF BASE, 6 INS. ABOVE GROUND. REBUILT 6 FT. DIAM. STONE MOUND TO CAP. SET AP 5 FT. N W/SIGN 54-9 FACING CAP. LATITUDE: 44°09'17.88155" N LONGITUDE: 119°35'13.91903" W	BT'S MARKED: 12 INS. JUN., N28-1/2°E, 56.4 FT., SCRIBED -C1/4 S27 XBT; 16 INS. JUN., S22-1/2°E, 79.2 FT., SCRIBED -C1/4 S27 BT; 7 INS. POND. PINE, S58°W, 105.8 FT., SCRIBED -C1/4 S27 BTX; 8 INS. JUN., N30°W, 93.3 FT., SCRIBED -X-@-BH-BT.	V-17 BLM P 46 	MONUMENT: FOUND 2-1/2 INS. GALV. PIPE WITH 3-1/4 INS. DIAM. BRASS CAP 8 INS. ABOVE GRND. IN 2 FT. DIAM. STONE MOUND. MONUMENT IS EAST OF AND ADJACENT TO ROCK FENCE CORNER, FENCES N AND W. MONUMENTATION: SET AP 5 FT. N W/SIGNS 54-2 AND 54-9 FACING CAP. LATITUDE: 44°08'50.83933" N LONGITUDE: 119°34'35.89880" W	BT'S FOUND: 28 INS. POND. PINE, N30-1/2°E, 55.2 FT., HEALED FACE; 17 INS. WHITE FIR, S34°E, 34.2 FT., HEALED FACE; 37 INS. POND. PINE, S21°W, 44.7 FT., HEALED FACE; 18 INS. WHITE FIR, N47°W, 19.4 FT., HEALED FACE.
T-17 BLM P 30 	MONUMENT: FOUND 2-1/2 INS. GALV. PIPE WITH 3-1/4 INS. DIAM. BRASS CAP 12 INS. ABOVE GRND., IN 6 FT. DIAM. STONE MOUND. MONUMENTATION: REBUILT 6 FT. DIAM. STONE MOUND TO CAP. SET AP 5 FT. N W/SIGN 54-9 FACING CAP. LATITUDE: 44°09'17.22435" N LONGITUDE: 119°34'37.50354" W	BT'S FOUND: 18 INS. JUN., S84-1/2°E, 107.1 FT., V.S. -1/4 S26 BT; 25 INS. POND. PINE, S12°W, 118.3 FT., HEALED FACE.	X-25/ X-1 BLM P 60 	MONUMENT: FOUND 2-1/2 INS. GALV. PIPE WITH 3-1/4 INS. DIAM. BRASS CAP 5 INS. ABOVE GROUND IN 3 FT. DIAM. STONE MOUND. N-S WIRE FENCE LIES 18.6 FT. W OF MONUMENT. MONUMENTATION: SET AP 5 FT. N W/SIGNS 54-2 AND 54-9 FACING CAP. LATITUDE: 44°08'26.39750" N LONGITUDE: 119°39'25.64205" W	BT'S FOUND: 19 INS. POND. PINE, N13°E, 23.2 FT., HEALED FACE; 15 INS. POND. PINE, N62°W 34.1 FT., HEALED FACE.
U-11 CS62 P 23 	MONUMENT: FOUND 2-1/2 INS. GALV. PIPE WITH 2-1/2 INS. DIAM. BRASS CAP 9 INS. ABOVE GRND., IN 4 FT. DIAM. STONE MOUND. MONUMENTATION: SET AP 5 FT. E W/SIGNS 54-2 AND 54-9 FACING CAP. LATITUDE: 44°09'05.42102 N LONGITUDE: 119°36'26.62188" W	BT'S MARKED: 8 INS. POND. PINE, N53-1/2°E, 27.3 FT., SCRIBED -X-@-BH-BT; 8 INS. JUN., N23°W, 23.6 FT., SCRIBED -CS1/16 S28 BT.			

REGISTERED
PROFESSIONAL
LAND SURVEYOR
David B. Armstrong
8/30/10 OREGON
DAVID B. ARMSTRONG
1026
Renewal 12/31/11

ARMSTRONG
surveying & engineering, inc.
established 1977
SHEET 6 OF 7
DRG. NO. 10-3921.DWG
W.O. 09-3921
GRANT COUNTY SURVEY 1899