



# LEGEND

- Found 2 1/2" iron pipe with attached BLM brass cap see Grant County Survey No. 849.
- Set 5/8"x30" iron pin with attached 2" aluminum cap marked CORNERSTONE SURVEYING, INC. and the proper corner designation.
- X—X Fence Line
- ( ) GLO record bearing and distance.
- 1( ) Survey No. 849 record bearing and distance.

## NARRATIVE

This survey was performed at the request of Bruce Hansen. The purpose of this survey was to establish the monument at the S1/16 corner between sections 8 and 9, T11S, R27E, W.M.

This survey was performed using static GPS receivers and Electronic Total Station. The bearings for this survey are based on the GPS survey. The state plane bearings were rotated clockwise 00°42'38" to true north near the SE corner of Section 8.

A search was made of the available records pertaining to this survey. Field measurements were made to locate the existing monuments and the 1/16 corner position. The BLM monumented the section corner and the 1/4 corner positions in 1982, see Survey No. 849 recorded in the Grant County Surveyor's records.

I accept the BLM monuments and established the S1/16 corner on line and at the mid-point between these two monuments.

RECEIVED AND FILED  
GRANT COUNTY SURVEYOR

JUL 05 2011

BY: *[Signature]*

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

OREGON  
SEPT 19, 1995  
JACK L. WATSON  
2734

Renewal Date 6/30/2012



**CORNERSTONE SURVEYING, Inc.**  
233 S. Canyon Blvd., John Day, Oregon 97845  
(541) 575-1813

MAP OF SURVEY  
SITUATED IN THE SE1/4 OF SECTION 8  
T11S, R27E, W.M.  
GRANT COUNTY, OREGON

SURVEYED FOR: **Bruce Hansen**

SURVEYED BY : Jack Watson

SURVEY COMPLETED: 6/24/2011

MAP OF SURVEY NO. 1926