



BASIS OF BEARINGS

N.00°01'47"W. BETWEEN THE W1/4 CORNER AND THE NW CORNER OF SECTION 6. BASED ON THE GEODETIC AZIMUTH DERIVED FROM A GPS OBSERVATION TAKEN NEAR THE W1/4 CORNER.

NARRATIVE

THIS SURVEY WAS PERFORMED FOR THE PURPOSE OF EXAMINING THE CONDITION OF THE MONUMENTS AND ACCESSORIES AT THE NORTHWEST, SOUTHWEST AND WEST 1/4 CORNERS OF SECTIONS 6, T.13S., R.28E., W.M. THE MONUMENTS SHOWN HEREON WERE ALL SET BY GRANT COUNTY SURVEYOR VERNON GLAZE IN 1914.

THE FOLLOWING IS A LIST OF APPURTENANT SURVEYS OF SECTION 6:

THE NORTHWEST CORNER OF SECTION 6 IS ALSO THE CORNER OF TOWNSHIPS 12 AND 13 SOUTH, RANGES 27 AND 28 EAST. THE CORNER WAS ORIGINALLY SET IN 1869 BY U.S. DEPUTY SURVEYOR JOHN B. DAVID UNDER CONTRACT NO. 131.

THE SOUTHWEST CORNER AND WEST 1/4 CORNER OF SAID SECTION 6 WERE SET IN 1873 BY U.S. DEPUTY SURVEYOR W.H. BYARS UNDER CONTRACT NO. 185.

IN 1914 GRANT COUNTY SURVEYOR VERNON GLAZE FOUND THE NORTHWEST CORNER AND WEST 1/4 CORNER OF SECTION 6 AND ESTABLISHED THE SOUTHWEST CORNER. HE SET 1" IRON PIPES WITH BRASS CAPS AT ALL THREE CORNERS. GLAZE'S NOTES ARE RECORDED IN THE GRANT COUNTY SURVEYOR'S OFFICE AS SURVEY NO. 7G.

I FOUND ALL OF MR. GLAZE'S MONUMENTS IN GOOD CONDITION, BUT WITH NO ACCESSORIES. I ADDED BEARING TREE AND REFERENCE POINT ACCESSORIES TO THE MONUMENTS AT THE SOUTHWEST CORNER AND WEST 1/4 CORNER. THERE ARE NO ACCESSORIES AT THE NORTHWEST CORNER EITHER AND I INTEND TO ADD THEM AT A LATER DATE. I ALSO ESTABLISHED STATE PLANE COORDINATES FOR ALL THREE CORNERS SHOWN HEREON.

STATE PLANE COORDINATES ARE BASED ON NGS OPUS SOLUTIONS. SEE CORNER RESTORATION SHEETS FILED IN THE OFFICE OF THE GRANT COUNTY SURVEYOR FOR ADDITIONAL INFORMATION ON THE SOUTHWEST CORNER AND W1/4 CORNER.

LEGEND


- FOUND 1" IRON PIPE WITH ATTACHED BRASS CAP FROM 1914 SURVEY BY COUNTY SURVEYOR VERNON GLAZE SEE RECORD SURVEY NO. 7G
- G[] GLO RECORD BEARING AND DISTANCE
- [] RECORD BEARING AND DISTANCE FROM SURVEY NO. 7G

RECEIVED AND FILED
GRANT COUNTY SURVEYOR

AUG 29 2014

BY: 

REGISTERED
PROFESSIONAL
LAND SURVEYOR


OREGON
JULY 9, 2002
MICHAEL C. SPRINGER
#70918

EXPIRES: 6/30/2016

GRANT COUNTY SURVEYOR
217 N. CANYON BLVD
JOHN DAY, OREGON 97845

MAP OF SURVEY
RESURVEY OF THE WEST LINE OF SECTION 6,
T.13S., R.28E., W.M.,
GRANT COUNTY, OREGON

SURVEYED FOR	GRANT COUNTY
SURVEYED BY	MICHAEL SPRINGER, GRANT COUNTY SURVEYOR
Scale: 1"=500'	Drawn by: MCS 8/21/2014

RECORD MAP OF SURVEY NO. 2008

