



Scale 1"=500'

BASIS OF BEARINGS

Survey No. 1411

LEGEND

- Found 2½" aluminum pipe with attached aluminum cap see Survey No. 1411.
- Found 1½" iron pipe with attached Grant County Surveyor brass cap, see re-monumentation records.
- Set 5/8"x30" iron pin with attached 2" aluminum cap marked CORNERSTONE SURVEYING, INC. and the appropriate corner designation.
- ⊙ Set 2½" aluminum pipe with attached 3¼" aluminum cap, see re-monumentation records for details.
- x—x Fence Line
- () GLO record bearing and distance.
- 1() Survey No. 1411 record bearing and distance.
- 2() Survey No. 1971 record bearing and distance.

NARRATIVE

This survey was performed at the request of Ralph Miller. The purpose of this survey was to monument the property corners, see Grant County Deed Instrument No. 101244.

A search was made of the available records pertaining to this survey. Field measurements were made to locate the existing monuments and the new corner positions. Evidence of the original corner was found at the N1/4 corner of Section 1, which I re-monumented. I accept the Grant County Surveyor monuments at the NE corner and NW corner and at the E1/4 corner of Section 1. The SW section corner and the S1/4 corner were established in Survey No. 1411, which I accept. The section was subdivided in accordance with the 2009 Manual of Surveying Instructions and monuments were established as shown.

This survey was performed using a Leica TCR 1101 total station.

RECEIVED AND FILED
GRANT COUNTY SURVEYOR

OCT 27 2014

BY: *[Signature]*

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
SEPT 19, 1995
JACK L. WATSON
2734

Renewal Date 6/30/2016



CORNERSTONE SURVEYING, Inc.
233 S. Canyon Blvd., John Day, Oregon 97845
(541) 575-1813

MAP OF SURVEY
SITUATED IN SECTION 1, T8S, R27E, W.M.
GRANT COUNTY, OREGON

SURVEYED FOR: **Ralph Miller**

SURVEYED BY: **Jack Watson**

SURVEY COMPLETED: 10/20/2014