

LEGEND

- SET 5/8" x 30" IRON PIN STAMPED B.G.F. SURVEY MK
- FOUND MONUMENT
- ⊙ FOUND ORE. STATE HWY. RIGHT OF WAY MONUMENT
- HWY. CENTER LINE
- M.L. MORE OR LESS

CURVE DATA

WEST RIGHT OF WAY LINE, AS SHOWN ON MAP  
RADIUS = 3467.91'

ARC	DELTA	ARC LENGTH	CHORD LENGTH	CHORD BEARING
"A"	2° 10' 52"	132.00	131.98	S 33° 26' 59" E
"B"	2° 12' 36"	133.78	133.76	S 31° 15' 15" E

REFERENCE MATERIAL  
MAP OF SURVEY NO. 209

NOTE: THIS SURVEY MADE AT THE REQUEST OF  
MR. BOETHIN & MR. GLOVER, TO REVISE  
ORIGINAL PROPERTY LINES AS SHOWN  
ON MAP OF SURVEY NO. 209, TO  
BETTER FIT EXISTING IMPROVEMENTS

RECEIVED AND  
FILED  
JUN 7 1971  
John M. Ferguson  
Surveyor, Grant County, Oregon

REGISTERED  
OREGON  
SURVEYOR  
JULY 12, 1968  
DOUGLAS M. FERGUSON  
848

BAGETT-GRIFFITH-FERGUSON

John Day, Oregon  
MAP OF SURVEY

PARCELS SITUATED IN THE WEST 1/2 OF  
THE SE 1/4 SECTION 26 T13S R31E W.M.  
CITY OF JOHN DAY  
GRANT COUNTY OREGON

SURVEYED FOR	R.L. BOETHIN & H.E. GLOVER
SURVEYED BY	D M F & R D B June 1971
Scale: 1" = 50'	Drawn by: D M F June 1971

Survey # 230

BASIS OF BEARINGS  
BY SOLAR OBSERVATIONS

Point of Beginning  
South 2498.29, East 346.29  
from Center North 1/16 Sec. Cor.  
Sec. 26, T13S, R31E

Approx. Center  
South 1/16 Corner  
S. 26, T13S, R31E

Point of Beginning South 2722.82 East 528.17  
from Center North 1/16 Sec. Cor. Sec. 26, T13S, R31E

P.C. Sta. 70+24.20

P.T.