

Fd Jackhammer bit set beneath 3" of asphalt paving in millyard. This has long been accepted as the sec. cor. and is referred to in Survey No. 74 & 76. from which NEW ACCESSORIES.

The location nail in a location Tag placed on the roof support post at the NW cor. of the greenchain, bears S15°E, 72 ft.

The location nail in a location Tag placed on the next roof support post East, bears N87°E, 150 ft.

At N1/16
SET G.C.S. BRASS CAP
Scribed NEW BTs
A 6" p. pine bears N7°W, 116 ft. mkd N1/16 S29CS BT.
A 13" p. pine bears S1°E, 0.8 ft. mkd N1/16 S28CS BT.

At S-N 1/64 Cor.
SET G.C.S. BRASS CAP
Scribed NEW BTs
A 11" p. pine bears N85°E, 351 ft. mkd SN1/64 S28CS BT.
A 8" p. pine bears N31°W, 406 ft. mkd SN1/64 S29CS BT.

Fd Original 1/4 Cor Stone and 2 BT stumps
SET G.C.S. BRASS CAP
Scribed NEW BTs
A 16" p. pine bears N53°E, 836 ft. mkd 1/4 S 28CS BT.
A 12" p. pine bears N57°W 87.8 ft. mkd 1/4 S29CS BT.

At S1/16 Cor.
SET G.C.S. BRASS CAP
Scribed NEW BTs
A 16" p. pine bears N54°E, 167 ft. mkd S1/16 S28CS BT.
A 20" lodgepole pine bears S44°E, 78.7 ft. mkd S1/16 S28CS BT.

Fd mound of stone commonly accepted as sec. cor. of record dist. West of Creek and record dist. North of road.
SET G.C.S. BRASS CAP
Scribed NEW BTs
A 40" p. pine bears S56°E 193.5 ft. mkd T11S R35E S33CS BT.
A 10" lodgepole pine bears S4°W, 460.0 ft. mkd T11S R35E S32CS BT.

TOWN OF
(S89°47'W 2634.72')
S89°52'58"W 2638.39

(S89°47'W 2640)
S89°52'24"W 2639.60

At NE Cor. of Sec.
Fd G.C.S. BRASS CAP
remonumented in 1968.

At N1/4 cor.
Fd 1 3/4" iron pipe as called
for in Survey No. 74 & 76.

At CNI/16
SET G.C.S. BRASS CAP
Scribed NEW BTs
A 18" p. pine bears N88°E, 533 ft. mkd CNI/16 S28CS BT.
A 19" p. pine bears S14°W, 216 ft. mkd CNI/16 S28CS BT.

At C-S-N 1/64 Cor.
SET G.C.S. BRASS CAP
Surround monument with mound of stone

At C1/4 Cor.
SET G.C.S. BRASS CAP
Scribed NEW BTs
A 16" p. pine bears N41°E, 50.4 ft. mkd, C1/4 S28CS BT.
A 15" p. pine bears N57°W, 287 ft. mkd, C1/4 S28CS BT.

At CS1/16
SET G.C.S. BRASS CAP
Scribed NEW BTs
A 12" p. pine bears S10°W 39.6 ft. mkd CS1/16 S28CS BT.
A 12" p. pine bears N46°W, 11.7 ft. mkd CS1/16 S28CS BT.

No Cor. evidence found
SET G.C.S. BRASS CAP AT PROPORTIONATE DISTANCE
Scribed NEW BTs
A 12" p. pine bears N52°06'E, 264.9 ft. mkd 1/4 S28CS BT.
A 36" p. pine bears S3°13'E, 227.1 ft. mkd 1/4 S33CS BT.

At S1/16
SET G.C.S. BRASS CAP
Scribed NEW BTs
A 8" p. pine bears N76°E, 109 ft. mkd S1/16 S27CS BT.
A 8" p. pine bears N11°W 245 ft. mkd S1/16 S28CS BT.
An unrecorded 1 3/4" iron pipe bears S4°45'27"E, 41.99 ft.

Fd original Corner & 1 3/4" iron pipe set by S. Wallulis in Survey No. 74.
SET G.C.S. BRASS CAP AT CORNER
Scribed NEW BTs
A 10" Larch bears N66°E, 42.7 ft. mkd T11S R35E S27CS BT.
A 26" Larch bears S9°E, 49.4 ft. mkd T11S R35E S34CS BT.
A 8" Larch bears S34°W, 45.2 ft. mkd S33CS BT.
A 8" lodgepole pine bears N21°W, 422 ft. mkd T11S R35E S28CS BT.

BASIS OF BEARINGS
Solar Observation near N.W. Cor. Sec. 28

- LEGEND**
- Found original corner or acceptable evidence
SET GRANT COUNTY SURVEYOR BRASS CAPPED IRON PIPE
 - SET GRANT COUNTY SURVEYOR BRASS CAPPED IRON PIPE
 - Found Monument of Record
 - Found Unrecorded Monument
 - () Record Bearing and Distance
 - x- Fence Line
 - P- Power Transmission Line
 - Buildings

CERTIFICATION

I, Robert D. Baggett, a registered professional land surveyor in the State of Oregon, hereby certify that this plat and the notes hereon, or attached, are a correct representation of a survey I performed during July and August 1973, for the U.S. Forest Service, in accordance with the statutes of the State of Oregon and with the Articles of my contract.

Robert D. Baggett
GRANT COUNTY SURVEYOR

Robert D. Baggett
REGISTERED PROFESSIONAL LAND SURVEYOR
OREGON
JULY 18, 1968
ROBERT D. BAGGETT
598

NOTE:
SEE CERTIFIED RECORD OF LAND CORNER MONUMENTATION SHEETS RECORDED WITH THIS PLAT FOR A DESCRIPTION OF EACH MONUMENT SET AND BEARING TREES TAKEN.

RECEIVED AND
FILED
OCT 9 1973
JOHN LIVEIRA, County Clerk
Deputy

BAGGETT-GRIFFITH-FERGUSON			
John Day, Oregon			
Map of Survey			
CADASTRAL SURVEY AND SUBDIVISION OF			
SECTION 28, T11S R35E, W. M.			
GRANT COUNTY, OREGON			
SURVEYED FOR	MALHEUR NATIONAL FOREST		
SURVEYED BY	R.D.B.	Aug, 1973	
Scale: 1"=300'	Drawn by: R.D.B. C.R.M.	Aug, 1973	