



BASIS OF BEARING

SOLAR OBSERVATIONS AT THE CENTER OF SECTION 5
 LATITUDE 44° 02' 20"
 MEAN VERTICAL ANGLE 27° 52' 30"
 MEAN SUN DECLINATION 17° 48' 28.8"
 MEAN HORIZONTAL ANGLE 220° 24' 07"
 MEAN MAGNETIC DECLINATION 17° EAST

DESCRIPTION OF FOREST SERVICE LANDS

SECTION 5	T18S R31E WM SECTION 18	SECTION 20
NW 1/4	N 1/2	S 1/2
N 1/2 of the SW 1/4	SW 1/4	NE 1/4
	N 1/2 of the SE 1/4	S 1/2 of the NW 1/4
	SW 1/4 of the SE 1/4	NE 1/4 of the NW 1/4
SECTION 7		
Entire Section		

SURVEYOR'S STATEMENT

I, DUANE I. GRIFFITH, REGISTERED LAND SURVEYOR IN THE STATE OF OREGON, HEREBY CERTIFY THAT THIS PLAT AND THE NOTES HEREON OR ATTACHED ARE A CORRECT REPRESENTATION OF THE SURVEY I MADE DURING AUGUST 1979 FOR THE U.S. FOREST SERVICE IN ACCORDANCE WITH THE STATUTES OF THE STATE OF OREGON AND THE ARTICLES OF MY CONTRACT.

Duane I. Griffith
 PLS 644



REFERENCE MATERIAL

G.L.O. FIELD NOTES
 GRANT COUNTY SURVEY RECORDS

LEGEND

- FOUND MONUMENT OF RECORD
(See remonumentation sheets by Sherman Anderson, 1978)
- SEARCHED FOR DID NOT FIND ORIGINAL CORNER, SET 2 1/2" X 30" IRON PIPE WITH BRASS CAP AT PROPORTIONATE DISTANCE
- ⊙ FOUND G.L.O. CORNER EVIDENCE SET 2 1/2" X 30" IRON PIPE WITH BRASS CAP
- SET 2 1/2" X 30" IRON PIPE WITH BRASS CAP
- () G.L.O. RECORD BEARING AND DISTANCE
- NATIONAL FOREST SERVICE BOUNDARY
- P PRIVATELY OWNED LANDS
- 267.321m METRIC DISTANCE

NOTE

FOR MONUMENTATION RECORDS OF CORNERS FOUND AND SET, SEE MONUMENTATION SHEETS FILED SEPARATELY.

BAGETT, GRIFFITH & ASSOCIATES
 John Day, Oregon
 Map of Survey
 ESTABLISH FOREST BOUNDARY
 in
 SECTIONS 5-6-7-8-17-18-19-20
 T18S R31E WM
 GRANT COUNTY, OREGON
 SURVEYED FOR MALHEUR NATIONAL FOREST
 SURVEYED BY DIG 8/79
 Scale: 1"=600' Drawn by TDG 9/79