

NARRATIVE: This survey was performed at the request of Bob Kimberling to locate the South line of Section 33 and 34, T. 12 S., R. 34 E.,

A search was made of available records pertaining to this survey.

I commenced at the Southwest corner of Section 33 and retraced the Township line to the East for two miles. I found the South I/4 corner of Section 33 and the Southeast corner of Section 34. I did not find any evidence of the South I/4 corner of Section 34 or the Southeast corner of Section 33. After a diligent search for these corners, I established them on the Township line at single proportionate measure between the found corners at the South I/4 corner of Section 33 and the Southeast corner of Section 34. I then established the East I/16 and West I/16 corners common to Section 34 and Section 3 at single proportionate measure as shown on this map.

See recorded Corner Remonumentation sheets for details of Section and I/4 Section corners found and set and Bearing Trees taken; of I/16 Section corners set and Bearing Trees taken.

REGISTERED PROFESSIONAL LAND SURVEYOR

OREGON
JULY 12, 1963
ROBERT D. BAGETT
598

RECEIVED AND

JUL 171980

OFFICE OF COUNTY SURVEYOR

AMach Ammy County County

BAGETT, GRIFFITH & ASSOCIATES

John Day, Oregon

Map of Survey

Set 5/8"x 30" iron pin with attached plastic cap mkd. B-G-A Survey Marker

Record bearing and distance Vernon Glaze Survey of 1913

Set Grant County Surveyor brass cap

Found brass cap monument of record

Record bearing and distance G.L.O.

THE SOUTH LINE OF SECTION 33
AND SECTION 34, T.12 S., R.34E., W. M.

GRANT COUNTY, OREGON

 SURVEYED FOR
 BOB KIMBERLING

 SURVEYED BY
 R.D.B. & G.L.E. 6/23-6/25/80

 Scale: I"= 500'
 Drawn by: G.L.E. 6/26/80