



LEGEND

- Found original G.L.O. corner, set 1" x 30" iron pipe, with brass cap.
- Found original G.L.O. corner, set 5/8" x 30" iron pin with plastic cap, marked B G A SURVEY MARKER.
- Set 1" x 30" iron pipe, with brass cap, on section line.
- () Record bearing and distance.

NOTE:
See remonumentation sheets, filed separately.

BASIS OF BEARING

Solar observations at the S.W. corner of section 14.

NARRATIVE

This survey was made for Crown Zellerbach Corporation in Aug. of 1981 to establish and mark the exterior lines of section 23, T 14 S, R 34 E, W.M. The original subdivision of the Township was made by S.W. Lackland in 1880 and was discontinued on the south line of sections 13, 14, 15, 16, 17, and 18. In 1901 the subdivision of the Township was completed by Homer D. Angell, who closed on Lackland's line. I retraced the south line of section 14 and found corners as shown. I placed the closing corner at the N.W. corner of said section 23, and the N 1/4 corner of said section 23 on the retraced south line of section 14. I did not retrace the south line of section 13. I remonumented the closing corner at the N.E. corner of section 23 in the position found, which may not be on the south line of section 13. I found no unusual conditions.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

John I. Griffith

OREGON
JULY 10, 1964
DUANE I. GRIFFITH
644

REFERENCE MATERIAL

General Land Office Survey Notes
Volume 211
Volume 445

RECEIVED AND
FILED

SEP 1 1981

OFFICE OF COUNTY SURVEYOR

Robert R. Sargent
Niles
Co. Clerk

BAGETT - GRIFFITH & ASSOCIATES John Day, Oregon		
MAP OF SURVEY Section 23 T 14 S, R 34 E, W.M. GRANT COUNTY, OREGON		
SURVEYED FOR	CROWN ZELLERBACH CORP.	
SURVEYED BY	d.i.g. - g.t.b. - r.g.r.	8/81
Scale: 1" = 500'	Drawn by: d.i.g.	8/81