

FieldNotes

Survey #70

August 16, 17, 22, & 23rd

Clear - Hot

Firm: Wall & Terrieson --- Consulting EngineersSubject: Survey of two springs, one in section 23 & another in section 26 for City of Prairie City, Oregon. Springs are in Twn 12 S, R. 33 EWM Grant County, Oregon.Chief of Party: Stanley G. WallulisChainman: Donald Branton

We made a search through county files and couldn't find any surveys in section 23 or 26 since the original land subdivision. We went in the field and found a fence intersection that met ~~we~~ with references obtained from original land subdivision field notes. We accepted this corner as the NE corner of section 26. We established line to the west by following a fence line to the approximate location of the NW cor of section 26. We then set an iron pipe on the west side of said fence intersection for the NE cor of section 26. We then went west along said North line of section 26 a distance of 1708.17 and set a nail on the East side of Dixie Creek Road. From this point we ran traverses for both springs as follows:

Upper Spring, Sec 23

<u>Actual Traverse</u>	<u>to</u>	<u>Adjusted Traverse</u>
West --- 26.04 ft - Set nail		West --- 26.04 ft
N 3°46'30"E --- 1092.74 ft - Set hub		N 3°46'27"E --- 1092.75 ft
S 87°16'E --- 275.26 ft - Set Iron Pipe		S 87°16'04"E --- 275.24 ft
N S 87°19'30"W --- 142.14 ft - Set Iron Pipe		S 87°19'48"W --- 142.10 ft
N 78°30'30"W --- 136.30 ft - back on hub		N 78°30'22"W --- 136.26 ft
S 2°24'30"W --- 1091.33 ft - Point of Beg		S 2°24'35"W --- 1091.33 ft

Survey #70 See attached map for spring site details