

Corner Monumentation in
Section 8, T. 16S. R. 30 E. W.M.
Grant County, Oregon
96 Cadastral Survey

- ① Fd: No evidence of original post.
Ref: 17" burnt B.T. S 46°W 42lks (S 40°W 42lks)
scribed "CC"
15" snag S 78°E 31lks (S 85°E 31lks)
scribed "CC" "BT"
Set: AP 26" in ground. Comp. decl. 18° East
Ref: 15" PPBT. S 26 1/2°W 57.6ft.
13" PPBT. S 24°E 12.4ft.
- ② Fd: 12"x12"x5" stone with 5 notches south in a mos.
Set: AP 24" in ground in mos. Buried original stone
alongside new monument. Comp. decl. 18° East
Ref: 7" PPBT. N 02°W 36.3ft.
7" DFBT. N 56°E 39.5ft.
7" PPBT. S 76 1/2°W 9.3ft.
9" DFBT. S 32°E 29.5ft.
- ③ Fd: No evidence of original corner. Corner position
established by double proportionate measure-
ment. No monument set.
- ④ Fd: No evidence of original corner.
Set: By single proportionate measurement, an AP 20"
in ground to bedrock. Comp. decl. 18° East.
Ref: 9" Fir B.T. S 63°W 12.6ft.
6" Fir B.T. N 84°E 39.7ft.
- ⑤ Fd: No evidence of original corner. Corner position
established by double proportionate measure-
ment during survey of section 17, T. 16S. R. 30E. W.M.
No monument set.
- ⑥ Fd: 3 1/4" aluminum cap, R.L.S. 1664, 1981. Comp. decl. 18° East.
Ref: 11" PPBT. S 57°W 60.6ft.
13" PPBT. N 67 1/2°E 29.7ft.
- ⑦ Set: AP 24" in ground. Comp. decl. 18° East.
Ref: 10" PPBT. N 27°E 71.6ft.
10" PPBT. S 03°E 16.4ft.
- ⑧ Fd: No evidence of original post.
Ref: 20" PP snag with badly burnt and weathered face.
Top of "B" and bottom of "T" are visible in lower
blaze. S 42°E 3lks (S 20°E 3lks)
14" PP dead and down N 05°W 12lks (N 03°E 12lks)
No visible scribing in badly burnt face.
Set: AP 22" in ground in mos. Comp. decl. 18° East
Ref: 13" PPBT. S 00 1/2°W 11.7ft.
9" PPBT. N 79°E 30.5ft.

- ⑨ Fd: No evidence of original post.
Ref: 36" PP stump N 50°E 55lks. Scribed "BT"
(N 50°E 55lks)
36" PP stump hole with stump alongside. Open face
with scribing weathered S 19°E 61lks (S 62°E 58lks)
42" PP snag S 44°W 115lks (S 48°W 99lks) Face burnt,
no visible scribing.
No evidence of NW BT.
Set: AP 24" in ground in mos. Comp. decl. 18 3/4° East
Ref: 10" PPBT. N 18°W 32.1ft.
10" PPBT. N 64°E 32.2ft.
7" PPBT. S 27°W 24.0ft.
9" PPBT. S 36°E 12.9ft.
- ⑩ Fd: No evidence of original corner.
Set: By single proportionate measurement, an AP 26"
in ground. Comp. decl. 18° East.
Ref: 11" PPBT. N 29°W 12.4ft.
12" PPBT. S 24°E 24.9ft.
- ⑪ Fd: 3 1/4" AP, R.L.S. 1664, 1981. Comp. decl. 19° East.
Ref: 14" PPBT. S 54°W 49.4ft.
11" PPBT. N 68 1/2°E 100.0ft.
12" PPBT. S 06°E 65.4ft.
39" PPBT. N 07°W 24lks
33" PP stump S 38°W 17lks
28" PP stump N 78°E 67lks

Note

Bearings based on solar observation.
All corners have a steel fence post, with appropriate
signs, 3 ft. to 5 ft. from monument.
All bearing trees marked as per BLM Manual of Instruc-
tions, 1973, with the addition of:
a) a red band painted breast high.
b) a brass tag, stamped R.L.S. 1664, in lower blaze.
Monuments marked as per BLM Manual of Instructions,
1973, except:
a) all monuments are stamped R.L.S. 1664.
All original stones found were buried upsidedown and
alongside new monument.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Carl E. Sundet
OREGON
JULY 14, 1978
CARL E. SUNDET
1664

Surveyed for: U.S. Forest Service
Contract No. 53-04H1-0-8252N

Surveyed by: Sundet and Associates
27 South "L" Street
Lakeview, Oregon
Ph.No. 503-947-3293

Date : 1980-1981
Drawing No. 174A

Sheet 2 of 2