

Corner Monumentation in
Section 17, T.16 S. R.30 E. W.M.
Grant County, Oregon
96 Cadastral Survey

- ① Fd: No evidence of original post.
Ref: 23"PPBT. S 10°E 65lks(S 10°E 65lks) Scribing
visible "S" "B".
No evidence of NE BT.
Set: AP 25" in ground in m.o.s. Comp.decl. 18° East.
Ref: 7"PPBT. N 79°W 15.9ft.
9"FirBT. S 29°E 18.5ft.
- ② Fd: No evidence of original post.
Ref: 17"BT. S 46°W 42lks (S 40°W 42lks) Burntface with
visible scribing "CC".
15"snag S 78°E 31lks (S 85°E 31lks) Scribing
visible "CC" "BT".
Set: AP 26" in ground. Comp.decl. 18° East.
Ref: 15"PPBT. S 26 1/2°W 57.6ft.
13"PPBT. S 24°E 12.4ft.
- ③ Fd: No evidence of original corner. Corner position
established by double proportionate measurement.
No monument set.
- ④ Fd: No evidence of original corner.
Set: By single proportionate measurement, an AP 24"
in ground. Comp. decl. 18° East.
Ref: 11"PPBT. S 57°W 60.6ft.
13"PPBT. N 67 1/2°E 29.7ft.
- ⑤ Fd: No evidence of original post.
Ref: 39"PPBT. N 07°W 24lks (N 10°W 24lks) Healed face
33"PP stump S 38°W 17lks (S 28°W 16lks) Burnt face
28"PP stump N 78°E 67lks
Set: AP 26" in ground. Comp. decl. 19° East.
Ref: 11"PPBT. N 68 1/2°E 100.0ft.
14"PPBT. S 54°W 49.4ft.
12"PPBT. S 06°E 65.4ft.
- ⑥ Fd: AP, R.L.S. 1664, 1981. Comp.decl. 19° East.
Ref: 9"FirBT. N 38°W 14.2ft.
8"FirBT. S 45 1/2°E 14.5ft.
30"PP stump N 30°W 35lks
- ⑦ Set: AP 24" in ground in m.o.s. Comp.decl. 19° East.
Ref: 6"PPBT. N 82°W 50.9ft.
6"PPBT. S 03 1/2°E 15.5ft.
- ⑧ Fd: No evidence of original corner.
Set: By single proportionate measurement, an AP 26"
in ground. Comp.decl. 18° East.
Ref: 10"PPBT. N 10°E 150.4ft.
16"PPBT. S 19 1/2°W 139.6ft.

- ⑨ Fd: No evidence of original corner. Corner position
established by double proportionate measurement
during survey of section 19, T.16 S. R. 30 E. W.M. No
monument set.
- ⑩ Fd: AP, R.L.S. 1664, 1981. Comp.decl. 18° East.
Ref: 13"DFBT. S 62°W 65.9ft.
8"DFBT. N 66°E 49.0ft.
- ⑪ Fd: AP, R.L.S. 1664, 1981. Comp.decl. 19° East.
Ref: 8"PPBT. N 52°W 38.8ft.
13"PPBT. N 64°E 29.8ft.
7"PPBT. S 77°W 15.7ft.
9"PPBT. S 49°E 32.2ft.
36"PP stump S 60°E 77lks

Note

Bearing based on solar observation.
All corners have a steel fence post, with appropriate
signs, 3' to 5' from monument.
All bearing trees and monuments are marked as per
BLM Manual of Instructions, 1973, except BT's also have
a red band painted breast high and a brass tag, stamped
R.L.S. 1664, in lower blaze and monuments are stamped
R.L.S. 1664.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Carl E. Sundet
OREGON
JULY 14, 1978
CARL E. SUNDET
1664

Surveyed for: U.S. Forest Service
Contract No. 53-04H1-0-8252N
Surveyed by: Sundet and Associates
PO. Box 1228
Lakeview, Oregon
Ph.No. 503-947-3293
Date : 1980-1981
Drawing No. 175A

Sheet 2 of 2