

Corner Monumentation in
Section 19, T. 16 S. R. 30 E. W.M.
Grant County, Oregon
96 Cadastral Survey

① Fd: Remains of scribed post
Ref: PP stump N 60°W 86 lks, scribing visible,
(N 60°W - 86 lks)
37" DFBT snag S 44°W 14.3 ft., healed face,
(24" Pine S 70°W 15 lks)
10" PPBT stump with log laying alongside,
N 60°E 26.4 ft., scribing visible,
(N 60°E 40 lks)
No evidence of aspen B.T.
Set: AP 24" in ground. Comp. decl. 19° East
Ref: 9" LPBT. N 27°W 24.9 ft.
26" PPBT. N 77 1/2°E 30.4 ft.
8" LPBT. S 07°E 42.0 ft.
8" LPBT. S 74°W 39.4 ft.

② Fd: 3 1/4" aluminum cap, O.R.L.S. 1805, 1979.
Ref: 30" PPBT. N 86°E 81 lks (N 88°E 80 lks)
21" PPBT. S 89°E 87 lks (S 87°E 86 lks)
23" PPBT. North 80 lks

③ Fd: 3 1/4" aluminum cap, O.R.L.S. 1805, 1979.
Ref: 11" PPBT. N 24°E 51 1/2 lks
12" PPBT. N 36°W 51 lks
PP stump N 86°E 26 lks (N 85°E 24 lks)
16" PPBT. S 38°E 75 1/2 lks (S 70°E 75 lks)
32" PPBT. S 74°W 14 lks (S 85°W 12 lks)
28" PP snag N 20°W 47 lks (N 15°W 45 lks)

④ Fd: No evidence of original post.
Ref: 59" PPBT. stump, N 72°E 62 lks, scribing
visible, (N 72°E 62 lks)
Set: AP 24" in ground. Comp. decl. 19° East.
Ref: 10" PPBT. S 73°W 25.4 ft.
7" JunBT. S 25°E 38.3 ft.

⑤ Fd: No original evidence.
Set: AP 26" in ground. Comp. decl. 19° East
Ref: 14" PPBT. S 50°W 12.1 ft.
14" PPBT. N 87°E 27.8 ft.

⑥ Set: AP 6" below surface of road no. 24
Ref: 17" PPBT. N 34 1/2°W 205.9 ft.
9" LPBT. S 03°E 96.4 ft.
By single proportionate measurement.

⑦ Set: AP 26" in ground in m.o.s. Comp. decl. 19° East.
Ref: 22" PPBT. N 13°W 194.0 ft.
19" PPBT. N 73°E 163.7 ft.
By single proportionate measurement.

⑧ Set: By single proportionate measurement, an AP 18"
in ground in m.o.s. Comp. decl. 18° East.
Ref: 18" PPBT. N 16 1/2°W 112.9 ft.
7" PPBT. S 52°W 14.4 ft.

⑨ Fd: 14"x8"x6" stone, in m.o.s., with 3 notches north
and 3 notches south.
Set: AP 23" in ground in m.o.s. Buried original stone
alongside. Comp. decl. 18° East.
Ref: 10" Double Jun. N 45°W 127.8 lks.
17" PPBT. N 24°E 128.1 lks.
14" PPBT. S 53°E 270.8 lks.
16" PPBT. S 06°W 361.1 lks.

⑩ Fd: No evidence of original corner.
Set: By single proportionate measurement, an AP 10"
in ground in large mound of stone. Comp. decl.
18° East.
Ref: 15" PPBT. N 10 1/2°W 87.0 ft.
14" PPBT. S 07°E 90.6 ft.

⑪ Fd: No evidence of original corner. Corner position
established by double proportionate measure-
ment. No monument set.

⑫ Fd: No evidence of original post.
Ref: 30" PP stump N 30°W 35 lks. Scribed "BT".
No evidence of NE BT.
Set: AP 28" in ground in m.o.s. Comp. decl. 19° East.
Ref: 9" Fir BT. N 38°W 14.2 ft.
8" Fir BT. S 45 1/2°E 14.5 ft.

⑬ Fd: No evidence of original corner.
Set: By single proportionate measurement, an AP 22"
in ground in m.o.s. Comp. decl. 18° East.
Ref: 8" DFBT. N 66°E 49.0 ft.
13" DFBT. S 62°W 65.9 ft.

⑭ Fd: No evidence of original post.
Ref: 36" PP stump S 60°E 77 lks. Stump has burnt face
with scribing visible, but not readable.
12" burnt log with BT face. Scribing burnt off.
Cannot tell where log came from.
Set: AP 26" in ground in m.o.s. Comp. decl. 19° East.
Ref: 8" PPBT. N 52°W 38.8 ft.
13" PPBT. N 64°E 29.8 ft.
7" PPBT. S 77°W 15.7 ft.
9" PPBT. S 49°E 32.2 ft.

Note

Bearings based on solar observation.
All corners have a steel fence post, with
appropriate signs, 3 ft. to 5 ft. from monument.
All bearing trees marked as per BLM Manual
of Instructions, 1973, with the addition of:
a) a red band painted at breast height.
b) a brass tag, stamped R.L.S. 1664, in lower
blaze.

Monuments marked as per BLM Manual of
Instructions, 1973, except:
a) 1/16 corners have township and range
stamped on monument.
b) all monuments are stamped R.L.S. 1664.
All original stones found were buried up-
side down and alongside new monument.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Carl E. Sundet
OREGON
JULY 14, 1978
CARL E. SUNDET
1664

Surveyed for: U.S. Forest Service
Contract No. 53-04H1-O-8252N

Surveyed by: Sundet and Associates
27 South "L" Street
Lakeview, Oregon
Ph.No. 503-947-3293

Date: 1980-1981

Drawing no. 159A

Sheet 2 of 2

749
MAP OF Survey No. 702