

Corner Monumentation in
Section 20, T. 16 S. R. 30 E. W.M.
Grant County, Oregon
96 Cadastral Survey

① Fd: 3 1/4" aluminum cap, O.R.L.S. 1805, 1979.
Ref: 23" PPBT. N 27°W 236.8 ft.
16" PPBT. N 41°E 233.4 ft.
40" PPBT. stump S 20°E 83.8 ft.

② Set: AP 26" in ground. Comp. decl. 19° East.
Ref: 13" PPBT. N 41°W 138.8 ft.
14" PPBT. N 68°E 315.0 ft.

③ Fd: 3 1/4" aluminum cap, O.R.L.S. 1805, 1979.
Ref: 11" PPBT. N 24°E 51 1/2 lks.
12" PPBT. N 36°W 51 lks.
PP stump N 86°E 26 lks.
16" PPBT. S 38°E 75 1/2 lks.
32" PPBT. S 74°W 14 lks.
28" PP snag N 20°W 47 lks.

④ Fd: 3 1/4" aluminum cap, R.L.S. 1664, 1980.
Ref: 10" PPBT. S 73°W 25.4 ft.
7" JunBT. S 25°E 38.3 ft.
59" PPBT. stump N 72°E 62 lks.

⑤ Fd: No evidence of original post.
Set: AP 26" in ground. Comp. decl. 19° East.
Ref: 13" PPBT. N 30°W 37.2 ft.
18" PPBT. S 29°W 170.6 ft.

⑥ Fd: Remains of scribed post in small m.o.s.
Ref: 22" PPBT. N 11°E 45.8 ft. (N 12°E 55 lks)
8" burnt stump N 20°W 30.7 ft.
(N 20°W - 45 lks)
19" PP snag S 40°W - 29.0 ft. (S 40°W - 44 lks)
PP snag S 28 1/2°E - 21.4 ft. (S 08°E - 29 lks)
Set: AP 24" in ground in m.o.s. Comp. decl. 19° East.
Ref: 13" PPBT. S 14°W - 45.3 ft.
13" PPBT. S 88°E - 7.5 ft.
8" PPBT. N 22°W - 64.5 ft.

⑦ Fd: 3 1/4" aluminum cap, R.L.S. 1664, 1980.
Ref: 22" PPBT. N 13°W - 194.0 ft.
19" PPBT. N 73°E - 163.7 ft.

⑧ Fd: No evidence of original corner. Corner position established by double proportionate measurement during survey of section 19, T. 16 S. R. 30 E., W.M. No monument set.

⑨ Fd: 3 1/4" AP, R.L.S. 1664, 1981. Comp. decl. 18° East.
Ref: 8" DFBT. N 66°E 49.0 ft.
13" DFBT. S 62°W 65.9 ft.

⑩ Set: AP 22" in ground in m.o.s. Comp. decl. 18° East.
Ref: 10" PPBT. N 02°W 20.7 ft.
11" PPBT. S 74°E 24.6 ft.

⑪ Fd: 3 1/4" AP, R.L.S. 1664, 1981. Comp. decl. 19° East.
Ref: 8" PPBT. N 52°W 38.8 ft.
13" PPBT. N 64°E 29.8 ft.
9" PPBT. S 49°E 32.2 ft.
7" PPBT. S 77°W 15.7 ft.

Note

Bearings based on solar observation.

All corners have a steel fence post, with appropriate signs, 3 ft. to 5 ft. from monument.

All bearing trees marked as per BLM Manual of Instructions, 1973, with the addition of:

a) a red band painted breast high.

b) a brass tag, stamped R.L.S. 1664, in lower blaze.

Monuments marked as per BLM Manual of Instructions, 1973, except:

a) 1/16 corners have township and range stamped on monument.

b) all monuments are stamped R.L.S. 1664.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Carl E. Sundet

OREGON
JULY 14, 1978
CARL E. SUNDET
1664

Surveyed for: U.S. Forest Service
Contract No. 53-04H1-0-8252N

Surveyed by: Sundet and Associates
27 South "L" Street
Lakeview, Oregon
Ph.No. 503-947-3293

Date : 1980-1981
Drawing No. 160A

Sheet 2 of 2

MAR 05 1981

9 of 9