

CONSULTING  
*Engineers* — TENNESON ENGINEERING CORPORATION

PHONE CYPRESS 6-9177

412 WEST SECOND PLACE

THE DALLES, ORE. 97058

December 30, 1964

## FIELD NOTES

For Henry Bernard, Work Order #3311, Survey in Section 17 and 20, Township 17 South, Range 26 East, Willamette Meridian, Grant County, Oregon.

CREW: Robert Chisholm, Party Chief  
Bruce Joseph, Chainmen  
Stacy Whitehouse

We began the survey by searching for the Northeast Corner of Section 20. We found nothing but a fence corner, so we used it as a starting point for our random line running West.

At 22+78.96 we offset at Right Angles North 69.4 feet, at 5100.9 feet and 56.72 feet North we found a 30" x 24" x 14" stone, the size of which agrees with the monument as described in the original Government Field Notes, which we accepted as the true corner. The Government Field Notes gave the distance of 80.24 chains or 5295.84 feet along the North line of Section 20. As our distance on the random line was 5101 feet, we were 194.8 feet short. Returning to our starting point, we chained East 141 feet and found a 20" x 18" x 10" stone, which agrees with the original monument in the East-West Fence, which we accepted as the true corner.

Beginning from this monument, we ran a true line to the stone which is the Northwest corner of Section 20, measuring a distance of 5243.68.

At 2621.84 feet on the true line we set an iron pin for the North Quarter Corner of Section 20.

At this Quarter Corner, we turned 90° off of the true section line and ran due North 1320 feet and set a point for the approximate 1/16 corner. We also set lath on line for fence building.

At the Southwest Corner of Section 20 we found a 16" x 10" x 3" stone at a fence corner. The size of this stone agrees with the original Government Field Notes and it was accepted as the true corner.

From this corner we ran a line East along the fence and set a hub at 1318.64 feet for the approximate 1/16 corner. This is the call distance of the G.L.O. Notes.

From this corner we sighted a fence corner due South, approximately 2 miles distant,