

## CORNER NOTES

Reset 21 brass cap on iron pipe and changed the date as shown.

BTs: 11" Ponderosa Pine bears S 50° W, 30.6 ft., scribed N1/16 S21 BT, with washer "PLS 1918". 12" Ponderosa Pine bears S 44° E, 6.5 ft., scribed N1/16 S22 BT,

321 + 522 PLS' 1918

Reset 24" brass cap on iron pipe and changed the date as shown.

BTs: No trees within range (300 ft.)

with washer "PLS 1918".

with washer "PLS 1918".

321 + 522 PLS' 1918

TILS R32E

Reset 23" brass cap on iron pipe at original distance and direction from found original BT, and changed the date as shown.

BTs: Stump of original BT, fragmentary scribing visible, bears N 5° E, 142.56 ft. (216 lks). 18" Ponderosa Pine bears S 83° W, 58.6 ft., scribed T16S R32E S21

521 522 528 527 PLS 1918 11" Ponderosa Pine bears N 39° E, 103.4 ft., scribed T16S R32E S22

BT, with washer "PLS 1918".

Reset 23" brass cap on iron pipe and changed date as shown.

BT, rescribed to T16S R32E S28 BT, with washer "PLS 1918".

BTs: 26" Ponderosa Pine bears N 66° E, 22.7 ft., scribed CN1/16 S22 BT, with washer "PLS 1918". 11" Ponderosa Pine bears S 78° W, 40.3 ft., scribed CN1/16 S22 BT,

11/16 \$ 522

NARRATIVE

This plat ammends and corrects the plat recorded as CS 638, as filed in the Grant County Surveyor's Office due to the discovery of an original Bearing Tree to the southwest corner of Section 22 by Mr. Robert D. Bagett, Grant County Surveyor. Work was performed for the United States Forest Service under contract No. 53-Q4H1-0-8007N, Glade Cadastral Survey.

Discovery of original evidence of the southwest corner of Section 22 required the remonumentation of that corner and the resetting of the 1/4 corner to Sections 21 and 22, the N 1/16 corner to Sections 21 and 22, and the CN 1/16 corner to Section 22. Basis of Bearings was a solar observation taken near the east 1/4 corner to Section 23, taken in 1980. Sufficient control remained from the 1980 survey to reset the required corners. The southwest corner of Section 22 was remonumented at record distance and direction from the center of the stump of the found original Bearing Tree. Postitions of the other corners were then calculated and those corners reset. Monuments from the 1980 survey were removed from the ground and reused after changing the date. Additional search was made for the 1/4 corners to Sections 21 and 22, and to Sections 27 and 28, without result. The original monument at the southwest corner of Section 22 was searched for but not found.

The plat, corner notes, and narrative of CS 638 remain valid, except as changed by

## SURVEYOR'S CERTIFICATE

I, Tyler B. Parsons, a Registered Land Surveyor in the State of Oregon, hereby certify that this plat, and the notes hereon or attached, are a correct representation of a survey I performed for the U.S. Forest Service during October 1982, in accordance with the Statutes of the State of Oregon and the articles of my contract.

RECEIVED AND

OFFICE OF COUNTY SURVEYOR

A STATE OF THE PARTY OF THE PAR	REGISTERED PROFESSIONAL LAND SURVEYOR	
ا د د	Telu B. Parson	W
	OREGON JULY 18, 1980	
	TYLER B. PARSONS	

States

**AMENDMENT** 

**REVISIONS** 

97 61 **1688 s, 0R** 757-08 MSS In P.O.Box 16: Corvallis, (503) 757 Date 16 November 1988 Scale | = 1000' Drawn TBP J-115/G-253

Sheet