

①
T14S R27E
528|527
533|334
1982
R.L.S. 934

CORNER TO SECTIONS 27, 28, 33 & 34, T14S, R27E
FND. BASALT STONE 14"x7"x6", LEANING NLY., WITH 1 NOTCH ON SOUTH AND 3 NOTCHES ON EAST EDGES, ON S. SIDE OF STONE MOUND 4 FT. DIAM.
IN PLACE OF FOUND STONE I SET A 3"x30" AL. PIPE WITH 3 1/2" AL. CAP STAMPED AS SHOWN, BURIED STONE MON. ALONGSIDE, AND BUILT A MOUND OF STONE AROUND CORNER. MY NEW ACCESSORIES ARE AS FOLLOWS:
A 8"D.B.H. JUNIPER, SCRIBED "T14S R27E S28 BT" BEARS N 54 1/2° W, 118.8 FT.
A 19"D.B.H. TRIPLE JUNIPER, SCRIBED "T14S R27E S27 BT" BEARS N 09° E, 207.8 FT.
A 19"D.B.H. JUNIPER, SCRIBED "T14S R27E S33 BT" BEARS S 18° W, 175.4 FT.
A BASALT STONE IN PLACE 19"x32"x8" HIGH, CHISELED "40" IN NW FACE, BEARS S 41 1/2° E, 62.3 FT.

②
T14S R27E
523|524
526|525
1982
R.L.S. 934

CORNER TO SECTIONS 23, 24, 25 & 26, T14S, R27E
FND. BASALT STONE 12"x7"x7" SETTING FIRMLY IN STONE MOUND, WITH 2 NOTCHES ON SOUTH AND 1 NOTCH ON EAST EDGES, FROM WHICH:
O.B.T., A 30"D.B.H. P. PINE SNAG 11 FT. TALL, LEANING SLY., SCRIBES "S2 TIR2" VISIBLE, BEARS S73° W 30.0 FT. (REC. S78° W 45 LKS. = 27.7 FT.)
O.B.T., A 22"D.B.H. DOUBLE P. PINE, BURNT FACE, BEARS N17° E 35.4 FT. (REC. N23° E 51 LKS. = 33.7 FT.)
IN PLACE OF FOUND STONE I SET A 3"x30" AL. PIPE WITH 3 1/2" AL. CAP STAMPED AS SHOWN, 20" IN GROUND, BURIED STONE ALONGSIDE, AND BUILT A MOUND OF STONE AROUND IT.
MY NEW BT'S ARE AS FOLLOWS:
A 15"D.B.H. D. FIR, SCRIBED "T14S R27E S26 BT" BEARS S72° W, 11.3 FT.
A 12"D.B.H. P. PINE, SCRIBED "T14S R27E S25 BT" BEARS S55° E, 22.4 FT.
A 9"D.B.H. P. PINE, SCRIBED "T14S R27E S23 BT" BEARS N29° W, 48.9 FT.

③
T14S R27E
526|525
535|536
1982
R.L.S. 934

CORNER TO SECTIONS 25, 26, 35 & 36, T14S, R27E
NO EVIDENCE FOUND
AT CALCULATED POSITION (BY DOUBLE PROPORTIONMENT) I SET A 3"x30" AL. PIPE WITH 3 1/2" AL. CAP STAMPED AS SHOWN, 18" IN GROUND, AND BUILT A MOUND OF STONE AROUND IT. MY NEW BT'S ARE AS FOLLOWS:
A 15"D.B.H. JUNIPER, SCRIBED "T14S R27E S26 BT" BEARS N63° W, 136.6 FT.
A 14"D.B.H. JUNIPER, SCRIBED "T14S R27E S35 BT" BEARS S59° W, 98.2 FT.
A 11"D.B.H. JUNIPER, SCRIBED "T14S R27E S36 BT" BEARS S13° E, 153.2 FT.
A 11"D.B.H. JUNIPER, SCRIBED "T14S R27E S25 BT" BEARS N45° E, 121.2 FT.

④
T14S R27E
1/2 525
1/2 536
1982
R.L.S. 934

1/4 CORNER TO SECTIONS 25 & 36, T14S, R27E
NO EVIDENCE FOUND
AT CALCULATED POSITION (BY SINGLE PROPORTIONMENT) I SET A 3"x30" AL. PIPE WITH 3 1/2" AL. CAP STAMPED AS SHOWN, 18" IN GROUND, AND BUILT A MOUND OF STONE AROUND IT.
MY NEW BT'S ARE AS FOLLOWS:
A 14"D.B.H. JUNIPER, SCRIBED "1/2 536 BT" BEARS S32° W, 135.8 FT.
A 19"D.B.H. JUNIPER, SCRIBED "1/2 525 BT" BEARS N21 1/2° E, 173.1 FT.

⑤
T14S R27E R28E
525|530
536|331
1939

SECTION CORNER TO SECTIONS 25 & 36, T14S, R27E, AND SECTIONS 30 & 31, T14S, R28E
FND. 2" PIPE WITH G.L.O. BRASS CAP STAMPED AS SHOWN, LEANING SOUTHEASTERLY. I STRAIGHTENED PIPE AND REBUILT MOUND OF STONE AROUND IT. 1939 BT'S ARE AS FOLLOWS:
A 20"D.B.H. P. PINE, GOOD SCAR, BEARS S54 1/2° W 25.5 FT. (REC. S53° W 39 LKS. = 25.7 FT.)
A 29"D.B.H. D. FIR, GOOD SCAR, BEARS N28° E 61.5 FT. (REC. N28° E 93 LKS. = 61.4 FT.)
A 14"D.B.H. W. FIR, GOOD SCAR, BEARS S35° E 26.3 FT. (REC. S36° E 40 LKS. = 26.4 FT.)
A 15" PINE WINDFALL, BADLY ROTTED, SCRIBES VISIBLE ON PARTLY HEALED FACE, BEARS N28° W 13.2 FT. PER RECORD.
MY NEW BT IS AS FOLLOWS:
A 21"D.B.H. D. FIR, SCRIBED "T14S R27E S25 BT" BEARS N75° W, 42.7 FT.

⑥
T14S R27E R28E
536|531
51|56
1939

TOWNSHIP CORNER TO TOWNSHIPS 14 & 15 SOUTH, RANGES 27 & 28 EAST
FND. 3" PIPE WITH G.L.O. BRASS CAP STAMPED AS SHOWN, IN PARTLY SCATTERED STONE MOUND.
I REBUILT THE STONE MOUND AROUND THE PIPE.
1939 BT'S ARE AS FOLLOWS:
A 20"D.B.H. JUNIPER, SCRIBES VISIBLE ON PARTLY HEALED FACE, BEARS N61 1/2° E 191.4 FT. (REC. N61 1/2° E 290 LKS. = 191.4 FT.)
A 20"D.B.H. JUNIPER, SCRIBES VISIBLE ON PARTLY HEALED FACE, BEARS S44° E 115.4 FT. (REC. S44° E 176 LKS. = 116.2 FT.)
A 11"D.B.H. JUNIPER, SCRIBES "T15S R27E S1 BT" VISIBLE, BEARS S5° W, 155.1 FT. (REC. S5° W, 235 LKS. = 155.1 FT.)
A 18"D.B.H. JUNIPER, SCRIBES VISIBLE ON PARTLY HEALED FACE, BEARS N39 1/2° W 193.8 FT. (REC. N39 1/2° W 293 LKS. = 193.4 FT.)

⑦
T14S R27E
533|534
54|53
1982
R.L.S. 934

SECTION CORNER TO SECTIONS 33 & 34, T14S R27E AND SECTIONS 3 & 4, T15S, R27E
FND. BASALT STONE 19"x10"x6" IN RING OF STONES WITH 3 NOTCHES ON EAST AND 3 NOTCHES ON WEST SIDES, AND "4" ON TOP.
IN PLACE OF FOUND STONE I SET A 3"x30" AL. PIPE WITH 3 1/2" AL. CAP STAMPED AS SHOWN, 20" IN GROUND, BURIED COR. STONE ALONGSIDE, AND BUILT A MOUND OF STONE AROUND IT. MY NEW ACCESSORIES ARE AS FOLLOWS:
A BASALT BOULDER 43"x35"x26" HIGH, CHISELED "40" ON SE. GR., 8" ABOVE GROUND, BEARS N57° W, 106.3 FT.
A BASALT BOULDER 33"x28"x10" HIGH, CHISELED "40" ON TOP, BEARS S58° W, 153.1 FT.
A BASALT BOULDER 19"x23"x9" HIGH, CHISELED "40" ON TOP, BEARS S79 1/2° E, 139.5 FT.
A BASALT BOULDER 30"x36"x12" HIGH, CHISELED "40" ON TOP, BEARS N15 1/2° E, 142.4 FT.

LEGEND

- FOUND BRASS CAP, USED FOR SURVEY CONTROL
- SET 3"x30" AL. PIPE WITH 3 1/2" AL. CAP FROM FOUND G.L.O. EVIDENCE, USED FOR SURVEY CONTROL
- SET 3"x30" AL. PIPE WITH 3 1/2" AL. CAP BY PROPORTIONMENT
- CORNER CALCULATED ONLY, NOT FOUND OR SET
- M METERS (UNLABELED DISTANCES ARE FEET)
- CH. CHAINS
- () BEARINGS AND DISTANCES IN BRACKETS ARE FROM ORIGINAL GOVERNMENT SURVEY NOTES
- NATIONAL FOREST BOUNDARY, POSTED WITH STEEL POSTS AND U.S.F.S. PROPERTY BOUNDARY SIGN 54-2
- MEAN MAGNETIC DECLINATION 16°30' EAST

①
28|27
33|34
N 89° 54' 10" W
3241.725 M.
10,635.56
(159.76 CH.)

②
23|24
26|25

1616.220 M.
5302.55
N 0° 04' 55" W
(North 80.00 CH.)

③
26|25
35|36
N 89° 37' 59" W 2656.23
(N 89° 48' W 39.90 CH.)
809.621 M.
④
25|30
36|31
N 89° 37' 59" W 2656.23
(N 89° 48' W 39.90 CH.)
809.621 M.
⑤
25|30
36|31

PRIVATE PRIVATE

1616.220 M.
5302.55
N 0° 11' 28" E
(North 80.00 CH.)

⑦
33|34
4|3
N 89° 52' 44" W
3236.422 M.
10,618.16
(S 89° 55' W 160.00 CH.)

⑥
35|36
2|1
N 89° 54' 00" W
(S 89° 55' W 80.00 CH.)
1618.211 M.
5309.08
③
36|31
1|6

NOTES:

FILED HERewith ARE U.S.F.S. FORMS R6-7100-57, "CERTIFIED RECORD OF LAND CORNER MONUMENTATION" FOR THE FOLLOWING CORNERS (DENOTED BY STANDARD INDEX FILE NUMBERS) FOR T14S, R27E: R-21, V-13, V-21, V-23, V-25, Z-13, Z-25.

THE ORIGINAL FIELD NOTES FOR THIS PLAT ARE IN TRAVERSE BOOK 7 AND IN CORNER BOOK 5 FOR ALDRICH CADASTRAL SURVEY.

1000 0 1000 2000 3000 4000 Ft.
304.801M. 0 304.801M. 609.601M. 914.402 M. 1219.202 M.

PLAT OF SURVEY

LOCATED IN
T.14S., R.27E., W.M., GRANT COUNTY, OREGON

FOR
THE UNITED STATES DEPARTMENT OF AGRICULTURE
MALHEUR NATIONAL FOREST

SURVEYED BY VICTOR M. McLIND, MILTON-FREEWATER, OR.

JULY - NOVEMBER, 1982

SCALE: 1" = 1000'

BEARINGS TRUE, BASED ON SOLAR OBSERVATION

ALDRICH CADASTRAL SURVEY

CONTRACT NO. 53-04H1-2-8968N

RECEIVED AND
FILED

JAN 18 1983

OFFICE OF COUNTY SURVEYOR

Attest: *James E. Gurnee*

CERTIFICATION:

I, Victor M. McLind, a registered Land Surveyor in the State of Oregon, hereby certify that this plat and the notes hereon, or attached, are a correct representation of a survey I performed from July to November, 1982, for the U.S. Forest Service, in accordance with the statutes of the State of Oregon and with the articles of my contract.

Victor M. McLind

Victor M. McLind
Registered Land Surveyor
Oregon License No. 934

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Victor M. McLind

OREGON
JULY 17, 1970
VICTOR M. McLIND
934