

①
T14S R27E
533 534
54 53
T15S
1982
RCS 934

CORNER TO SECTIONS 33 & 34, T14S, R27E, AND SECTIONS 3 & 4, T15S, R27E
FND. MY 3" AL. PIPE WITH 3 1/2" AL. CAP STAMPED AS SHOWN, 10" ABOVE GROUND
IN STONE MOUND, FROM WHICH:
A BASALT BOULDER 43" x 35" x 26" HIGH WITH "+ 80" CHISELED ON S.E. COR.,
BEARS N57°W, 106.3 FT.
A BASALT BOULDER 33" x 28" x 10" HIGH WITH "+ 80" CHISELED ON TOP, BEARS S58°W, 153.1 FT.
A BASALT BOULDER 19" x 23" x 9" HIGH WITH "+ 80" CHISELED ON TOP, BEARS S94°E, 139.5 FT.
A BASALT BOULDER 30" x 36" x 12" HIGH WITH "+ 80" CHISELED ON TOP, BEARS N154°E, 142.4 FT.

②
T14S R27E
534 535
53 52
T15S
1983
RCS 934

CORNER TO SECTIONS 34 & 35, T14S, R27E, AND SECTIONS 2 & 3, T15S, R27E
NO EVIDENCE OF ORIGINAL CORNER FOUND.
AT CALCULATED POSITION (BY SINGLE PROPORTIONMENT) I SET A 3"x30" AL. PIPE WITH
3 1/2" AL. CAP, STAMPED AS SHOWN, 8" ABOVE GROUND, IN MOUND OF STONE. MY NEW
ACCESSORIES ARE AS FOLLOWS:
A 16" DBH. JUNIPER IN CLUMP OF 3, SCRIBED "T14S R27E S35 BT" BEARS N194°E, 83.7 FT.
A 20" DBH. JUNIPER, SCRIBED "T15S R27E S2 BT" BEARS S154°E, 154.7 FT.
A 18" DBH. JUNIPER, SCRIBED "T15S R27E S3 BT" BEARS S12°W, 304.4 FT.
BEARING OBJECT, A BASALT ROCK OUTCROPPING 24" x 28" x 16" HIGH, CHISELED "+ 80" ON FACE
SLOPING TOWARDS CORNER, BEARS N374°W, 76.9 FT. TO +.

③
T14S R27E
535 536
52 51
T15S
1983
RCS 934

CORNER TO SECTIONS 35 & 36, T14S, R27E AND SECTIONS 1 & 2, T15S, R27E
NO EVIDENCE OF ORIGINAL CORNER FOUND.
AT CALCULATED POSITION (BY SINGLE PROPORTIONMENT) I SET A 3"x30" AL. PIPE WITH
3 1/2" AL. CAP STAMPED AS SHOWN, 6" ABOVE GROUND, AND SET STONES AROUND PIPE.
MY NEW BT'S ARE AS FOLLOWS:
A 14" DBH JUNIPER, SCRIBED "T14S R27E S35 BT" BEARS N774°W, 92.2 FT.
A 14" DBH JUNIPER, SCRIBED "T15S R27E S2 BT" BEARS S59°W, 113.7 FT.
A 22" DBH JUNIPER, SCRIBED "T14S R27E S36 BT" BEARS N27°E, 63.3 FT.
A 8" DBH JUNIPER, SCRIBED "T15S R27E S1 BT" BEARS S564°E, 30.8 FT.

④
T14S
R27E R28E
536 531
51 56
T15S
1939

TOWNSHIP CORNER TO TOWNSHIPS 14 & 15 SOUTH, RANGES 27 & 28 EAST
FND. 3" PIPE WITH G.L.O. BR. CAP STAMPED AS SHOWN, IN A LARGE STONE MOUND.
FND. 4 BT'S AS FOLLOWS:
A 20" DBH JUNIPER, SCRIBES VISIBLE ON PARTLY HEALED FACE, BEARS N614°E, 191.4 FT.
(REC. N614°E 290 LKS.)
A 20" DBH JUNIPER, SCRIBES VISIBLE ON PARTLY HEALED FACE, BEARS S44°E, 115.4 FT.
(REC. S44°E 176 LKS.)
A 11" DBH JUNIPER, SCRIBES "T15S R27E S1 BT" VISIBLE, BEARS S5°W, 155.1 FT.
(REC. S5°W 235 LKS.)
A 18" DBH JUNIPER, SCRIBES VISIBLE ON PARTLY HEALED FACE, BEARS N394°W, 193.8 FT.
(REC. N394°W 293 LKS.)

⑤
1/4
536 531
1939

1/4 CORNER TO SECTION 36, T14S R27E, AND SECTION 31, T14S R28E.
FND. 1" PIPE WITH 2 1/2" G.L.O. BR. CAP STAMPED AS SHOWN, IN STONE MOUND. POOR CONDITION.
FND. 1939 BT'S AS FOLLOWS:
A 19" DBH JUNIPER, HEALED FACE, BEARS N78°W, 164.7 FT. (REC. N78°W 249 LKS.)
A 10" DBH. JUNIPER, SCRIBES PARTLY VISIBLE ON ALMOST HEALED FACE, BEARS N214°E, 89.3 FT.
(REC. N23°E, 134 LKS.)
I REBUILT THE STONE MOUND.

T14S 33 34 589°52'19"E 1618.211 M. 34 35 589°53'09"E 1618.211 M. 35 36 589°53'47"E 809.105 M. 36 31 589°54'13"E 809.105 M.
T15S 4 3 589°55'W 80.00 CH. 3 2 589°55'W 80.00 CH. 2 1 589°55'W 40.00 CH. 1 6 589°55'W 40.00 CH.

⑥
T14S
R27E R28E
525 530
536 531
1939

SECTION CORNER TO SECTIONS 25 & 36, T14S, R27E, AND SECTIONS 30 & 31, T14S, R28E
FND. 2" PIPE WITH G.L.O. BR. CAP STAMPED AS SHOWN, IN STONE MOUND.
1939 BT'S ARE AS FOLLOWS:
A 20" DBH P. PINE, GOOD SCAR, BEARS S544°W, 25.5 FT. (REC. S53°W, 39 LKS.)
A 29" DBH D. FIR, GOOD SCAR, BEARS N28°E, 61.5 FT. (REC. N28°E, 93 LKS.)
A 14" DBH W. FIR, GOOD SCAR, BEARS S35°E, 26.3 FT. (REC. S36°E, 40 LKS.)
A 15" P. PINE WINDFALL, BADLY ROTTED, SCRIBES VISIBLE ON PARTLY HEALED FACE, BEARS N28°W, 13.2 FT.
MY 1982 BT, A 21" DBH D. FIR, SCRIBED "T14S, R27E S25 BT" BEARS N75°W, 42.7 FT.

⑦
T14S R27E
1/4 S 36
5 31
T15S
1983
RCS 934

1/4 CORNER TO SECTION 36, T14S, R27E, AND SECTION 1, T15S, R27E
NO EVIDENCE OF ORIGINAL CORNER FOUND.
AT CALCULATED POSITION (BY SINGLE PROPORTIONMENT) I SET A 3"x30" AL. PIPE WITH A 3 1/2"
AL. CAP STAMPED AS SHOWN, 12" ABOVE GROUND IN A STONE MOUND.
MY NEW BT'S ARE AS FOLLOWS:
A 11" DBH JUNIPER, SCRIBED "1/4 S 36 BT" ON DOUBLE BLAZE, BEARS N634°W, 121.5 FT.
A 13" DBH JUNIPER, SCRIBED "1/4 S 1 BT" ON DOUBLE BLAZE, BEARS S314°E, 149.9 FT.

LEGEND

- FOUND CORNER MONUMENT, USED FOR SURVEY CONTROL
- ◎ SET 3"x30" ALUMINUM PIPE WITH 3 1/2" ALUMINUM CAP BY PROPORTIONMENT
- M METERS (UNLABELED DISTANCES ARE FEET)
- CH. CHAINS
- () BEARINGS AND DISTANCES IN BRACKETS ARE FROM ORIGINAL GOVERNMENT SURVEY NOTES.
- NATIONAL FOREST BOUNDARY; POSTED WITH STEEL POSTS AND U.S.F.S. PROPERTY BOUNDARY SIGN 54-2
- MEAN MAGNETIC DECLINATION 16°30' EAST

PRIVATE

U.S.

PRIVATE

PRIVATE

U.S.

RECEIVED AND
FILED

AUG 29 1983

OFFICE OF COUNTY SURVEYOR
Robert O. Boren
Attest: Mary M. Boren

PLAT OF SURVEY

LOCATED IN
T14S., R.27E., W.M., GRANT COUNTY, OREGON
FOR
THE UNITED STATES DEPARTMENT OF AGRICULTURE
MALHEUR NATIONAL FOREST
SURVEYED BY VICTOR M. McLIND, MILTON-FREEWATER, OR.
JULY - AUGUST, 1983 SCALE: 1"=1000'
BEARINGS TRUE, BASED ON SOLAR OBSERVATION.

ALDRICH CADASTRAL SURVEY

CONTRACT NO. 53-04H1-2-8968N

I, Victor M. McLind, a registered Land Surveyor in the State of Oregon, hereby certify that this plat and the notes hereon, or attached, are a correct representation of a survey I performed during July and August, 1983, for the U.S. Forest Service, in accordance with the statutes of the State of Oregon and with the articles of my contract.

Victor M. McLind
Victor M. McLind
Registered Land Surveyor
Oregon License No. 934

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Victor M. McLind

OREGON
JULY 17, 1970
VICTOR M. McLIND
934