

REGISTERED
PROFESSIONAL
LAND SURVEYOR

David B. Armstrong

10/8/83 OREGON
AUGUST 22, 1973
DAVID B. ARMSTRONG
1026

MALHEUR NATIONAL FOREST
D.S. CADASTRAL SURVEY
CONTRACT NO. 53-04KK-3-01176
PRAIRIE CITY RANGER DISTRICT

BOUNDARY SURVEY AND SECTION SUBDIVISION OF
SECTION 9, TOWNSHIP 16 SOUTH, RANGE 33 1/2 EAST, W.M.,
GRANT COUNTY, OREGON
W.O. 83-406A

RECEIVED AND
FILED

DEC 28 1983

OFFICE OF COUNTY SURVEYOR
Robert D. Beyer
Attest: *James L. Landon*

GENERAL SURVEY NOTES

1. SURVEY FIELD NOTES ARE ON FILE IN THE OFFICE OF ARMSTRONG SURVEYING & ENGINEERING, INC., 378 EAST SECOND STREET, PRINEVILLE, OREGON - ONE BOOK.
2. BASIS OF BEARINGS - BEARINGS FOR THIS SURVEY ARE BASED ON SOLAR OBSERVATION AT SE CORNER SECTION 9 AND VERIFIED BY SOLAR OBSERVATION AT SOUTH 1/4 CORNER SECTION 9.
3. GENERAL LAND OFFICE RECORD FOR SUBDIVISION OF T. 16 S., R. 33 1/2 E., W.M. FROM OFFICIAL NOTES AND PLAT BY HENRY W. COOKE, DEPUTY SURVEYOR, PERFORMED UNDER G.L.O. CONTRACT NO. 494, DATED JANUARY 16, 1884, AND CONDUCTED DURING THAT YEAR.
4. SOUTHWEST CORNER SECTION 9 REMONUMENTED BY DOUGLAS M. FERGUSON, LS 848, ON AUGUST 3, 1982.
5. SOUTHEAST CORNER SECTION 9 REMONUMENTED BY DOUGLAS M. FERGUSON, LS 848, ON NOVEMBER 26, 1969.

SURVEY INFORMATION

SEE ACCOMPANYING 3 SHEETS OF CORNER ACCESSORY INFORMATION. SEE ALSO ACCOMPANYING CERTIFIED RECORDS OF LAND CORNER MONUMENTATION FOR ALL CORNERS SET OR MAINTAINED IN THIS SURVEY, A TOTAL OF 14. SEE ALSO ATTACHED SURVEY NARRATIVE, 2 SHEETS, FOR ADDITIONAL INFORMATION ON PROCEDURES AND/OR CONDITIONS ENCOUNTERED DURING THIS SURVEY.

COR. NO.	CAP MARKINGS	FIELD BOOK-PAGE/DECL.	EVIDENCE FOUND	CORNER ACCESSORIES
1	T16SR331/2E 1-36 1/4 & 37 S8 S9 M.V. LS 1026 20°E 1983		FND. STONE 14"X10"X8" SET 7" IN GROUND MARKED "1/4" ON WEST FACE. ORIG. SE BT ON 11" TAMARACK DEAD & DOWN, ROOT HOLE BEARS S.2°30'E, 6.6 FT.. V.S.-1/4S BT; ORIG. NW BT, A 14" TAMARACK DEAD & DOWN & DISTURBED, ROOT WAD BEARS N.62° 45'E., 21.5 FT.. V.S.-BT. NOT PREVIOUSLY ESTABLISHED.	BT'S MARKED: 7" PONDEROSA PINE, S.36°30'E., 53.0 FT., SCRIBED-1/4S9BT; 7" PONDEROSA PINE, S.50°W., 68.8 FT., SCRIBED-1/4S8BT. RAISED 2 1/2 FT. DIAM. STONE & EARTH MOUND TO CAP.
2	T16SR331/2E 1-44 S1/16 M.V. S8 S9 20°E LS 1026 1983		S-E WIRE FENCE CORNER BRS. S.55° E., 36 FT..	BT'S MARKED: 6" PONDEROSA PINE, N.62°E., 27.1 FT., SCRIBED-S1/16S9BT; 5" PONDEROSA PINE, N.26°45'W., SCRIBED-S1/16S8BT. RAISED 2 FT. DIAM. STONE & EARTH MOUND TO CAP.
3	T16SR331/2E 1-45 S8 S9 M.V. S17 S16 20°E 1982 PLS 848		FND. 2 1/2" O.D. ALUM. PIPE WITH 3 1/4" ALUM. CAP, 10" ABOVE GROUND IN 3 FT. DIAM. STONE MOUND. FERGUSON BT'S FOUND: 11" LODGEPOLE PINE (DEAD), N.30° E., 63.6 FT., V.S.-T16SR331/2E S9 BT; 9" LODGEPOLE PINE (DEAD), S.71°30'E, 36.2 FT., V.S.-T16S R331/2ES16BT; 6" LODGEPOLE PINE (GOOD CONDITION), S.29°30'W., 28.4 FT., V.S.-XBT; 8" LODGEPOLE PINE (GOOD CONDITION), N.21°30'W., 19.8 FT., V.S.-XBT.	BT'S MARKED: 6" PONDEROSA PINE, N.9°E., 43.5 FT., SCRIBED-T16SR331/2ES9BT; 5" LODGE-POLE PINE, S.49°30'E., 46.5 FT., SCRIBED-XBT.
4	T16SR331/2E 1-43 SW1/16 S9 M.V. LS 1026 20°E 1983		NOT PREVIOUSLY ESTABLISHED. N-W WIRE FENCE CORNER BRS. N.60° 30'W., 60 FT..	BT'S MARKED: 11" PONDEROSA PINE, N.75°W., 230.7 FT., SCRIBED-SW1/16S9BT; 16" LODGE-POLE PINE, S.71°W., 242.2 FT., SCRIBED-SW1/16S9BT. RAISED STONE MOUND 2 FT. DIAM. TO CAP.
5	T16SR331/2E 1-42 W1/16 M.V. C—C 20°E S9 LS 1026 1983		NOT PREVIOUSLY ESTABLISHED ROUNDED E-S WIRE FENCE CORNER. BRS. N.77°E., 93 FT..	BT'S MARKED: 8" PONDEROSA PINE, N.63°W., 13.1 FT., SCRIBED-CW1/16S9BT; 9" LODGE-POLE PINE, S.22°30'W., 40.0 FT., SCRIBED-CW1/16S9BT.

ARMSTRONG SURVEYING & ENGINEERING, INC.
378 EAST SECOND STREET
PRINEVILLE, OREGON 97754
503/447-7791