

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*David B. Armstrong*

10/3/83 OREGON  
AUGUST 22, 1973  
DAVID B. ARMSTRONG  
1026

MALHEUR NATIONAL FOREST  
D.S. CADASTRAL SURVEY  
CONTRACT NO. 53-04KK-3-01176  
PRAIRIE CITY RANGER DISTRICT

RECEIVED AND  
FILED

DEC 28 1983

BOUNDARY SURVEY AND SECTION SUBDIVISION OF  
SECTION 9, TOWNSHIP 16 SOUTH, RANGE 33 1/2 EAST, W.M.,  
GRANT COUNTY, OREGON  
W.O. 83-406A

OFFICE OF COUNTY SURVEYOR  
*Robert D. Burt*  
Attest: *Donnie L. Lamm*

COR. CAP NO. MARKINGS	FIELD BOOK- PAGE/ DECL.	EVIDENCE FOUND	CORNER ACCESSORIES
6 T16SR331/2E 1/4 S4 S9 LS 1026 1983	1-34 & 35 M.V. 20°E	FOUND STONE 22"X9"X5" SET 10" IN GROUND MKD. "1/4" ON NORTH FACE. FND. ORIG. NW BT, A 31" PONDEROSA PINE (ALIVE), N.28°30'W., 18.0 FT., V.S.-4; FND. ORIG. SW BT, A 30" PONDEROSA PINE (DEAD & DOWN SNAG) ROOT HOLE BRS. S.53°30'W., 34.0 FT., V.S.-1/4S AND BT.	BT'S MARKED: 6" PONDEROSA PINE, N.45°W., 11.9 FT., SCRIBED-1/4S4BT; 7" PONDER- OSA PINE, S.31°15'W., 10.0 FT., SCRIBED-1/4S9BT. RAISED STONE & EARTH MOUND 4 FT. DIAM. TO CAP.
7 T16SR331/2E C1 S9 4 LS 1026 1983	1-41 M.V. 20°E	NOT PREVIOUSLY ESTABLISHED. N-E-W WIRE FENCE CORNER BRS. N. 24°E., 84.0 FT..	BT'S MARKED: 15" LODGEPOLE PINE, N.2°30'W., 97.0 FT., SCRIBED-C1/4S9BT; 17" LODGEPOLE PINE, N.82°15'W., 196.6 FT., SCRIBED-C1/4S9BT.
8 T16SR331/2E 1/4 S9 S16 LS 1026 1983	1-28 & 29 M.V. 20°E	NO DEFINITE ORIG. EVIDENCE RE- COVERED, CORNER CONSIDERED OB- LITERATED, AND TRUE POSITION PERPETUATED BY OLD NOW DOWN WOOD RAIL & JACK FENCE CORNER. FENCES SOUTH & WEST. ACCEPT OLD FENCE INTERSECTION AS CORNER.	REFERENCE MONUMENTS SET: 6 FT. STEEL FENCE POST BRS. N.71° 30'W., 9.0 FT.; 6 FT. STEEL FENCE POST BRS. S.7°W., 6.8 FT.. BOLTED SIGNS 54-3 AND 54-4 ON EACH POST. RAISED STONE MOUND 3 FT. DIAM. TO CAP.
9 T16SR331/2E E1 S9 16 S16 LS 1026 1983	1-38 M.V. 20°E	NOT PREVIOUSLY ESTABLISHED. E-W WIRE FENCE PASSES 4.6 FT. SOUTH OF CORNER. N-S WIRE FENCE PASSES 4.5 FT. WEST OF CORNER.	BT'S MARKED: 9" LODGEPOLE PINE, N.21°15'E., 22.5 FT., SCRIBED-E1/16S9BT; 9" LODGEPOLE PINE, S.31°45'E., 24.0 FT., SCRIBED-E1/16S16BT.
10 T16SR331/2E E1/16 C S9 LS 1026 1983	1-39 M.V. 20°E	NOT PREVIOUSLY ESTABLISHED. N-S-W WIRE FENCE CORNER BRS. N. 42°30'E., 126.0 FT..	BT'S MARKED: 12" LODGEPOLE PINE, S.35°W., 66.0 FT., SCRIBED-CE1/16S9BT; 9" LODGE- POLE PINE, S.38°E., 234.0 FT., SCRIBED-CE1/16S9BT. RAISED STONE MOUND 2 FT. DIAM. TO CAP.
11 T16SR331/2E E1 S4 16 S9 LS 1026 1983	1-40 M.V. 20°E	NOT PREVIOUSLY ESTABLISHED. N-S-E WIRE FENCE CORNER LOCATED 39 FT. NORTH AND 1 FT. EAST OF CORNER.	BT'S MARKED: 10" LODGEPOLE PINE, N.56°45'E., 69.1 FT., SCRIBED-E1/16S4BT; 8" PONDEROSA PINE, S.3°E., 161.4 FT., SCRIBED-E1/16S9BT. RAISED STONE MOUND 2 FT. DIAM. TO CAP.
12 T16SR331/2E S4   S3 S9   S10 LS 1026 1983	1-32 & 33 M.V. 20°E	FOUND ORIGINAL STONE 18"X13"X 9" SET 12" IN GROUND MKD WITH 3 GROOVES EAST FACE & 5 GROOVES SOUTH FACE. SURROUNDED BY 3 SMALLER STONES. RUSTED 6D NAIL DRIVEN IN TOP OF STONE. E-W WIRE FENCE PASSES 1.5 FT., NORTH OF CORNER.	BT'S MARKED: 15" PONDEROSA PINE, N.67°E., 271.2 FT., SCRIBED-T16SR331/2ES3BT; 8" DOUBLE LODGEPOLE PINE, S.56°45'E., 404.6 FT., SCRIBED-T16SR331/2ES10BT. REFERENCE MONUMENTS SET: 6 FT. LONG STEEL FENCE POST BRS. S.50°30'W., 6.3 FT.; 6 FT. LONG STEEL FENCE POST BRS. N.35°W., 9.8 FT.. RAISED STONE MOUND 2 1/2 FT. DIAM. TO CAP.
13 T16SR331/2E 1/4 S9 S10 LS 1026 1983	1-30 & 31 M.V. 20°E	FOUND ORIGINAL BASALT STONE 20"X14"X12" SET 8" IN GROUND TIPPED OVER TO WEST. WHEN RAISED UPRIGHT STONE CLEARLY MKD. "1/4" ON WEST FACE. NO EVIDENCE REMAINS OF SE BT. AT RECORD POSITION OF NW BT FOUND ALMOST COMPLETELY ROTTED LOG, SIZE INDETERMINATE.	BT'S MARKED: 6" LODGEPOLE PINE, S.12°45'E., 56.2 FT., SCRIBED-1/4S10BT; 7" LODGEPOLE PINE, S.65°W., 34.8 FT., SCRIBED-1/4S9BT. RAISED STONE & EARTH MOUND 2 FT. DIAM. TO CAP.

ARMSTRONG SURVEYING & ENGINEERING, INC.  
378 EAST SECOND STREET  
PRINEVILLE, OREGON 97754  
503/447-7791