

REGISTERED
PROFESSIONAL
LAND SURVEYOR

David B. Armstrong
10/3/83 OREGON
AUGUST 22, 1973
DAVID B. ARMSTRONG
1026

MALHEUR NATIONAL FOREST
D.S. CADASTRAL SURVEY
CONTRACT NO. 53-04KK-3-01176
BURNS RANGER DISTRICT

SURVEY OF EAST AND NORTH LINES OF
SECTION 21, TOWNSHIP 18 SOUTH, RANGE 31 EAST, W.M.,
GRANT COUNTY, OREGON
W.O. 83-406B

GENERAL SURVEY NOTES

1. SURVEY FIELD NOTES ARE ON FILE IN THE OFFICE OF ARMSTRONG SURVEYING & ENGINEERING, INC., 378 EAST SECOND STREET, PRINEVILLE, OREGON - ONE BOOK.
2. BASIS OF BEARINGS - BEARINGS FOR THIS SURVEY ARE BASED ON SOLAR OBSERVATION TAKEN NEAR THE EAST 1/4 CORNER SECTION 21 AND VERIFIED BY SOLAR OBSERVATION NEAR THE SE CORNER OF SECTION 21.
3. GENERAL LAND OFFICE RECORD FOR SUBDIVISION OF T. 18 S., R. 31 E., W.M. FROM OFFICIAL NOTES AND PLAT BY REUBEN R. LEIGH, DEPUTY SURVEYOR, PERFORMED UNDER G.L.O. CONTRACT NO. 462 DATED APRIL 11, 1883, AND CONDUCTED DURING THAT YEAR.
4. NORTHWEST CORNER OF SECTION 21 REMONUMENTED BY SHERMAN E. ANDERSON, LS 1067, ON JULY 6, 1978.

SURVEY INFORMATION

SEE ACCOMPANYING 2 SHEETS OF CORNER ACCESSORY INFORMATION. SEE ALSO ACCOMPANYING CERTIFIED RECORDS OF LAND CORNER MONUMENTATION FOR ALL CORNERS SET, OR LINE TREES MAINTAINED IN THIS SURVEY, A TOTAL OF 6. SEE ALSO ATTACHED SURVEY NARRATIVE, 2 SHEETS, FOR ADDITIONAL INFORMATION ON PROCEDURES AND/OR CONDITIONS ENCOUNTERED DURING THIS SURVEY.

COR. NO.	CAP MARKINGS	FIELD BOOK-PAGE/DECL.	EVIDENCE FOUND	CORNER ACCESSORIES
1	T18SR31E S21 S22 S28 S27 LS 1026 1983	1-65 & 66 M.V. 19°E	FND. ORIG. SW BT, A 31" PONDEROSA PINE WITH OLD HEALED PARTIALLY OPEN FACE, V.S.-T18SR3, BRS. S.70°W., 102.30 FT.; FND. ORIG. SE BT, A 30" PONDEROSA PINE DEAD & STANDING SNAG WITH OPEN FACE, V.S.-T18SR31ES27, BRS. S.44°E., 89.76 FT., RE-ESTABLISH CORNER AT RECORD DISTANCES FROM BT'S.	BT'S MARKED: 6" PONDEROSA PINE, N.66°30'E., 42.7 FT., SCRIBED-T18SR31ES22BT; 9" PONDEROSA PINE, S.71°E., 52.3 FT., SCRIBED-T18SR31ES27BT; 13" PONDEROSA PINE, N.59°W., 11.6 FT., SCRIBED-T18SR31ES21BT. RAISED STONE & EARTH MOUND 3 FT. DIAM. TO CAP.
2	LINE TREE	1-76 M.V. 19°E	FND. 54" DIAM. PONDEROSA PINE SAWED STUMP 48" HIGH WITH 2 DISTINCT HEALED HACK MARKS ON NORTH FACE, SOUTH HACKS REMOVED WITH LOG.	BT'S MARKED: 9" PONDEROSA PINE, S.60°E., 17.9 FT., SCRIBED-APS22BT; 10" PONDEROSA PINE, S.30°W., 35.5 FT., SCRIBED-APS21BT.
3	T18SR31E 1/4 S21 S22 LS 1026 1983	1-67 & 68 M.V. 19°E	FND. ORIG. SW BT, A 23" PONDEROSA PINE BOTH FACES HEALED, BRS. S.60°30'W., 72.6 FT.; FND. ORIG. SE BT A 36" PONDEROSA PINE SAWED STUMP 12" HIGH, V.S.-BT, BRS. S.55°30'E., 26.4 FT.. RE-ESTABLISH CORNER AT RECORD DISTANCES FROM BT'S.	BT'S MARKED: 6" PONDEROSA PINE, S.44°E., 16.0 FT., SCRIBED-1/4S22BT; 7" PONDEROSA PINE, S.42°W., 9.3 FT., SCRIBED-1/4S21BT. RAISED STONE & EARTH MOUND 3 FT. DIAM. TO CAP.
4	LINE TREE	1-77 M.V. 19°E	FND. 59" DOUBLE PONDEROSA PINE SNAG DEAD & STANDING WITH 2 DISTINCT HACKS ON NORTH FACE & 2 DISTINCT HACKS ON SOUTH FACE. TREE IS ON LINE BETWEEN CORNERS & MATCHES THE RECORD DISTANCE CALL.	BT'S MARKED: 6" JUNIPER, S.82°51'E., 25.56 FT., SCRIBED-APS22BT; 7" PONDEROSA PINE, N.24°53'W., 19.50 FT., SCRIBED-S21BT.
5	T18SR31E S16 S15 S21 S22 LS 1026 1983	1-70 & 71 M.V. 19°E	FND. BASALT STONE 20"X18"X7" FIRMLY SET 12" IN GROUND, AT NE COR. OF ROCK JACK AT OLD ANGLE IRON WIRE FENCE LINE. STONE MKD. WITH 3 GROOVES ON SOUTH & EAST FACES.	BT'S MARKED: 6" JUNIPER, N.44°E., 96.2 FT., SCRIBED-T18SR31ES15BT; 22" JUNIPER, S.2°30'E., 170.7 FT., SCRIBED-T18SR31ES22BT; 7" JUNIPER, S.56°45'W., 136.5 FT., SCRIBED-T18SR31ES21BT; 16" JUNIPER, N.52°W., 63.6 FT., SCRIBED-T18SR31ES16BT. RAISED STONE MOUND 2 1/2 FT. DIAM. TO CAP.

ARMSTRONG SURVEYING & ENGINEERING, INC.
378 EAST SECOND STREET
PRINEVILLE, OREGON 97754
503/447-7791

RECEIVED AND
FILED

DEC 28 1983

OFFICE OF COUNTY SURVEYOR
Robert D. Bryant
Attest: *Annice L. Lunsford*

W.O. 83-406B