



NOTES:
ALL BEARINGS AND DISTANCES IN PARENTHESIS ARE RECORD BEARINGS AND DISTANCES.
FOR ADDITIONAL INFORMATION ON CORNERS RECOVERED OR MONUMENTED, SEE CERTIFIED RECORD OF LAND CORNER MONUMENTATION FORMS FILED HEREWITH.
FIELD BOOK REFERENCE - TRAVERSE BOOK NO. 2 AND 3 AND MONUMENTATION BOOK NO. 1 & 2 OF THE GREENHORN MINES CADASTRAL SURVEY.

SURVEYOR'S CERTIFICATION
I, WILLIAM R. WELLS, A REGISTERED PROFESSIONAL LAND SURVEYOR IN THE STATE OF OREGON, HEREBY CERTIFY, THAT THIS PLAT, AND THE NOTES HEREON, ARE A CORRECT REPRESENTATION OF A SURVEY PERFORMED BY ME DURING THE MONTHS OF JULY AND AUGUST, 1983, AT THE REQUEST OF THE USDA, FOREST SERVICE. SAID PLAT AND NOTES WERE PREPARED IN ACCORDANCE WITH THE STATUTES OF THE STATE OF OREGON AND WITH THE ARTICLES OF THE CONTRACT.

William R. Wells
WILLIAM R. WELLS, PLS
OREGON LICENSE NO. 1106

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells
OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

- LEGEND**
- - SET 2 1/2" X 3/4" ALUMINUM PIPE WITH 2 1/2" ALUM. CAP FROM EXISTING EVIDENCE UNLESS OTHERWISE NOTED.
 - - SET 2 1/2" X 3/4" ALUMINUM PIPE WITH 2 1/2" ALUM. CAP BY TRAVERSE SURVEY.
 - ⊙ - FOUND 2 1/2" X 3/4" G.I.P. WITH 2 1/2" BRASS CAP SET FROM EXISTING EVIDENCE BY HAMBLETON IN 1972.
 - ⊙ - 1/4 AND 5/8 SECTION CORNERS FOUND AS NOTED.
 - - U.S. NATIONAL FOREST BOUNDARY - BOUNDARY POSTED.

NARRATIVE OF SURVEY
THIS SURVEY INVOLVED RETRACEMENT OF THE BOUNDARIES, REMONUMENTATION OF CORNERS AND POSTING OF MS 458 CLAIMS VIRGIN AMENDED, MYRTHFUL AND GREENHORN AND MS 548, COLIN PIERCE. MS 458 WAS ORIGINALLY SURVEYED BY ARTHUR PHILBRICK IN JUNE, 1902. MS 548 WAS ORIGINALLY SURVEYED BY ARTHUR PHILBRICK IN SEPTEMBER, 1903. THE SURVEY ALSO INVOLVED PARTIAL SECTION BREAKDOWN OF SECTION 9, T10S, R35E, W.M. TO DENOTE THE FOREST BOUNDARY WITHIN THE SOUTHEAST 1/4 SECTION 9 WAS ORIGINALLY SURVEYED BY HERMAN D. GRADON UNDER OLD CONTRACT NO. 416 DURING OCTOBER, 1881. OUR SURVEY WAS MADE WITH A 6" THEODOLITE AND INFA-RED DISTANCE MEASURING EQUIPMENT. MS 458, VIRGIN, WAS AMENDED BY WILLIAM W. ELMER IN JULY, 1904.

RECEIVED AND FILED
MAY 10 1984
OFFICE OF COUNTY SURVEYOR
Robert D. Sargent
Attest: *James A. Lawrence*

WALLULIS PROJECT NO:		AGENCY PROJECT NO: USFS CONTRACT 53-04M3-3-2886 R16-85-11N	
PROJECT: GREENHORN MINES CADASTRAL SURVEY WALLOWA-WHITMAN NATIONAL FOREST LOCATED IN THE EAST 1/2 OF SECTION 9, AND NORTH 1/2 OF SECTION 10, T10S, R35E, W.M., BAKER AND GRANT COUNTIES, OREGON.			
WALLULIS & ASSOCIATES, INC. ENGINEERING & PLANNING			
SCALE: 1"=300'	DATE: 8-7-83	DES BY:	DR BY: WRW
TITLE: MS 458 MS 548		CK BY: WRW	
REVISIONS			
DRAWING:			
SHEET 1 OF 1			