



BASIS OF BEARING

A.M. Solar observation taken at a point 300 feet East of the West quarter corner of Section 13, Township 8 South, Range 26 East of the Willamette Meridian.

Date May 20, 1984
Mean vertical angle 43°39'23"
Mean horizontal angle 270°14'42"
Mean declination 20°07'58"
Latitude 44°52'25"
Magnetic declination 20° East

LEGEND

- Found BLM aluminum monument
- ⊙ Found GLO evidence - set 2 1/2" x 30" aluminum monument
- ⊙ Set 2 1/2" x 30" aluminum monument at proportionate position
- () Record GLO distance and bearing
- ////// Posted line

For monumentation information, see remonumentation sheets filed separately

SURVEYOR'S STATEMENT

I, Duane I. Griffith, Registered Land Surveyor in the State of Oregon, hereby certify that this plat and the notes hereon, or attached, are a true and correct representation of the survey I made in May and June, 1984, at the request of the USDA, Forest Service, in accordance with the statutes of the State of Oregon, and with the articles of my contract.

I began my survey by locating existing monumented corners in Section 23, and the corners outside of Section 23 as shown. From this information I developed search areas for the corners in Section 23 not yet found. I found all corners pertinent to Section 23 as shown. I therefore did not search for any additional corners, as I had the necessary information for my work in the Section. I am showing the bearings and distances to the outlying corners for informational purposes only. There may be existing original corners between these monuments not searched for on this contract.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 10, 1964
DUANE I. GRIFFITH
644

Duane I. Griffith
Duane I. Griffith, OPLS 644
Bagett, Griffith and Associates
P.O. Box 576
La Grande, Oregon 97850

HISTORY OF SURVEYS

The South line and subdivisional lines of Township 8 South, Range 26 East, were surveyed by Alonzo Gesner in 1877 under G.L.O. contract number 266. In 1982 the BLM monumented the following corners using original corner evidence:

- The Northwest corner of Section 14
- The East 1/4 corner of Section 22
- The Southwest corner of Section 22
- The South 1/4 corner of Section 23
- The Southeast corner of Section 23

RECEIVED AND
FILED

AUG 15 1984

OFFICE OF COUNTY SURVEYOR
Duane I. Griffith
Attest: *Carol L. Wright, Clerk*

BAGETT - GRIFFITH & ASSOCIATES La Grande, Oregon		
Map of Survey Section 23 Township 8 South, Range 26 East Willamette Meridian GRANT COUNTY, OREGON		
SURVEYED FOR	Umatilla National Forest	
SURVEYED BY	d.i.g.	6/84
Scale: 1" = 600'	Drawn by: r.g.r.	6/84

RECORD MAP OF SURVEY NO. 827