



REFERENCE MATERIAL

G.L.O. Notes & Plats T8S & T9S R35E

Deed Records Book 92 Page 374 Grant Co. Deed Records
Book 94 Page 599 Grant Co. Deed Records
Book 97 Page 452 Grant Co. Deed Records
Book 108 Page 238 Grant Co. Deed Records
Book 99 Page 251 Grant Co. Deed Records
Book 111 Page 481 Grant Co. Deed Records
Book 118 Page 60 Grant Co. Deed Records

Grant County
Record Survey
#575

NOTE

All corner positions established by this survey were determined in accordance with procedures outlined in the Manual of Instructions for the Survey of the Public Lands of the United States, 1973, Bureau of Land Management Technical Bulletin No. 6. Exterior section and 1/4 section corners were positioned according to the relationships given in the record of the original government survey. All subdivisional 1/16, 1/64 and 1/256 corner locations were determined by survey and are based on the prescribed procedures for subdivision of sections. A complete description of each monument established by this survey is given on individual Certified Record of Land Corner Monumentation forms being filed concurrently with this survey map.

HISTORY OF SURVEYS

The Township line between T8S T9S, R35E and T8S and T9S subdivision surveys were performed in 1884 by Herman Gradon under G.L.O. contract No. 499.

In 1965 an unrecorded survey performed by Donald L. Staebler, Registered Engineer No. 5408, attempted to define the subdivisional lines in Sections 27, 28 and 35, T8S, R35E w.m. (See Narrative)

In 1979 the east lines of Section 2, T9S, R35E were retraced by William Hanley, PLS 1639. See Grant Co. Record Survey 575.

SURVEYOR'S STATEMENT

I, Gary L. Langlitz, a Registered Land Surveyor in the State of Oregon, hereby certify that this plat and the notes hereon or attached are a correct representation of a survey I performed during July 1982 - Sept. 1983 for the U.S. Forest Service, in accordance with the statutes of the State of Oregon and the Articles of the Lawton-Chopper Cadastral Survey Contract No. 53-04R3-2-01275.

Gary L. Langlitz 7-17-84



RECEIVED AND FILED AUG 30 1984 OFFICE OF COUNTY SURVEYOR <i>Robert D. [Signature]</i> Attest: <i>James [Signature]</i>	
MAP OF SURVEY SECTIONS 27, 28, 34, 35 OF T8S, R35E AND SECTION 2, T9S, R35E, WILLAMETTE MERIDIAN GRANT COUNTY, OREGON	
FOR: U.S. FOREST SERVICE	
SCALE: 1" = 1000'	SHEET NO. 1/1
DATE: 1982-1984 JOB NO. 831-10	Anderson Perry & Associates, Inc. ENGINEERING • SURVEYING • MATERIALS TESTING LA GRANDE, ORE. & WALLA WALLA, WASH.

NARRATIVE

This survey was for the U.S. Forest Service to mark part of the Umatilla National Forest Boundary in Sections 26, 27, 28, 34, 35 T8S R35E W.M. and Section 2 T9S R35E W.M.

An extensive search was performed to locate missing corners by computing search areas from our survey control.

Monumentation on the township line is based upon the recovery of the original 3/4 corner of Section 34, T8S, R35E, in conjunction with the existing section corner common to Sections 35 & 36 T8S R35E. The proportioning of the corners pertaining to T8S and T9S is based upon the G.L.O. retracement of the south boundary of T8S R35E for setting corners pertaining to T9S.

We have found 5/8" iron rods at numerous fence corners in Sections 27, 28 and 35 T8S, R35E. A search of Grant Co. records revealed no recorded survey in that area. The Forest Service records show pins were set by Donald Staebler. We contacted him and he furnished us with a map of his survey. In reviewing this map we feel that the sections were not properly subdivided due to lack of controlling corners on the township line and lack of adequate section and quarter corners. Therefore the pins appear out of position. Refer to our corner monumentation for ties to these pins.

In 1979 William Hanley LS #1639 set the northwest section corner of Section 1, T9S, R35E, by using record distance from the section corner common to sections 35 and 36 T8S, R35E measured along the south line of Section 36 instead of a proportion from the section corner common to 35 and 36 to the south 1/4 corner of Section 36 where Hanley accepted a mound of stone that was long accepted by local long-time residents as the 1/4 corner to Section 36. By using this position for the northwest corner of Section 1, we will maintain harmony in the area with the existing survey monumentation.

LEGEND

- Set monument as described on corner remon. sheets filed separately.
- Set monument from original evid. as described on corner remon. sheets filed separately.
- Set monument on township line as described on corner remon. sheets filed separately.
- Set monument on township line from original evid. as described on corner remon. sheets filed separately.
- Found 2" diameter iron pipe with brass cap as described in Grant Co. Survey No. 575.
- Found 2" diameter iron pipe with brass cap as set and described by William Hanley, L.S. 1639, in 1979. (See Grant Co. Surveyor's Remonumentation Records).
- Record G.L.O. dimension.
- Record dimension from Grant Co. Survey No. 575.
- Area in Private Ownership.
- U.S. Dept. of Agriculture - Forest Service Lands.