

OCHOCO NATIONAL FOREST  
SAWMILL CADASTRAL SURVEY  
CONTRACT NO. 53-04H1-3-9360N  
PAULINAR RANGER DISTRICT

SURVEY OF LINE BETWEEN SECTIONS 10 AND 11,  
TOWNSHIP 14 SOUTH, RANGE 26 EAST, W.M.,  
GRANT COUNTY, OREGON  
W.O. 83-411D

COR. NO.	CAP MARKINGS	FIELD BOOK- PAGE/ DECL.	EVIDENCE FOUND	CORNER ACCESSORIES
1	T14SR26E S3   S2 S10   S11 LS 1026 1982	5-49 M.V. 19°E.	FND. 2 1/2" ALUM. PIPE WITH 3 1/4" ALUM. CAP 18" ABOVE GRND. IN CENTER 3 FT. DIAM. STONE MND..	FND. 1982 BT'S: 8" DOUGLAS FIR, N28°30'E, 32.8 FT., SCRIBED-T14SR26ES2BT; 19" DOUGLAS FIR, S65°E, 16.9 FT., SCRIBED-T14S R26ES11BT; 12" DOUGLAS FIR, S54°W, 11.7 FT., SCRIBED-T14SR26ES10BT; 8" POND. PINE, N6°W, 34.2 FT., SCRIBED-T14SR26ES3BT.
2	T14SR26E 1 4 S10   S11 LS 1026 1984	5-52 & 53 M.V. 18°30'E.	FND. BASALT STONE 15"X11"X 10" SET IN CENTER 2 1/2 FT. DIAM. STONE MND. CONSISTING OF 5 OTHER STONES, ORIG. STONE MARKED "1/4S" ON NORTH FACE.	BT'S MARKED: 9" POND. PINE, N49°45'W, 17.1 FT., SCRIBED-1/4S10BT; 10" POND. PINE, N67°30'E, 20.9 FT., SCRIBED-1/4S11 BT.
3	T14SR26E S10   S11 S15   S14 LS 1026 1982	5-50 M.V. 18°30'E.	FND. 2 1/2" ALUM. PIPE WITH 3 1/4" ALUM. CAP 10" ABOVE GRND. IN CENTER OF 4 FT. DI DIAM. STONE MND..	FND. 1982 BT'S: 16" JUNIPER, N9°30'E, 29.2 FT., SCRIBED-T14SR26ES11BT; 8" JUNIPER, S78°E, 18.0 FT., SCRIBED-T14SR26E S14BT; 4" JUNIPER, S70°W, 26.3 FT., SCRIBED-XBT. FND. 1982 B.O.: BASALT BOULDER 6 FT. X 7 FT. X 5 FT., N48°15'W, 9.1 FT., MARKED "+BO". FND. UNRECORDED BT: 26" JUNIPER, S22°15'W, 37.1 FT., V.S.-T1R26S15BT.

CORNER NOTES

BOOK AND PAGE NUMBERS REFER TO FIELD BOOK AND PAGE. ALL CORNER MONUMENTS SET ARE 2 1/2 INCH O.D. ALUMINUM PIPE 30 INCHES LONG WITH 3 1/4 INCH ALUMINUM CAP MARKED AS PER CORNER DIAGRAM. ALL BEARING TREES ARE SCRIBED AS PER B.L.M. MANUAL OF INSTRUCTIONS, 1973, WITH THE ADDITION OF A BRASS WASHER MARKED "AS&E LS1026" NAILED IN LOWER BLAZE. BEARINGS TO BEARING TREES ARE BY STAFF COMPASS USING DECLINATION AS NOTED, DISTANCES ARE MEASURED TO CENTER SIDE OF BEARING TREE. SEE ALSO ACCOMPANYING CERTIFIED RECORD OF LAND CORNER MONUMENTATION FOR ALL CORNERS SET OR MAINTAINED. THIS CORNER RECORD SHOULD BE CONSULTED FOR A MORE COMPLETE DESCRIPTION OF EVIDENCE FOUND AND MONUMENTATION OF CORNER.

RECORDATION

OFFICE OF COUNTY SURVEYOR, COUNTY  
OF GRANT, STATE OF OREGON. I  
HEREBY CERTIFY THAT THE WITHIN  
INSTRUMENT WAS FILED FOR RECORD ON  
THE 23 DAY OF Nov, 1984.

*Robert D. Baggett*  
GRANT COUNTY SURVEYOR

ARMSTRONG SURVEYING & ENGINEERING,  
INC.  
378 EAST SECOND STREET  
PRINEVILLE, OREGON 97754  
PHONE (503) 447-7791

SHEET 2 OF 2

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*David B. Armstrong*  
11/7/84 OREGON  
AUGUST 22, 1975  
DAVID B. ARMSTRONG  
1026

W.O. 83-411D

MAP OF SURVEY NO. 845