

OCHOCO NATIONAL FOREST  
SAWMILL CADASTRAL SURVEY  
CONTRACT NO. 53-04H1-3-9360N  
PAULINA RANGER DISTRICT

SURVEY OF LINE BETWEEN SECTIONS 34 AND 35,  
TOWNSHIP 13 SOUTH, RANGE 26 EAST, W.M.,  
GRANT COUNTY, OREGON  
W.O. 83-411E

GENERAL SURVEY NOTES - CONTINUED FROM PAGE 1

6. THE CORNER COMMON TO SECTIONS 34 AND 35 ONLY WAS REMONUMENTED BY DAVID B. ARMSTRONG, LS 1026, DURING JUNE-JULY, 1982, AND A CERTIFIED RECORD OF LAND CORNER MONUMENTATION WAS FILED WITH THE GRANT COUNTY SURVEYOR ON SEPTEMBER 3, 1982.

7. SURVEY INFORMATION - SEE ACCOMPANYING TABLE OF CORNER ACCESSORY INFORMATION; ACCOMPANYING CERTIFIED RECORD OF LAND CORNER MONUMENTATION FOR THE CORNERS SET DURING THIS SURVEY, 2; AND ATTACHED SURVEY NARRATIVE FOR ADDITIONAL INFORMATION ON PROCEDURES AND/OR CONDITIONS ENCOUNTERED DURING THIS SURVEY.

COR. NO.	CAP MARKINGS	FIELD BOOK-PAGE/DECL.	EVIDENCE FOUND	CORNER ACCESSORIES
1	T13SR26E S27   S26 S34   S35 1962 B.L.M.	5-58 M.V. 18°30'	FND. 2 1/2" BRASS CAP ON 2 1/2" O.D. GALV. IRON PIPE 5" ABOVE GRND. IN CENTER 3 FT. DIAM. STONE MOUND.	FND. 1962 BT'S: 20" DOUGLAS FIR, N83°30'E, 31.7 FT., HEALED FACE; 15" PONDEROSA PINE, S24°30'E, 8.0 FT., HEALED FACE; 18" PONDEROSA PINE, S49°30'W, 31.0 FT., HEALED FACE; 21" PONDEROSA PINE, N66°30'W, 43.0 FT., HEALED FACE. BT'S MARKED: 8" JUNIPER, S49°15'W, 67.0 FT., SCRIBED-1/4S34BT; 10" JUNIPER, S14°15'E, 5.1 FT., SCRIBED-1/4S35BT.
2	T13SR26E 1 4 S34   S35 LS 1026 1984	5-4 & 5	ORIGINAL CORNER LOST. FOUND. U.S.F.S. APPROX. 1/4 CORNER, BASALT STONE 18"X10"X10" IN LOOSE STONE RING. NOT ACCEPTED AS CORNER. APPROX. 1/4 CORNER BRS. S46°10'E, 266.2 FT. FROM MONUMENTED CORNER.	BT'S MARKED: 17" DOUGLAS FIR, N43°30'E, 28.8 FT., SCRIBED-S1/16S35BT; 18" PONDEROSA PINE, N61°45'W, 45.7 FT., SCRIBED-S1/16S34BT.
3	T13SR26E S 1 16 S34   S35 RLS 1026 1984	5-67	CORNER NOT PREVIOUSLY ESTAB- LISHED.	BT'S MARKED: 17" DOUGLAS FIR, N43°30'E, 28.8 FT., SCRIBED-S1/16S35BT; 18" PONDEROSA PINE, N61°45'W, 45.7 FT., SCRIBED-S1/16S34BT.
4	T13SR26E SC S34   S35 S2 T14S LS 1026 1982	5-60	FND. 3 1/4" ALUM. CAP ON 2 1/2" O.D. ALUM. PIPE 14" ABOVE GRND. IN CENTER 3 FT. DIAM. STONE MOUND.	FND. 1982 BT'S: 14" JUNIPER, N27°30'E, 23.6 FT., VISIBLE SCRIBING-T13SR26ES35SCBT; 10" JUNIPER, N62°30'W, 50.5 FT., VISIBLE SCRIBING-T13SR26ES34SCBT.

CORNER NOTES

BOOK AND PAGE NUMBERS REFER TO FIELD BOOK AND PAGE. ALL CORNER MONUMENTS SET ARE 2 1/2 INCH O.D. ALUMINUM PIPE 30 INCHES LONG WITH 3 1/4 INCH ALUMINUM CAP MARKED AS PER CORNER DIAGRAM. ALL BEARING TREES ARE SCRIBED AS PER B.L.M. MANUAL OF INSTRUCTIONS, 1973, WITH THE ADDITION OF A BRASS WASHER MARKED "AS&E LS1026" NAILED IN LOWER BLAZE. BEARINGS TO BEARING TREES ARE BY STAFF COMPASS USING DECLINATION AS NOTED, DISTANCES ARE MEASURED TO CENTER SIDE OF BEARING TREE. SEE ALSO ACCOMPANYING CERTIFIED RECORD OF LAND CORNER MONUMENTATION FOR ALL CORNERS SET OR MAINTAINED. THIS CORNER RECORD SHOULD BE CONSULTED FOR A MORE COMPLETE DESCRIPTION OF EVIDENCE FOUND AND MONUMENTATION OF CORNER.

RECORDATION

OFFICE OF COUNTY SURVEYOR, COUNTY  
OF GRANT, STATE OF OREGON. I  
HEREBY CERTIFY THAT THE WITHIN  
INSTRUMENT WAS FILED FOR RECORD ON  
THE 23 DAY OF NOV, 1984.

*Robert D. Baggett*  
GRANT COUNTY SURVEYOR

ARMSTRONG SURVEYING & ENGINEERING,  
INC.  
378 EAST SECOND STREET  
PRINEVILLE, OREGON 97754  
PHONE (503) 447-7791

SHEET 2 OF 2

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*David B. Armstrong*  
11/7/84 OREGON  
AUGUST 22, 1975  
DAVID B. ARMSTRONG  
1026

W.O. 83-411E

MAP OF SURVEY NO. 846