

OCHOCO NATIONAL FOREST
SAWMILL CADASTRAL SURVEY
CONTRACT NO. 53-04H1-3-9360N
PAULINA RANGER DISTRICT

SURVEY OF LINES BETWEEN SECTIONS 9 AND 16, 16 AND 17, AND 20 AND 21,
TOWNSHIP 14 SOUTH, RANGE 26 EAST, W.M.,
GRANT COUNTY, OREGON
W.O. 83-411C

COR. NO.	CAP MARKINGS	FIELD BOOK-PAGE/DECL.	EVIDENCE FOUND	CORNER ACCESSORIES
1	T14SR26E S9 S10 S16 S15 LS 1026 1982	5-37 M.V. 20°E.	FND. 2 1/2" ALUM. PIPE WITH 3 1/4" ALUM. CAP 24" ABOVE GRND. IN CENTER OF LARGE 4 FT. DIAM. STONE MND..	FND. 1982 BT'S: 18" JUNIPER, N24°E, 12.3 FT., SCRIBED- T14SR26ES10BT; 13" JUNIPER, S25°E, 11.7 FT., SCRIBED-T14SR26ES15BT; 16" JUNIPER, S32°30'W, 20.9 FT., SCRIBED- T14SR26ES16BT; 20" JUNIPER, N70°W, 38.9 FT., SCRIBED-T14SR26ES9BT.
2	T14SR26E 1 S9 4 S16 LS 1026 1982	5-11 M.V. 20°E.	FND. 2 1/2" ALUM. PIPE WITH 3 1/4" ALUM. CAP 10" ABOVE GRND. IN CENTER 3 FT. DIAM. STONE MND..	FND. 1982 BT'S: 6" POND. PINE, S42°E, 1.4 FT., SCRIBED-1/4S16BT; 6" POND. PINE, N15°W, 15.8 FT., SCRIBED-1/4S9BT.
3	T14SR26E S8 S9 S17 S16 LS 1026 1982	5-18 M.V. 17°E.	FND. 2 1/2" ALUM. PIPE WITH 3 1/4" ALUM. CAP 8" ABOVE GRND. IN CENTER 3 1/2 FT. DIAM. STONE MND..	FND. 1982 BT'S: 6" DOUGLAS FIR, N64°30'E, 26.9 FT., SCRIBED-T14SR26ES9BT; 7" DOUGLAS FIR, S17°30'E, 33.0 FT., SCRIBED-T14SR26E S16BT; 6" POND. PINE, S22°30'W, 11.7 FT., SCRIBED-T14SR26ES17BT; 10" DOUGLAS FIR, N83°30'W, 34.9 FT., SCRIBED-T14SR26ES8BT. FND. ORIG. 1881 BT'S: 35" POND. PINE, S57°E, 21.3 FT., CHARRED FACE; 33" POND. PINE, N41° 30'W, 21.3 FT., V.S.-T14SR26ES81BT.
4	T14SR26E 1 4 S17 S16 LS 1026 1984	5-54 & 55 M.V. 18°30'E.	NO ORIG. CORNER EVIDENCE FND.. CORNER LOST, RE- ESTABLISH BY SINGLE PRO- PORTION METHOD BY SURVEY.	BT'S MARKED: 9" JUNIPER, N66°00'E, 32.9 FT., SCRIBED-1/4S16BT; 19" JUNIPER, S12° 00'W, 62.0 FT., SCRIBED-1/4S17BT. RAISED STONE MND. 4 FT. DIAM. TO CAP.
5	T14SR26E S17 S16 S20 S21 LS 1026 1984	5-56 & 57 M.V. 18°30'E.	FND. BASALT STONE 16"X10" X4" FIRMLY IN EARTH CAST 4" DEEP IN WEST SIDE OF STONE RING 3 FT. DIAM. CONSISTING OF 6 OTHER LARGE STONES.	BT'S MARKED: 9" JUNIPER, N42°00'E, 74.7 FT., SCRIBED-T14SR26ES16BT; 14" JUNIPER, S27°30'E, 12.2 FT., SCRIBED-T14S R26ES21BT; 12" DOUBLE JUNIPER, S42° 30'W, 10.6 FT., SCRIBED-T14SR26ES20 BT; 11" POND. PINE, N20°15'W, 69.7 FT., SCRIBED-T14SR26ES17BT. RAISED STONE MND. 4 FT. DIAM. TO CAP.
6	T14SR26E 1 4 S20 S21 LS 1026 1982	5-36 M.V. 20°E.	FND. 2 1/2" ALUM. PIPE WITH 3 1/4" ALUM. CAP 4" ABOVE GRND. IN CENTER 2 1/2 FT. DIAM. STONE MND..	FND. 1982 BT'S: 29" DOUGLAS FIR, N53°E, 11.7 FT., SCRIBED-1/4S21BT; 19" POND. PINE, N68°30'W, 41.8 FT., SCRIBED-1/4S20BT.

CORNER NOTES

BOOK AND PAGE NUMBERS REFER TO FIELD BOOK AND PAGE. ALL CORNER MONUMENTS SET ARE 2 1/2 INCH O.D. ALUMINUM PIPE 30 INCHES LONG WITH 3 1/4 INCH ALUMINUM CAP MARKED AS PER CORNER DIAGRAM. ALL BEARING TREES ARE SCRIBED AS PER B.L.M. MANUAL OF INSTRUCTIONS, 1973, WITH THE ADDITION OF A BRASS WASHER MARKED "AS&E LS1026" NAILED IN LOWER BLAZE. BEARINGS TO BEARING TREES ARE BY STAFF COMPASS USING DECLINATION AS NOTED, DISTANCES ARE MEASURED TO CENTER SIDE OF BEARING TREE. SEE ALSO ACCOMPANYING CERTIFIED RECORD OF LAND CORNER MONUMENTATION FOR ALL CORNERS SET OR MAINTAINED. THIS CORNER RECORD SHOULD BE CONSULTED FOR A MORE COMPLETE DESCRIPTION OF EVIDENCE FOUND AND MONUMENTATION OF CORNER.

RECORDATION

OFFICE OF COUNTY SURVEYOR, COUNTY
OF GRANT, STATE OF OREGON. I
HEREBY CERTIFY THAT THE WITHIN
INSTRUMENT WAS FILED FOR RECORD ON
THE 23 DAY OF Nov, 1984.

Robert D. Baggett
GRANT COUNTY SURVEYOR

ARMSTRONG SURVEYING & ENGINEERING,
INC.
378 EAST SECOND STREET
PRINEVILLE, OREGON 97754
PHONE (503) 447-7791

SHEET 2 OF 2

REGISTERED
PROFESSIONAL
LAND SURVEYOR

David B. Armstrong
11/7/84 OREGON
AUGUST 22, 1975
DAVID B. ARMSTRONG
1026

W.O. 83-411C

MAP OF SURVEY NO. 247