

GENERAL SURVEY NOTES

1. SURVEY FIELD NOTES ARE ON FILE IN THE OFFICE OF ARMSTRONG SURVEYING & ENGINEERING, INC., 378 EAST SECOND STREET, PRINEVILLE, OREGON.
2. BASIS OF BEARINGS - BEARINGS FOR THIS SURVEY ARE BASED ON SOLAR OBSERVATION TAKEN ALONG THE WEST LINE OF SECTION 36, T.18S., R.28E., W.M., NEAR THE NORTHWEST CORNER AND VERIFIED BY A SECOND SOLAR OBSERVATION TAKEN ALONG THE WEST LINE NEAR THE SOUTHWEST CORNER OF SECTION 36. BEARINGS OF THIS SURVEY ARE THEREFORE ON THE SAME BASE AS THOSE OF A SURVEY TO BE FILED CONCURRENTLY WITH THIS SURVEY ENTITLED "SURVEY OF EXTERIOR LINES OF SECTION 36, TOWNSHIP 18 SOUTH, RANGE 28 EAST, W.M., GRANT COUNTY, OREGON" FOR THE MALHEUR NATIONAL FOREST.
3. GENERAL LAND OFFICE RECORD FOR EXTERIOR LINES OF SECTION 6 FROM OFFICIAL NOTES AND PLAT BY JAMES P. CURRIN, DEPUTY SURVEYOR, UNDER GENERAL LAND OFFICE CONTRACT NO. 348 DATED JANUARY 22, 1880, AND PERFORMED DURING THAT YEAR.
4. SURVEY INFORMATION - SEE ACCOMPANYING SHEETS OF CORNER ACCESSORY INFORMATION; ACCOMPANYING CERTIFIED RECORDS OF LAND CORNER MONUMENTATION FOR ALL CORNERS SET DURING THIS SURVEY, A TOTAL OF 9; AND ATTACHED SURVEY NARRATIVE FOR ADDITIONAL INFORMATION ON PROCEDURES AND/OR CONDITIONS ENCOUNTERED DURING THIS SURVEY.

CORNER SUMMARY

COR. NO.	CAP MARKINGS	FIELD BOOK-PAGE/DECL.	EVIDENCE FOUND	CORNER ACCESSORIES
1	T18S R28E R29E S36 S31 S1 S6 T19S LS 1026 1984	3-17&18 M.V. 18°30'E.	FOUND BASALT STONE 17"X13"X6" FIRMLY SET IN STONE MND. 3 FT. DIAM. CONSISTING OF 15 OTHER STONES. STONE MKD. WITH 6 NOTCHES SE & SW EDGES.	BT'S MARKED: 7" POND. PINE, N28°30'E, 15.6 FT., SCRIBED-T18SR29ES31BT; 19" POND. PINE, S55°30'E, 38.0 FT., SCRIBED-T19SR29ES6BT; 10" POND. PINE, N40°30'W, 59.8 FT., SCRIBED-T18S R28ES36BT; 13" DOUGLAS FIR, S63° 00'W, 21.7 FT., SCRIBED-T19SR28E S1BT. RAISED STONE MND. 3 FT. DIAM. TO CAP.
2	T18SR29E 1/4 S31 S6 T19S LS 1026 1984	3-19&20 M.V. 18°30'E.	FOUND BASALT STONE 19"X10"X6" IN STONE MND. 3 FT. DIAM. CONSISTING OF APPROX. 7 STONES. STONE MKD. "1/4" ON DOWN FACE.	BT'S MARKED: 17" POND. PINE, N14°00'W, 26.7 FT., SCRIBED-1/4S31BT.; 11" JUNIPER, S58°00'W, 23.5 FT., SCRIBED-1/4S6 BT. RAISED STONE MND. 3 FT. DIAM. TO CAP.
3	T18SR29E S31 S32 S6 S5 T19S LS 1026 1984	3-9&10 M.V. 18°30'E.	FOUND BASALT STONE 23"X14"X3" SET IN STONE MND. 3 FT. DIAM. CONSISTING OF 6 OTHER STONES. STONE MKD. WITH 5 GROOVES ON EAST FACE.	BT'S MARKED: 14" JUNIPER, S81°00'W, 112.5 FT., SCRIBED-T19SR29ES6BT; 10" POND. PINE, S74°30'E, 140.7 FT., SCRIBED-T19SR29ES5BT; 9" JUNIPER, N15°E, 146.8 FT., SCRIBED-T18S R29ES32BT; 7"X5" DOUBLE JUNIPER, N23°00'W, 138.9 FT., SCRIBED-T18S R29ES31BT. RAISED STONE MND. 4 FT. DIAM. TO CAP.
4	T19SR29E 1/4 S6 S5 LS 1026 1984	3-7&8 M.V. 18°30'E.	FOUND BASALT STONE 13"X11"X6" IN STONE MND. 2 FT. DIAM. CONSISTING OF 4 OTHER STONES. STONE MKD. "1/4" ON TOP FACE.	BT'S MARKED: 6" JUNIPER, N70°00'W, 7.3 FT., SCRIBED-1/4S6BT; 20" POND. PINE, N74°30'E, 51.9 FT., SCRIBED-1/4S5 BT. RAISED STONE MND. 3 FT. DIAM. TO CAP.
5	T19SR29E S6 S5 S7 S8 LS 1026 1984	3-5&6 M.V. 18°30'E.	FOUND BASALT STONE 18"X18"X9" FIRMLY SET IN STONE MND. 2 FT. DIAM. CONSISTING OF 7 OTHER STONES. STONE MARKED WITH 5 GROOVES SOUTH FACE AND 5 GROOVES EAST FACE.	BT'S MARKED: 15" JUNIPER, S40°W, 78.3 FT., SCRIBED-T19SR29ES7BT; 16" POND. PINE, S41°00'E, 76.4 FT., SCRIBED-T19SR29ES8BT; 11" JUNIPER, N64°30'E, 35.6 FT., SCRIBED-T19S R29ES5BT; 9" POND. PINE, N81°00'W, 71.5 FT., SCRIBED-T19SR29ES6BT. RAISED STONE MND. 4 FT. DIAM. TO CAP.

RECORDATION
OFFICE OF COUNTY SURVEYOR,
COUNTY OF Grant,
STATE OF OREGON. I HEREBY
CERTIFY THAT THE WITHIN IN-
STRUMENT WAS FILED FOR RECORD
ON THE 18 DAY OF Jan,
1985.

Robert D. Bayett
COUNTY SURVEYOR

SURVEY FOR SUBDIVISION OF SECTION 6, TOWNSHIP
19 SOUTH, RANGE 29 EAST, W.M., HARNEY COUNTY,
OREGON
MALHEUR NATIONAL FOREST
DON CADASTRAL SURVEY-BURNS RANGER DISTRICT
CONTRACT NO. 53-04H1-3-9357N

ARMSTRONG SURVEYING & ENGINEERING, INC.
378 EAST SECOND STREET
PRINEVILLE, OREGON 97754
503/447-7791

SHEET 2 OF 4

REGISTERED
PROFESSIONAL
LAND SURVEYOR

David B. Armstrong
11/9/85 OREGON
AUGUST 22, 1975
DAVID B. ARMSTRONG
1026

W.O. 83-414 A

MAP OF SURVEY NO. 854