

COR. NO.	CAP MARKINGS	FIELD BOOK-PAGE/DECL.	EVIDENCE FOUND	CORNER ACCESSORIES
6	T19SR29E 1/4 S6 S7 LS 1026 1984	3-13&14 M.V. 18°30'E.	FND. BASALT STONE 20"X18"X10" MARKED "1/4" ON SOUTH FACE FIRMLY SET IN CENTER OF 3 FT. DIAM. STONE MND. CONSISTING OF 6 OTHER STONES.	BT'S MARKED: 6" POND. PINE, N2°30'W, 21.7 FT., SCRIBED-1/4S6BT; 12" DOUGLAS FIR, S55°30'W, 8.7 FT., SCRIBED-1/4S7 BT. RAISED STONE MND. 3 1/2 FT. DIAM. TO CAP.
7	T19S R28ER29E S1 S6 S12 S7 LS 1026 1984	3-11&12 M.V. 18°30'E.	FND. BASALT STONE 17"X10"X6" IN STONE MND. CONSISTING OF APPROX. 7 OTHER STONES. STONE FALLEN OVER TO WEST. WHEN UPRIGHT STONE MKD. 5 NOTCHES ON S. EDGE AND 1 NOTCH N. EDGE.	BT'S MARKED: 8" JUNIPER, S64°15'E, 72.3 FT., SCRIBED-T19SR29ES7BT; 17" POND. PINE, N41°00'E, 58.3 FT., SCRIBED-T19SR29ES6BT; 5" JUNIPER, N44°45'W, 129.7 FT., SCRIBED-XBT; 9" JUNIPER, S81°30'W, 75.2 FT., SCRIBED-T19SR28ES12BT. RAISED STONE MND. 3 FT. DIAM. TO CAP.
8	T19S R28ER29E 1/4 S1 S6 LS 1026 1984	3-15&16 M.V. 18°30'E.	FND. BASALT STONE 13"X11"X6" FIRMLY SET IN STONE MND. 2 1/2 FT. DIAM. CONSISTING OF APPROX. 12 OTHER STONES. STONE MKD. "1/4" ON EAST FACE.	BT'S MARKED: 14" POND. PINE, S72°30'E, 114.5 FT., SCRIBED-1/4S6BT; 28" POND. PINE, S38°00'W, 53.2 FT., SCRIBED-1/4S1BT. RAISED STONE MND. 3 FT. DIAM. TO CAP.
9	T19SR29E NW1 . S6 1/6 LS 1026 1984	3-35 M.V. 18°30'E.	NOT PREVIOUSLY ESTABLISHED.	BT'S MARKED: 9" POND. PINE, S87°00'W, 33.5 FT., SCRIBED-NW1/16 S6BT; 13" POND. PINE, N22°30'E, 80.4 FT., SCRIBED-NW1/16S6BT. RAISED STONE MND. 3 FT. DIAM. TO CAP.
10	T19SR29E C N1 S6 1/6 C LS 1026 1984	3-36 M.V. 18°30'E.	NOT PREVIOUSLY ESTABLISHED.	BT'S MARKED: 12" POND. PINE, N38°30'E, 19.5 FT., SCRIBED-CN1/16S6BT; 22" & 16" DOUBLE POND. PINE, N65°15'W, 64.9 FT., SCRIBED-CN1/16S6BT. RAISED STONE MND. 4 FT. DIAM. TO CAP.
11	T19SR29E NE1 . S6 1/6 LS 1026 1984	3-37 M.V. 18°30'E.	NOT PREVIOUSLY ESTABLISHED.	BT'S MARKED: 11" JUNIPER, N66°30'W, 37.7 FT., SCRIBED-NE1/16S6BT; 6" JUNIPER, S37°00'E, 59.5 FT., SCRIBED-NE1/16S6BT. RAISED STONE MND. 4 FT. DIAM. TO CAP.
12	T19SR29E E1/16 C — C S6 LS 1026 1984	3-40 M.V. 18°30'E.	NOT PREVIOUSLY ESTABLISHED.	BT'S MARKED: 12" JUNIPER, S51°30'E, 51.5 FT., SCRIBED-CE1/16S6BT; 10" & 9" & 7" TRIPLE JUNIPER, S25°00'W, 55.0 FT., SCRIBED-CE1/16S6BT. RAISED STONE MND. 3 FT. DIAM. TO CAP.
13	T19SR29E SE1 . S6 1/6 LS 1026 1984	3-43 M.V. 18°30'E.	NOT PREVIOUSLY ESTABLISHED.	BT'S MARKED: 17" POND. PINE, N34°30'E, 70.8 FT., SCRIBED-SE1/16S6BT.; 14" POND. PINE, S82°45'E, 24.2 FT., SCRIBED-SE1/16S6BT. RAISED STONE MND. 3 1/2 FT. DIAM. TO CAP.
14	T19SR29E C S1 S6 1/6 C LS 1026 1984	3-42 M.V. 18°30'E.	NOT PREVIOUSLY ESTABLISHED.	BT'S MARKED: 14" POND. PINE, S12°15'W, 16.8 FT., SCRIBED-CS1/16S6BT; 14" POND. PINE, S75°30'W, 92.6 FT., SCRIBED-CS1/16S6BT. RAISED STONE MND. 2 FT. DIAM. TO CAP.
15	T19SR29E SW1 . S6 1/6 LS 1026 1984	3-41 M.V. 18°30'E.	NOT PREVIOUSLY ESTABLISHED.	BT'S MARKED: 7" DOUGLAS FIR, N72°45'W, 27.4 FT., SCRIBED-SW1/16S6BT; 6" DOUGLAS FIR, S24°30'W, 99.6 FT., SCRIBED-SW1/16S6BT. RAISED STONE MND. 3 FT. DIAM. TO CAP.

RECORDATION
OFFICE OF COUNTY SURVEYOR,
COUNTY OF Grant,
STATE OF OREGON. I HEREBY
CERTIFY THAT THE WITHIN IN-
STRUMENT WAS FILED FOR RECORD
ON THE 18 DAY OF Jan,
1985.

Robert D. Baggett
COUNTY SURVEYOR

SURVEY FOR SUBDIVISION OF SECTION 6, TOWNSHIP
19 SOUTH, RANGE 29 EAST, W.M., HARNEY COUNTY,
OREGON
MALHEUR NATIONAL FOREST
DON CADASTRAL SURVEY-BURNS RANGER DISTRICT
CONTRACT NO. 53-04H1-3-9357N

ARMSTRONG SURVEYING & ENGINEERING, INC.
378 EAST SECOND STREET
PRINEVILLE, OREGON 97754
503/447-7791

SHEET 3 OF 4

REGISTERED
PROFESSIONAL
LAND SURVEYOR

David B. Armstrong

1/9/85 OREGON
AUGUST 22, 1973
DAVID B. ARMSTRONG
1026

W.O. 83-414A

MAP OF SURVEY NO. 854