

COR. NO.	CAP MARKINGS	FIELD BOOK-PAGE/DECL.	EVIDENCE FOUND	CORNER ACCESSORIES
16	T19SR29E W1/16 C \rightarrow C S6 LS 1026 1984	3-38 M.V. 18°30'E.	NOT PREVIOUSLY ESTABLISHED.	BT'S MARKED: 9" POND. PINE, S42°00'W, 24.5 FT., SCRIBED-CW1/16S6BT; 6" DOUGLAS FIR, N44°30'W, 25.2 FT., SCRIBED- CW1/16S6BT. RAISED STONE MND. 3 FT. DIAM. TO CAP.
17	T19SR29E C1/4 S6 LS 1026 1984	3-39 M.V. 18°30'E.	NOT PREVIOUSLY ESTABLISHED.	BT'S MARKED: 5" POND. PINE, S11°00'E, 30.9 FT., SCRIBED-C1/4S6BT; 7" POND. PINE, N87°00'W, 83.4 FT., SCRIBED- C1/4S6BT. RAISED STONE MND. 2 FT. DIAM. TO CAP.

CORNER NOTES

BOOK AND PAGE NUMBERS REFER TO FIELD BOOK AND PAGE. ALL CORNER MONUMENTS SET ARE 2 1/2 INCH O.D. ALUMINUM PIPE 30 INCHES LONG WITH 3 1/4 INCH ALUMINUM CAP MARKED AS PER CORNER DIAGRAM. ALL BEARING TREES ARE SCRIBED AS PER B.L.M. MANUAL OF INSTRUCTIONS, 1973, WITH THE ADDITION OF A BRASS WASHER MARKED "AS&E LS1026" NAILED IN LOWER BLAZE. BEARINGS TO BEARING TREES ARE BY STAFF COMPASS USING DECLINATION AS NOTED, DISTANCES ARE MEASURED TO CENTER SIDE OF BEARING TREE. SEE ALSO ACCOMPANYING CERTIFIED RECORD OF LAND CORNER MONUMENTATION FOR ALL CORNERS SET OR MAINTAINED. THIS CORNER RECORD SHOULD BE CONSULTED FOR A MORE COMPLETE DESCRIPTION OF EVIDENCE FOUND AND MONUMENTATION OF CORNER.

SURVEYOR'S CERTIFICATION

I, DAVID B. ARMSTRONG, A REGISTERED PROFESSIONAL LAND SURVEYOR IN THE STATE OF OREGON, ON THE BASIS OF MY KNOWLEDGE, INFORMATION, AND BELIEF, CERTIFY THAT THIS PLAT, SURVEY NARRATIVE, AND CERTIFIED CORNER RECORDS AND/OR NOTES ARE A CORRECT REPRESENTATION OF A SURVEY PERFORMED DURING JUNE-SEPTEMBER, 1984, AT THE REQUEST OF THE U.S.D.A., FOREST SERVICE, IN ACCORDANCE WITH STATUTES OF THE STATE OF OREGON AND ARTICLES OF CONTRACT NO. 53-04H1-3-9357N WITH ARMSTRONG SURVEYING & ENGINEERING, INC..

RECORDATION
OFFICE OF COUNTY SURVEYOR,
COUNTY OF Grant,
STATE OF OREGON. I HEREBY
CERTIFY THAT THE WITHIN IN-
STRUMENT WAS FILED FOR RECORD
ON THE 18 DAY OF Jan,
1985.
Robert D. Leggett
COUNTY SURVEYOR

SURVEY FOR SUBDIVISION OF SECTION 6, TOWNSHIP
19 SOUTH, RANGE 29 EAST, W.M., HARNEY COUNTY,
OREGON
MALHEUR NATIONAL FOREST
DON CADASTRAL SURVEY-BURNS RANGER DISTRICT
CONTRACT NO. 53-04H1-3-9357N
ARMSTRONG SURVEYING & ENGINEERING, INC.
378 EAST SECOND STREET
PRINEVILLE, OREGON 97754
503/447-7791

SHEET 4 OF 4

REGISTERED
PROFESSIONAL
LAND SURVEYOR

David B. Armstrong
1/9/85 OREGON
AUGUST 22, 1973
DAVID B. ARMSTRONG
1026

W.O. 83-414A

MAP OF SURVEY NO. 854