

GENERAL SURVEY NOTES

1. SURVEY FIELD NOTES ARE ON FILE IN THE OFFICE OF ARMSTRONG SURVEYING & ENGINEERING, INC., 378 EAST SECOND STREET, PRINEVILLE, OREGON.
2. BASIS OF BEARINGS - BEARINGS FOR THIS SURVEY ARE BASED ON SOLAR OBSERVATION TAKEN ALONG THE WEST LINE OF SECTION 36 NEAR THE NORTHWEST CORNER AND VERIFIED BY A SECOND SOLAR OBSERVATION TAKEN ALONG THE WEST LINE NEAR THE SOUTHWEST CORNER OF SECTION 36,
3. GENERAL LAND OFFICE RECORD FOR SOUTH LINE SECTION 36 FROM OFFICIAL NOTES AND PLAT BY JAMES P. CURRIN, DEPUTY SURVEYOR, UNDER GENERAL LAND OFFICE CONTRACT NO. 348 DATED JANUARY 22, 1880 AND PERFORMED DURING THAT YEAR.
4. GENERAL LAND OFFICE RECORD FOR WEST AND NORTH LINES SECTION 36 FROM OFFICIAL NOTES AND PLAT BY HENRY W. COOKE, DEPUTY SURVEYOR, UNDER GENERAL LAND OFFICE CONTRACT NO. 494 DATED JANUARY 16, 1884 AND PERFORMED DURING THAT YEAR.
5. GENERAL LAND OFFICE RECORD FOR EAST LINE SECTION 36 FROM OFFICIAL NOTES AND PLAT BY BAMFORD ROBB, DEPUTY SURVEYOR, UNDER GENERAL LAND OFFICE CONTRACT NO. 366 DATED AUGUST 18, 1880 AND PERFORMED DURING THAT YEAR.
6. SURVEY INFORMATION - SEE ACCOMPANYING SHEETS OF CORNER ACCESSORY INFORMATION; ACCOMPANYING CERTIFIED RECORDS OF LAND CORNER MONUMENTATION FOR ALL CORNERS SET DURING THIS SURVEY, A TOTAL OF 8; AND ATTACHED SURVEY NARRATIVE FOR ADDITIONAL INFORMATION ON PROCEDURES AND/OR CONDITIONS ENCOUNTERED DURING THIS SURVEY.

CORNER SUMMARY

COR. NO.	CAP MARKINGS	FIELD BOOK-PAGE/DECL.	EVIDENCE FOUND	CORNER ACCESSORIES
1	T18S R28E29E S36 S31 S1 S6 T19S LS 1026 1984	3-17&18 M.V. 18°30'E.	FND. BASALT STONE 17"X13"X6" FIRMLY SET IN STONE MND. 3 FT. DIAM. CONSISTING OF 15 OTHER STONES. STONE MARKED WITH 6 NOTCHES SE & SW EDGES.	BT'S MARKED: 7" POND. PINE, N28°30'E, 15.6 FT., SCRIBED-T18SR29ES31BT; 19" POND. PINE, S55°30'E, 38.0 FT., SCRIBED-T19SR29ES6BT; 10" POND. PINE, N40°30'W, 59.8 FT., SCRIBED-T18SR28ES36BT; 13" DOUGLAS FIR, S63°00'W, 21.7 FT., SCRIBED-T19SR28ES1BT. RAISED STONE MND. 3 FT. DIAM. TO CAP.
2	T18SR28E 1 S36 4 S1 T19S LS 1026 1984	3-27&28 M.V. 18°30'E.	FND. BASALT STONE 14"X7"X4" MARKED "1/4" ON TOP FACE. NO STONE MND. PRESENT.	BT'S MARKED: 10" DOUG. FIR, N68°00'E, 16.1 FT., SCRIBED-1/4S36BT; 8" DOUGLAS FIR, S18°00'E, 12.4 FT., SCRIBED-1/4S1BT. RAISED STONE MND. 2 1/2 FT. DIAM. TO CAP.
3	T18SR28E S35 S36 S2 S1 T19S LS 1026 1984	3-25&26 M.V. 18°30'E.	FND. BASALT STONE 17"X11"X4" LYING FLAT AT BASE 13" DOUGLAS FIR. FND. STONE MND. CONSISTING OF 10 STONES AROUND TREE AND STONE. STONE MARKED WITH 6 NOTCHES ON EDGE. FND. ORIG. BT, 12" DIAM. 7 FT. HIGH POND. PINE SNAG VISIBLE SCRIBING-T19SS2R28EBT., BRS. S50°30'W, 17.3 FT..	BT'S MARKED: 10" POND. PINE, N54°00'E, 75.3 FT., SCRIBED-T18SR28ES36BT; 9" POND. PINE, S75°30'E, 103.7 FT., SCRIBED-T19SR28ES1BT; 9" DOUG. FIR, S36°45'W, 44.2 FT., SCRIBED-T19SR28ES2BT; 13" DOUG. FIR, N41°30'W, 1.7 FT., SCRIBED-T18SR28ES35BT. RAISED STONE MND. 2 1/2 FT. DIAM. TO CAP.
4	T18SR28E 1/4 S35 S36 LS 1026 1984	3-29&30 M.V. 18°30'E.	FND. BASALT STONE 19"X16"X12" SET IN STONE MND. 3 1/2 FT. DIAM. CONSISTING OF 20 OTHER STONES. STONE MARKED "1/4" ON W. FACE. FND. ORIG. BT'S: A 20" POND. PINE DEAD & DOWN & ROTTEN BRS. N17°25'E, 36.0 FT. TO ROOT HOLE; A 25" POND. PINE SNAG 6 FT. HIGH BRS. S63°30'E, 53.0 FT. TO FACE, V.S.-1/4SBT.	BT'S MARKED: 9" JUNIPER, N46°30'E, 13.3 FT., SCRIBED-1/4S36BT; 12" JUNIPER, N87°00'W, 15.2 FT., SCRIBED-1/4S35BT. RAISED STONE MND. 4 FT. DIAM. TO CAP.

RECORDATION
OFFICE OF COUNTY SURVEYOR,
COUNTY OF Grant,
STATE OF OREGON. I HEREBY
CERTIFY THAT THE WITHIN IN-
STRUMENT WAS FILED FOR RECORD
ON THE 18 DAY OF Jan,
1982.
Robert D. Dwyer
COUNTY SURVEYOR

SURVEY OF EXTERIOR LINES OF SECTION 36, TOWN-
SHIP 18 SOUTH, RANGE 28 EAST, W.M., GRANT
COUNTY, OREGON
MALHEUR NATIONAL FOREST
DON CADASTRAL SURVEY-BURNS RANGER DISTRICT
CONTRACT NO. 53-04H1-3-9357N
ARMSTRONG SURVEYING & ENGINEERING, INC.
378 EAST SECOND STREET
PRINEVILLE, OREGON 97754
503/447-7791 SHEET 2 OF 3

REGISTERED
PROFESSIONAL
LAND SURVEYOR

David B. Armstrong
1/9/85 OREGON
AUGUST 22, 1975
DAVID B. ARMSTRONG
1026

W. O. 83-414B