

| COR. NO. | CAP MARKINGS | FIELD BOOK-PAGE/DECL. | EVIDENCE FOUND | CORNER ACCESSORIES |
|----------|---|-----------------------------|---|--|
| 5 | T18SR28E S26 S25 S35 S36 LS 1026 1984 | 3-31&32 M.V. 18°30'E. | FND. BASALT STONE 16"X12"X10" IN STONE MND. 2 1/2 FT. DIAM. CONSISTING OF 19 OTHER STONES. STONE HAD POSSIBLE SINGLE MARKS ON 2 FACES. FND. ORIG. BT'S: 10" POND. PINE DEAD & DOWN BRS. N44°E, 31.0 FT., V.S.-T18SR28ES25BT; 18" DOUG. FIR DEAD & DOWN BRS. N15°00'W, 31.1 FT., V.S.-T18SR2; 20" POND. PINE BRS. S37°30'W, 46.2 FT., HEALED FACE. | BT'S MARKED: 9" DOUG. FIR, N60°15'E, 9.9 FT., SCRIBED-T18SR28ES25BT; 10" DOUG. FIR, S23°00'E, 18.6 FT., SCRIBED-T18SR28ES36BT; 6" WHITE FIR, N42°15'W, 15.4 FT., SCRIBED-T18SR28ES26BT. RAISED STONE MND. 2 FT. DIAM. TO CAP. |
| 6 | T18SR28E 1 S25 4 S36 LS 1026 1984 | 3-33&34 M.V. 18°30'E. | FND. BASALT STONE 20"X15"X9" IN STONE MND. 2 1/2 FT. DIAM. CONSISTING OF 5 OTHER STONES. STONE MARKED "1/4" ON N. FACE. FND. ORIG. BT'S: 22" DOUG. FIR BRS. S53°15'E, 29.1 FT., FACES HEALED; 16" DOUG. FIR DEAD & DOWN BRS. N53°00'E, 23.5 FT. TO ROOT HOLE, V.S.-1/4BT. | BT'S MARKED: 15" JUNIPER, N9°30'E, 46.2 FT., SCRIBED-1/4S25BT. RAISED STONE MND. 2 FT. DIAM. TO CAP. |
| 7 | T18S R28ER29E S25 S30 S36 S31 LS 1026 1984 | 3-23&24 M.V. 18°30'E. | FND. BASALT STONE 18"X9"X6" IN 3 1/2 FT. DIAM. STONE MND CONSISTING OF 17 OTHER STONES. STONE MARKED 1 GROOVE S. FACE & 5 GROOVES E. FACE. FND. ORIG. BT: 7" MAHOGANY DEAD & STANDING BRS. S19°00'W, 6.3 FT., V.S.-S36T18R28. | BT'S MARKED: 11" POND. PINE, N27°30'E, 42.4 FT., SCRIBED-T18SR29ES30BT; 10" JUNIPER, S11°30'E, 24.2 FT., SCRIBED-T18SR29ES31BT; 11" JUNIPER, S29°15'W, 67.6 FT., SCRIBED-T18SR28ES36BT; 11" JUNIPER, N32°00'W, 39.9 FT., SCRIBED-T18SR28ES25BT. RAISED STONE MND. 4 FT. DIAM. TO CAP. |
| 8 | T18S R28ER29E 1/4 S36 S31 LS 1026 1984 | 3-21&22 M.V. 18°30'E. | NO ORIGINAL EVIDENCE FOUND. SET CORNER BY SINGLE PROPORTION. | BT'S MARKED: 7" JUNIPER, S75°30'E, 12.6 FT., SCRIBED-1/4S31BT; 7" POND. PINE, S9°00'W, 19.4 FT., SCRIBED-1/4S36BT. RAISED STONE MND. 3 1/2 FT. DIAM. TO CAP. |

CORNER NOTES

BOOK AND PAGE NUMBERS REFER TO FIELD BOOK AND PAGE.. ALL CORNER MONUMENTS SET ARE 2 1/2 INCH O.D. ALUMINUM PIPE 30 INCHES LONG WITH 3 1/4 INCH ALUMINUM CAP MARKED AS PER CORNER DIAGRAM. ALL BEARING TREES ARE SCRIBED AS PER B.L.M. MANUAL OF INSTRUCTIONS, 1973, WITH THE ADDITION OF A BRASS WASHER MARKED "AS&E LS1026" NAILED IN LOWER BLAZE. BEARINGS TO BEARING TREES ARE BY STAFF COMPASS USING DECLINATION AS NOTED, DISTANCES ARE MEASURED TO CENTER SIDE OF BEARING TREE. SEE ALSO ACCOMPANYING CERTIFIED RECORD OF LAND CORNER MONUMENTATION FOR ALL CORNERS SET OR MAINTAINED. THIS CORNER RECORD SHOULD BE CONSULTED FOR A MORE COMPLETE DESCRIPTION OF EVIDENCE FOUND AND MONUMENTATION OF CORNER.

SURVEYOR'S CERTIFICATION

I, DAVID B. ARMSTRONG, A REGISTERED PROFESSIONAL LAND SURVEYOR IN THE STATE OF OREGON, ON THE BASIS OF MY KNOWLEDGE, INFORMATION, AND BELIEF, CERTIFY THAT THIS PLAT, SURVEY NARRATIVE AND CERTIFIED CORNER RECORDS AND/OR NOTES ARE A CORRECT REPRESENTATION OF A SURVEY PERFORMED DURING JUNE-SEPTEMBER, 1984, AT THE REQUEST OF THE U.S.D.A., FOREST SERVICE, IN ACCORDANCE WITH STATUTES OF THE STATE OF OREGON AND ARTICLES OF CONTRACT NO. 53-04H1-3-9357N WITH ARMSTRONG SURVEYING & ENGINEERING, INC..

RECORDATION
OFFICE OF COUNTY SURVEYOR,
COUNTY OF Grant,
STATE OF OREGON. I HEREBY
CERTIFY THAT THE WITHIN IN-
STRUMENT WAS FILED FOR RECORD
ON THE 18 DAY OF Jan,
1985.
Robert D. Layth
COUNTY SURVEYOR

SURVEY OF EXTERIOR LINES OF SECTION 36, TOWN-
SHIP 18 SOUTH, RANGE 28 EAST, W.M., GRANT
COUNTY, OREGON
MALHEUR NATIONAL FOREST
DON CADASTRAL SURVEY-BURNS RANGER DISTRICT
CONTRACT NO. 53-04H1-3-9357N

ARMSTRONG SURVEYING & ENGINEERING, INC.
378 EAST SECOND STREET
PRINEVILLE, OREGON 97754
503/447-7791 SHEET 3 OF 3

REGISTERED
PROFESSIONAL
LAND SURVEYOR

David B. Armstrong
1/9/85 OREGON
AUGUST 22, 1975
DAVID B. ARMSTRONG
1026

W.O. 83-414B