

GENERAL SURVEY NOTES

1. SURVEY FIELD NOTES ARE ON FILE IN THE OFFICE OF ARMSTRONG SURVEYING & ENGINEERING, INC., 378 EAST SECOND STREET, PRINEVILLE, OREGON.
2. BASIS OF BEARINGS - BEARINGS FOR THIS SURVEY ARE BASED ON SOLAR OBSERVATION TAKEN AT THE SECTION CORNER COMMON TO SECTIONS 33, 34, 3 AND 4.
3. GENERAL LAND OFFICE RECORD FOR TOWNSHIP LINE BETWEEN T.18S., R.28E. AND T.19S., R.28E., W.M., FROM OFFICIAL NOTES AND PLAT BY JAMES P. CURRIN, DEPUTY SURVEYOR, UNDER GENERAL LAND OFFICE CONTRACT NO. 348 DATED JANUARY 22, 1880, AND PERFORMED DURING THAT YEAR.
4. SURVEY INFORMATION - SEE ACCOMPANYING SHEET OF CORNER ACCESSORY INFORMATION; ACCOMPANYING CERTIFIED RECORDS OF LAND CORNER MONUMENTATION FOR ALL CORNERS SET DURING THIS SURVEY, A TOTAL OF 6; AND ATTACHED SURVEY NARRATIVE FOR ADDITIONAL INFORMATION OR PROCEDURES AND/OR CONDITIONS ENCOUNTERED DURING THIS SURVEY.

CORNER SUMMARY

COR. NO.	CAP MARKINGS	FIELD BOOK-PAGE/DECL.	EVIDENCE FOUND	CORNER ACCESSORIES
1	T18SR28E S33 S34 S4 S3 T19S LS 1026 1984	5-5&6 M.V. 18°30'E.	FND. BASALT STONE 12"X12"X9" FIRMLY SET 3" IN GRND. IN STONE MND. 2 1/2 FT. DIAM. CONSISTING OF 14 OTHER SMALL STONES. ORIG. STONE MARKED 3 GROOVES E. FACE & 6 GROOVES SOUTH EDGE.	BT'S MARKED: 14" POND. PINE, N37°00'E, 108.6 FT., SCRIBED-T18SR28ES34BT; 6" POND. PINE, S57°45'E, 55.2 FT., SCRIBED-T19SR28ES3BT; 8" POND. PINE, S52°30'W, 70.2 FT., SCRIBED-T19SR28ES4BT; 5" POND. PINE, N47°30'W, 36.8 FT., SCRIBED-XBT. RAISED STONE MOUND 3 1/2 FT. DIAM. TO CAP.
2	T18SR28E 1 S33 4 S4 T19S LS 1026 1984	5-7&8 M.V. 18°30'E.	FND. SANDSTONE 11"X7"X5" LYING FLAT MARKED "1/4" ON DOWN FACE. FND. 3 OTHER SMALL STONES ALONG-SIDE MARKED STONE WHICH WAS SODDED IN ABOUT EVEN WITH GRND. SURFACE.	BT'S MARKED: 18" POND. PINE, N83°00'E, 91.4 FT., SCRIBED-1/4S33BT; 17" POND. PINE, S14°30'W, 20.0 FT., SCRIBED-1/4S4BT. RAISED STONE MND. 2 1/2 FT. DIAM. TO CAP.
3	T18SR28E S32 S33 S5 S4 T19S LS 1026 1984	5-9&10 M.V. 18°30'E.	NO ORIGINAL EVIDENCE FOUND. CORNER FALLS ON STEEP 60% SOUTH SLOPE COMPOSED OF DISINTEGRATING SANDSTONE ERODING DOWNHILL. RE-ESTABLISHED BY SINGLE PROPORTION.	BT'S MARKED: 14" JUNIPER, N9°00'E, 95.8 FT., SCRIBED-T18SR28ES33BT; 22" JUNIPER, S6°00'E, 165.2 FT., SCRIBED-T19SR28ES4BT; 12" JUNIPER, S43°30'W, 77.9 FT., SCRIBED-T19SR28ES5BT; 20" JUNIPER, N73°30'W, 72.6 FT., SCRIBED-T18SR28ES32BT. RAISED STONE MND. 3 FT. DIAM. TO CAP.
4	T18SR28E 1 S32 4 S5 T19S LS 1026 1984	5-11&12 M.V. 18°30'E.	FND. SANDSTONE 14"X12"X11" LYING LOOSE ON TOP OF DIRT & LOOSE ROCK SLIDE NEAR TOE BREAK OF STEEP HILL S.E. SLOPE, MARKED-"1/4" ON TOP FACE. STONE DISTURBED BY EROSION PROCESSES & CORNER LOST. RE-ESTABLISHED BY SINGLE PROPORTION.	BT'S MARKED: 7" JUNIPER, N5°00'W, 100.2 FT., SCRIBED-1/4S32BT; 22" POND. PINE, S78°45'W, 20.1 FT., SCRIBED-1/4S5BT. RAISED STONE MND. 2 FT. DIAM. TO CAP.
5	T18SR28E S31 S32 S6 S5 T19S LS 1026 1984	5-13&14 M.V. 18°30'E.	NO ORIGINAL EVIDENCE FOUND. CORNER FALLS ON STEEP 50-60% SOUTH SLOPE COMPOSED OF DISINTEGRATING SANDSTONE ERODING DOWNHILL. RE-ESTABLISHED BY SINGLE PROPORTION.	BT'S MARKED: 16" POND. PINE, N36°30'E, 27.2 FT., SCRIBED-T18SR28ES32BT; 12" POND. PINE, S45°00'E, 60.9 FT., SCRIBED-T19SR28ES5BT; 20" JUNIPER, S59°30'W, 70.3 FT., SCRIBED-T19SR28ES6BT; 8" JUNIPER, N24°00'W, 56.1 FT., SCRIBED-T18SR28ES31BT. RAISED STONE MND. 2 1/2 FT. DIAM. TO CAP.

RECORDATION

OFFICE OF COUNTY SURVEYOR,
COUNTY OF Grant,
STATE OF OREGON. I HEREBY
CERTIFY THAT THE WITHIN INSTRUMENT WAS FILED FOR RECORD
ON THE 18 DAY OF Jan,
1985.

Robert D. Baggett
COUNTY SURVEYOR

SURVEY RETRACEMENT OF TOWNSHIP LINE COMMON TO
SECTIONS 4, 5 AND 6, T.19S., R.28E., W.M., AND
SECTIONS 31, 32 AND 33, T.18S., R.28E., W.M.,
HARNEY AND GRANT COUNTIES, OREGON
MALHEUR NATIONAL FOREST
DON CADASTRAL SURVEY-BURNS RANGER DISTRICT
CONTRACT NO. 53-04H1-3-9357N
ARMSTRONG SURVEYING & ENGINEERING, INC.
378 EAST SECOND STREET
PRINEVILLE, OREGON 97754
503/447-7791

SHEET 2 OF 3

REGISTERED
PROFESSIONAL
LAND SURVEYOR

David B. Armstrong

1/9/85 OREGON
AUGUST 22, 1975
DAVID B. ARMSTRONG
1026

W.O.83-414D

MAP OF SURVEY NO. 856