

COR. NO.	CAP MARKINGS	FIELD BOOK-PAGE/DECL.	EVIDENCE FOUND	CORNER ACCESSORIES
6	T18SR28E 1 S31 4 S6 T19S LS 1026 1984	5-69&70 M.V. 18°30'E.	FND. SANDSTONE 14"X8"X7" LYING FLAT IN STONE MND. 2 FT. DIAM. CONSISTING OF 10 OTHER STONES. ORIG. STONE BROKEN IN HALF BELOW MARKS WITH CLEAR MARKING "4" ON TOP FACE OF STONE. LARGER HALF STONE CONTAINS MARKS, NOW MEASURES 6"X8"X7".	BT'S MARKED: 20" JUNIPER, N51°00'W, 31.3 FT., SCRIBED-1/4S31BT; 27" PONDEROSA PINE, S21°00'W, 24.3 FT., SCRIBED-1/4S6BT. RAISED STONE MND. 4 FT. DIAM. TO CAP.

#### CORNER NOTES

BOOK AND PAGE NUMBERS REFER TO FIELD BOOK AND PAGE. ALL CORNER MONUMENTS SET ARE 2 1/2 INCH O.D. ALUMINUM PIPE 30 INCHES LONG WITH 3 1/4 INCH ALUMINUM CAP MARKED AS PER CORNER DIAGRAM. ALL BEARING TREES ARE SCRIBED AS PER B.L.M. MANUAL OF INSTRUCTIONS, 1973, WITH THE ADDITION OF A BRASS WASHER MARKED "AS&E LS1026" NAILED IN LOWER BLAZE. BEARINGS TO BEARING TREES ARE BY STAFF COMPASS USING DECLINATION AS NOTED, DISTANCES ARE MEASURED TO CENTER SIDE OF BEARING TREE. SEE ALSO ACCOMPANYING CERTIFIED RECORD OF LAND CORNER MONUMENTATION FOR ALL CORNERS SET OR MAINTAINED. THIS CORNER RECORD SHOULD BE CONSULTED FOR A MORE COMPLETE DESCRIPTION OF EVIDENCE FOUND AND MONUMENTATION OF CORNER.

#### SURVEYOR'S CERTIFICATION

I, DAVID B. ARMSTRONG, A REGISTERED PROFESSIONAL LAND SURVEYOR IN THE STATE OF OREGON, ON THE BASIS OF MY KNOWLEDGE, INFORMATION, AND BELIEF, CERTIFY THAT THIS PLAT, SURVEY NARRATIVE AND CERTIFIED CORNER RECORDS AND/OR NOTES ARE A CORRECT REPRESENTATION OF A SURVEY PERFORMED DURING JUNE-SEPTEMBER, 1984, AT THE REQUEST OF THE U.S.D.A., FOREST SERVICE, IN ACCORDANCE WITH STATUTES OF THE STATE OF OREGON AND ARTICLES OF CONTRACT NO. 53-04H1-3-9357N WITH ARMSTRONG SURVEYING & ENGINEERING, INC..

RECORDATION  
OFFICE OF COUNTY SURVEYOR,  
COUNTY OF Grant,  
STATE OF OREGON. I HEREBY  
CERTIFY THAT THE WITHIN IN-  
STRUMENT WAS FILED FOR RECORD  
ON THE 18 DAY OF Jan,  
1985.

Robert D. Begett  
COUNTY SURVEYOR

SURVEY RETRACEMENT OF TOWNSHIP LINE COMMON TO  
SECTIONS 4, 5 AND 6, T.19S., R.28E., W.M., AND  
SECTIONS 31, 32 AND 33, T.18S., R.28E., W.M.,  
HARNEY AND GRANT COUNTIES, OREGON  
MALHEUR NATIONAL FOREST  
DON CADASTRAL SURVEY-BURNS RANGER DISTRICT  
CONTRACT NO. 53-04H1-3-9357N

ARMSTRONG SURVEYING & ENGINEERING, INC.  
378 EAST SECOND STREET  
PRINEVILLE, OREGON 97754  
503/447-7791

SHEET 3 OF 3

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

David B. Armstrong

1/9/85 OREGON  
AUGUST 22, 1975  
DAVID B. ARMSTRONG  
1026

W.O. 83-414D