

National Forest Lands

Township 12 South, Range 28 East

Section 10
Section 11
Section 12
The Northeast 1/4 of Section 13

Township 12 South, Range 29 East

Section 7
Section 8
Section 9

History of Surveys

The exterior of Township 12 South, Range 28 East was established by W.N. Byars under GLO contract number 185, dated May 7, 1873.

The North line of Township 12 South, Range 28 East was retraced by Aaron F. York under GLO contract number 371, dated September 8, 1880.

The North line of Township 12 South, Range 28 East was retraced and Township 12 South, Ranges 28 and 29 East were subdivided by William R. Gradon under GLO contract number 497, dated March 7, 1884.

In 1914 Vernon Glaze, Grant County Surveyor, set a brass cap monument from original GLO corner evidence at the South 1/4 corner and the Southwest corner of Section 13, Township 12 South, Range 28 East. He also set these monuments erroneously at the East and West 1/4 corners and the Southeast corner of said Section. (See narrative filed in conjunction with this survey).

In the summer of 1958, Howard E. Taylor registered engineer no. 2891 found original GLO evidence at the Northeast and Northwest corners of Section 12 Township 12 South, Range 28 East and took new bearing trees. He found the Southwest corner of Section 36, Township 11 South, Range 28 East in November, 1960, but did no additional work.

The Southwest corner of Section 10, Township 12 South, Range 28 East was monumented by the BLM (C. Albert White, Surveyor) under special instructions dated August 27, 1962, for group number 482, Oregon.


Surveyor's Statement

I, Duane I. Griffith, Registered Land Surveyor in the State of Oregon, hereby certify that this plat and the notes hereon, or attached, are a true and correct representation of the survey I made in September and October, 1984 at the request of the USDA, Forest Service, in accordance with the statutes of the State of Oregon, and with the articles of my contract.

Duane I. Griffith
Bagett, Griffith and Assoc.
P.O. Box 576
La Grande, Oregon 97850

NOTE:
For detailed information concerning the survey decisions relating to this plat, see narrative filed in conjunction with this survey.

Scale: 1" = 1000'



1 Meter = 3.2808333 Feet

BASIS OF BEARING

A.M. Solar observation taken at a point 270 feet South and 15 feet West of the Northeast corner of Section 16, Township 12 South, Range 29 East of the Willamette Meridian.

Date: September 16, 1984
Mean Vertical Angle: 18° 00' 11"
Mean Horizontal Angle: 27° 23' 10"
Mean Declination: 2° 17' 14"
Latitude: 44° 31' 58"
Magnetic Declination: 20° East

LEGEND

- Found original G.L.O. corner evidence and set a 2 1/2" x 30" aluminum monument
- Set 2 1/2" x 30" aluminum monument at position determined by survey
- Found standard BLM brass cap monument
- Found 1" iron pipe with brass cap set by Vernon Glaze, Grant County Surveyor, in 1914
- S.F.N.F. Corner searched for but not found or monumented
- Posted line
- Record G.L.O. bearing and distance

NOTE:
For monumentation information, see remonumentation sheets filed separately.

RECEIVED AND
FILED
JUN 11 1985
OFFICE OF COUNTY SURVEYOR
Attest: *[Signature]*

REGISTERED
PROFESSIONAL
LAND SURVEYOR
OREGON
JULY 10, 1984
DUANE I. GRIFFITH
644

BAGETT - GRIFFITH & ASSOCIATES La Grande, Oregon		
Map of Survey		
Survey in Township 12 South, Ranges 28 and 29 East, Willamette Meridian		
GRANT COUNTY, OREGON		
SURVEYED FOR	Malheur National Forest	
SURVEYED BY	d.i.g.	9+10/84
Scale: 1" = 1000'	Drawn by: r.g.r.	1/85