

RECORD OF SURVEY for the U. S. FOREST SERVICE

MALHEUR NATIONAL FOREST
Sec. 29 and a portion of Secs. 32 & 33, T17S, R32E
Willamette Meridian
Grant County, Oregon
ROAD CADASTRAL SURVEY
21 APRIL 1985

<p>G No evidence of the original stone or accessories found. Corner falls near an irrigation ditch and may have been disturbed during its construction. Reset this corner by single proportion. Set a 3-1/2"x30" aluminum monument 22" in the ground. Set a 2" aluminum cap on iron rod West 25.0 ft for RM stamped T17S R32E 1/4 S31 RM EAST 25.0 FT PLS 1918 1985. Set a 2" aluminum cap on iron rod East 25.0 ft for RM stamped T17S R32E 1/4 S32 RM WEST 25.0 FT PLS 1918 1985.</p>	<p>T17S R32E 1/4 S31: S32 PLS 1918 1985</p>	<p>S Set 3-1/4"x30" aluminum monument 22" in the ground in a mound of stone. Monument is in a swampy area. 9" Ponderosa Pine S140E 213.6 ft scribed CESUNW1/256S29BT. 21" Ponderosa Pine S37-1/20W 117.6 ft scribed CESUNW1/256S29BT.</p>	<p>T17S R32E CESUNW1/256 + S29 PLS 1918 1985</p>		
<p>H Found 16x11x8 lava stone (record 16x12x7 basalt) firmly set, no markings visible. Set a 3-1/4"x30" USDA aluminum monument 22" in the ground and buried the original stone alongside. Set 2" aluminum cap on iron rod N450E 25.0 ft for RM stamped T17S R32E S32 RM S45W 25.0 FT PLS 1918 1985. Set 2" aluminum cap on iron rod N450W 25.0 ft for RM stamped T17S R32E S31 RM S45E 25.0 FT PLS 1918 1985. Set 2" aluminum cap on iron rod S450W 25.0 ft for RM stamped T18S R32E S6 RM N45E 25.0 FT PLS 1918 1985. Set 2" aluminum cap on iron rod S450E 25.0 ft for RM stamped T18S R32E S5 RM N45W 25.0 FT PLS 1918 1985.</p>	<p>T17S R32E S31: S32 ----- S6: S5 T18S PLS 1918 1985</p>	<p>T Set 3-1/4"x30" aluminum monument 15" in the ground in a mound of earth 3 ft base 1 ft high. 12" Ponderosa Pine N23-1/2E 172.2 ft scribed SWNW1/64S29BT. 3-1/4" aluminum monument (CESUNW 1/256) N89055'12"E 331.04 ft.</p>	<p>T17S R32E SWNW 1/64 + S29 PLS 1918 1918</p>	<p>U Set 3-1/4"x30" aluminum monument 24" in the ground. 23" Ponderosa Pine S510W 209.5 ft scribed CUNW1/64S29BT. 3-1/4" aluminum monument (CUNW 1/256) S89055'38"W 331.00 ft.</p>	<p>T17S R32E CUNW 1/64 + S29 PLS 1918 1985</p>
<p>I Found 24x22x7 stone (record 20x20x5) marked 1/4 lying flat on a southeast slope. Set a 3-1/4"x30" aluminum monument in a mound of stone. Placed the original stone in the mound. Set a 2" aluminum cap on iron rod North 25.0 ft for RM stamped T17S R32E S32 RM SOUTH 25.0 FT PLS 1918 1985. Set a 2" aluminum cap on iron rod South 25.0 ft for RM stamped T18S R32E S5 RM NORTH 25.0 FT PLS 1918 1985.</p>	<p>T17S R32E S32 1/4--- S5 T18S PLS 1918 1985</p>	<p>V Set 3-1/4"x30" aluminum monument 15" in the ground in a mound of earth. 14" Ponderosa Pine N160W 67.4 ft scribed CUNW1/256S29BT. 3-1/4" aluminum monument (CUNW 1/256) N89055'38"E 331.00 ft</p>	<p>T17S R32E CUNW1/256 + S29 PLS 1918 1985</p>	<p>AE Set 3-1/4"x30" aluminum monument 22" in the ground. 11" Ponderosa Pine S20-1/20W 90.7 ft scribed SWNESW1/256S29BT. 9" Ponderosa Pine(double) S66-3/40E 90.0 ft scribed SWNESW1/256S29BT.</p>	<p>T17S R32E SWNESW1/256 + S29 PLS 1918 1985</p>
<p>J Found 19x11x7 stone (record 19x10x6), 2 grooves in the west face and 4 grooves in the east face, firmly set. Set a 3-1/4"x30" USDA aluminum monument 22" in the ground in a mound of stone. Placed the original stone in the mound. Set 15" Ponderosa Pine N50-1/20E 206.8 ft scribed T17SR32ES33BT. Set a 2" aluminum cap on iron rod S450E 25.0 ft for RM stamped T18S R32E S4 RM N45W 25.0 FT PLS 1918 1985. Set a 2" aluminum cap on iron rod S450W 25.0 ft for RM stamped T18S R32E S5 RM N45E 25.0 FT PLS 1918 1985. Set a 2" aluminum cap on iron rod N450W 25.0 ft for RM stamped T17S R32E S32 RM S45E 25.0 FT PLS 1918 1985.</p>	<p>T17S R32E S32: S33 ----- S5: S4 T18S PLS 1918 1985</p>	<p>W Set 3-1/4"x30" aluminum monument 22" in the ground in a ring of stones. 6" Ponderosa Pine S44-1/20W 42.7 ft scribed CUNW1/256S29BT. 15" Juniper N47-3/40E 85.4 ft scribed CUNW1/256S29BT.</p>	<p>T17S R32E CUNW1/256 + S29 PLS 1918 1985</p>	<p>AF Set 3-1/4"x30" aluminum monument 22" in the ground in a mound of stone. 15" Ponderosa Pine S51-1/20E 79.9 ft scribed CSNESW1/256S29BT. 14" Ponderosa Pine N20-3/40E 56.0 ft scribed CSNESW1/256S29BT.</p>	<p>T17S R32E CSNESW1/256 + S29 PLS 1918 1985</p>
<p>K Found 3-1/4" USDA aluminum monument in a mound of stone. Fd 16" Ponderosa Pine N120E 80.5 ft scribed 1/4S33BT, with washer "LS 1805". Fd 14" Juniper S730W 46.4 ft, scribed 1/4S4BT, with washer "LS 1805"</p>	<p>T17S R32E S33 1/4--- S4 T18S PLS 1805 1980</p>	<p>X Set 3-1/4"x30" aluminum monument 18" in the ground in a mound of stone. 17" Ponderosa Pine N57-1/20W 28.9 ft scribed CENW1/256S29BT. 7" Ponderosa Pine S81-3/40W 132.2 ft scribed CENW1/256S29BT.</p>	<p>T17S R32E CENW1/256 + S29 PLS 1918 1985</p>	<p>AG Set 3-1/4"x30" aluminum monument 22" in the ground in a mound of stone at the top of a cut bank, east side of FS Rd 11" Ponderosa Pine S52-1/20E 70.8 ft scribed CNSESW1/256S29BT. 7" Ponderosa Pine N19-1/20W 56.9 ft scribed CNSESW1/256S29BT.</p>	<p>T17S R32E CNSESW1/256 + S29 PLS 1918 1985</p>
<p>L Set 3-1/4"x30" aluminum monument 20" in the ground in a mound of stone. 10" Ponderosa Pine S20-1/40E 56.5 ft scribed S1/16S29BT. 2" aluminum cap on rebar West 25.0 ft stamped T17S R32E S1/16 S30 RM EAST 25.0 PLS 1918 1985.</p>	<p>T17S R32E S 1/16 S30: S29 PLS 1918 1985</p>	<p>Y Set 3-1/4"x30" aluminum monument 12" in the ground in a mound of stone. 6" Ponderosa Pine S54-1/20W 56.9 ft scribed CENW1/256S29BT. 3-1/4" aluminum monument (CUNW 1/64) S89055'38"W 331.00 ft.</p>	<p>T17S R32E CENW 1/256 + S29 PLS 1918 1985</p>	<p>AH Set 3-1/2"x30" aluminum monument 15" in the ground in a mound of earth 2-1/2 ft base and 9" high. 10" Ponderosa Pine N37-3/4E 53.3 ft scribed CNSSW1/256S29BT. 13" Ponderosa Pine S40-3/40E 9.9 ft scribed CNSSW1/256S29BT.</p>	<p>T17S R32E CNSSW 1/256 + S29 PLS 1918 1985</p>
<p>M Set 3-1/4"x30" aluminum monument 22" in the ground. 15" Ponderosa Pine S61-1/20W 85.0 ft scribed CUNW1/256S29BT. 10" Ponderosa Pine S13-3/40W 90.5 ft scribed CUNW1/256S29BT.</p>	<p>T17S R32E CUNW1/256 S29 PLS 1918 1985</p>	<p>Z Set 3-1/4"x30" aluminum monument 12" in the ground in a mound of stone. 15" Ponderosa Pine S32-3/40W 247.8 ft scribed NW1/16S29BT. 20" Juniper N480W 153.6 ft scribed NW1/16S29BT.</p>	<p>T17S R32E NW 1/16 + S29 PLS 1918 1918</p>	<p>AI Set 3-1/4"x30" aluminum monument 20" in the ground. 12" Ponderosa Pine S54-1/40E 14.8 ft scribed SW1/16S29BT. 10" Ponderosa Pine S75-1/20W 26.2 ft scribed SW1/16S29BT.</p>	<p>T17S R32E SW 1/16 + S29 PLS 1918 1985</p>
<p>N Set 3-1/4"x30" aluminum monument 15" in the ground in a mound of stone. 15" Ponderosa Pine N83-1/40E 167.9 ft scribed SWNW1/256S29BT. 12" Juniper(double) S42-1/40W 111.0 ft scribed SWNW1/256S29BT.</p>	<p>T17S R32E SWNW1/256 + S29 PLS 1918 1985</p>	<p>AA Set 3-1/4"x30" aluminum monument 12" in the ground in a mound of stone. Set 2" aluminum cap on rebar for RM stamped T17S R32E CNSW1/256 RM SOUTH 22.0 S29 PLS 1918 1985. 3-1/4" aluminum monument (NWSW 1/256) N89055'26"E 331.02 ft.</p>	<p>T17S R32E CNSW1/256 + S29 PLS 1918 1918</p>	<p>AJ Set 3-1/4"x30" aluminum monument 22" in the ground. 10" Ponderosa Pine S87-1/20E 90.0 ft scribed CUNW1/64S29BT. 7" Ponderosa Pine S13-3/40E 86.5 ft scribed CUNW1/64S29BT.</p>	<p>T17S R32E CUNW 1/64 + S29 PLS 1918 1985</p>
<p>O Set 3-1/4"x30" aluminum monument 15" in the ground in a mound of stone. 11" Ponderosa Pine S38-1/20E 71.5 ft scribed CSNW1/256S29BT. 16" Ponderosa Pine N52-3/40E 91.2 ft scribed CSNW1/256S29BT.</p>	<p>T17S R32E CSNW1/256 + PLS 1918 1985</p>	<p>AB Set 3-1/4"x30" aluminum monument 22" in the ground. 8" Ponderosa Pine S40-1/20E 111.4 ft scribed NWSW1/256S29BT. 9" Ponderosa Pine N670E 137.9 ft scribed NWSW1/256S29BT.</p>	<p>T17S R32E NWSW1/256 + S29 PLS 1918 1985</p>	<p>AK Set 3-1/4"x30" aluminum monument 12" in the ground in a mound of earth 3 ft base and 1 ft high. 10" Ponderosa Pine S50E 83.0 ft scribed SWSW1/64S29BT. 10" Ponderosa Pine N720W 94.0 ft scribed SWSW1/64S29BT.</p>	<p>T17S R32E SWSW 1/64 + S29 PLS 1918 1985</p>
<p>P Set 3-1/4"x30" aluminum monument 22" in the ground. 14" Ponderosa Pine N87-1/20E 87.8 ft scribed NWSW1/64S29BT. 3-1/4" aluminum monument (CENW 1/256) N89055'56"E 331.03 ft.</p>	<p>T17S R32E NWSW 1/64 + S29 PLS 1918 1985</p>	<p>AC Set 3-1/4"x30" aluminum monument 22" in the ground in a mound of stone. 15" Ponderosa Pine S300E 66.2 ft scribed CWEW1/256S29BT. 19" Ponderosa Pine N85-1/40W 136.6 ft scribed CWEW1/256S29BT.</p>	<p>T17S R32E CWEW 1/256 + S29 PLS 1918 1985</p>	<p>AL Set 3-1/4"x30" aluminum monument 22" in the ground. 9" Ponderosa Pine S230E 62.8 ft scribed SS1/64S29BT. 11" Juniper S68-1/20W 138.5 ft scribed SS1/64S30BT.</p>	<p>T17S R32E SS 1/64 S30 S29 PLS 1918 1985</p>
<p>Q Set 3-1/4"x30" aluminum monument 22" in the ground in a mound of stone. 13" Ponderosa Pine N40-1/20W 168.5 ft scribed CENW1/256S29BT. 3-1/4" aluminum monument (NWSW 1/64) S89055'56"W 331.03 ft.</p>	<p>T17S R32E CENW 1/256 + S29 PLS 1918 1985</p>	<p>AD Set 3-1/4"x30" aluminum monument 22" in the ground in a mound of stone. 12" Ponderosa Pine S670W 103.5 ft scribed C1/4S29BT. 12" Ponderosa Pine S340E 73.0 ft scribed C1/4S29BT.</p>	<p>T17S R32E C 1/4 + S29 PLS 1918 1985</p>	<p>R Set 3-1/4"x30" aluminum monument 20" in the ground in a mound of stone. 7" Juniper S30-1/40E 204.6 ft scribed CENW1/256S29BT. 4" Juniper N89-3/40E 109.4 ft scribed X BT.</p>	<p>T17S R32E CENW 1/256 + S29 PLS 1918 1985</p>

TYLER B. PARSONS
1915 SE STONE STREET
CORVALLIS, OR 97333
(503) 752-7515



**RECEIVED AND
FILED**

JUN 19 1985

OFFICE OF COUNTY SURVEYOR
Robert B. Hays
Attest: *Carol J. C. Clark*