

GENERAL SURVEY NOTES

1. SURVEY FIELD NOTES ARE ON FILE IN THE OFFICE OF ARMSTRONG SURVEYING & ENGINEERING, INC., 378 EAST SECOND STREET, PRINEVILLE, OREGON.
2. BASIS OF BEARINGS - BEARINGS FOR THIS SURVEY ARE BASED ON SOLAR OBSERVATION TAKEN ALONG THE WEST LINE OF SECTION 19, T.18S., R.28E., W.M., NEAR THE SOUTHWEST CORNER AND VERIFIED BY A SECOND SOLAR OBSERVATION TAKEN ALONG THE EAST LINE OF SECTION 19 AT THE EAST 1/4 CORNER.
3. GENERAL LAND OFFICE RECORD FOR EXTERIOR LINES OF SECTION 19 FROM OFFICIAL NOTES AND PLAT BY BAMFORD ROBB, DEPUTY SURVEYOR, UNDER GENERAL LAND OFFICE CONTRACT NO. 366 DATED AUGUST 18, 1880, AND PERFORMED DURING OCTOBER, 1880.
4. SURVEY INFORMATION - SEE ACCOMPANYING SHEETS OF CORNER ACCESSORY INFORMATION; ACCOMPANYING CERTIFIED RECORDS OF LAND CORNER MONUMENTATION FOR ALL CORNERS SET DURING THIS SURVEY, A TOTAL OF 8; AND ATTACHED SURVEY NARRATIVE FOR ADDITIONAL INFORMATION ON PROCEDURES AND/OR CONDITIONS ENCOUNTERED DURING THIS SURVEY.

CORNER SUMMARY

COR. NO.	CAP MARKINGS	FIELD BOOK-PAGE/DECL.	EVIDENCE FOUND	CORNER ACCESSORIES
1	T18S R28E R29E S13 S18 S24 S19 1980 OPLS 598 SURVEYOR	7-19 M.V. 18°30'E	FOUND 1 1/2" O.D. GALV. IRON PIPE 6" ABOVE GRND. IN CENTER 2 1/2 FT. STONE MOUND WITH 2 1/2" BRASS CAP MARKED AS SHOWN.	FOUND 1980 BT: 12" JUNIPER, N87°W, 186.4 FT. WITH OPEN FACE VISIBLE SCRIBING-S13T18S R28EBT. FOUND REFERENCE MONUMENTS: A 5/8" IRON ROD WITH YELLOW PLASTIC CAP MARKED B-G-A SURVEY MARKER BEARS, N49°W, 10.0 FT.; A 5/8" IRON ROD SAME CAP, BEARS S49°E, 10.0 FT.; A 5/8" IRON ROD, SAME CAP, BEARS S33°W, 10.0 FT..
2	T18SR29E 1 S18 4 S19 LS1026 1985	4/9&10 M.V. 18°30'E	FND. ROUGH STN. 19"x17"x5" MEASURED IN CENTER LYING OVER SUNKEN STN. MND. 3 FT. DIA. CONSISTING OF 5 OTHER STONES. STN. APPEARED TO HAVE ILLEGIBLE MARKS AT END WHICH WOULD HAVE BEEN N. FACE. STN. IS IN OLD N-S FENCE LINE BETWEEN FENCE POSTS. WIRE IS REMOVED AND MOST POSTS ARE DOWN. ACCEPT AS ORIG. COR. BECAUSE OF MND. APPEARANCE & PROPER SIZE & OLD FENCE LINE PERPETUATION. REMONUMENT: SET 2 1/2"x30" ALUM. PIPE 25" IN GRND. TO BEDROCK WITH 3 1/4" ALUM. CAP MARKED AS SHOWN.	BT'S MARKED: 10" JUNIPER, N23°00'E, 61.4 FT., SCRIBED-1/4S18BT; 6" JUNIPER, S70°30'W, 30.4 FT., SCRIBED-1/4S19BT. RAISED 3 FT. DIAMETER STONE MOUND TO CAP.
3	T18SR29E E 1 S18 16 S19 LS1026 1985	4-16 M.V. 18°30'E	CORNER NOT PREVIOUSLY ESTABLISHED. REMONUMENT: SET 2 1/2"x30" ALUM. PIPE 4" IN GROUND TO BEDROCK WITH 3 1/4" ALUM. CAP MARKED AS SHOWN.	BT'S MARKED: 5" JUNIPER, N41°15'W, 14.8 FT., SCRIBED-E1/16S18BT; 8" JUNIPER, S14°30'W, 29.0 FT., SCRIBED-E1/16S19BT. RAISED STONE MOUND 5 FT. DIA. TO CAP.
4	T18SR29E S18 S17 S19 S20 LS1026 1985	4-7&8 M.V. 18°30'E	FND. BASALT STN. 12"x11"x6" SET IN STN. MND. 2 1/2 FT. DIA. CONSISTING OF 5 OTHER STONES. FND. 3 CLEAR AND 2 OTHER POSSIBLE NOTCHES ON E. EDGE & APPARENT "+" CROSS CUT INTO S. FACE. VERY LITTLE SURFACE STN. & MND. APPEARS MAN PLACED. FND. POSSIBLE 3 GROOVES S. FACE ON EXAMINATION 5-13-85. REMONUMENT: SET 2 1/2"x30" ALUM. PIPE 25" IN GRND. WITH 3 1/4" ALUM. CAP MARKED AS SHOWN.	BT'S MARKED: 6" JUNIPER, N18°45'W, 54.3 FT., SCRIBED-T18SR29ES18BT; 16" JUNIPER, N64°15'E, 130.0 FT., SCRIBED-T18SR29ES17BT; 6" JUNIPER, S69°30'E, 124.9 FT., SCRIBED-T18SR29ES20BT; 7" & 4" DBL. JUNIPER, S28°30'W, 109.2 FT., SCRIBED-T18SR29ES19BT. RAISED 2 1/2 FT. STONE MOUND TO CAP.

RECORDATION

OFFICE OF COUNTY SURVEYOR,
COUNTY OF Grant,
STATE OF OREGON. I HEREBY
CERTIFY THAT THE WITHIN INSTRUMENT WAS FILED FOR RECORD
ON THE 15 DAY OF July,
1985.

Robert D. Bayett
COUNTY SURVEYOR

SURVEY FOR SUBDIVISION OF SECTION 19,
TOWNSHIP 18 SOUTH, RANGE 29 EAST, W.M.,
GRANT COUNTY, OREGON
MALHEUR NATIONAL FOREST
DON CADASTRAL SURVEY - BURNS RANGER DISTRICT
CONTRACT NO. 53-04H1-3-9357N

ARMSTRONG SURVEYING & ENGINEERING, INC.
378 EAST SECOND STREET
PRINEVILLE, OREGON 97754
503/447-7791

SHEET 2 OF 4

REGISTERED
PROFESSIONAL
LAND SURVEYOR

David B. Armstrong
7/9/85 OREGON
AUGUST 22, 1975
DAVID B. ARMSTRONG
1026

W.O. 83-414E