

COR. NO.	CAP MARKINGS	FIELD BOOK-PAGE/DECL.	EVIDENCE FOUND	CORNER ACCESSORIES
5	T18S R28ER29E 1/4 S24 S19 1980 OPLS 598	7-6 M.V. 18°30'E	FND. 1 1/2" GALV. IRON PIPE 4" ABOVE GRND. IN CENTER OF 1 1/2 FT. DIA. STN. MND. WITH 2" BRASS CAP MKD. AS SHOWN.	FOUND 1980 BT'S: 6" JUNIPER, S88°W, 185.5 FT., V.S.-1/4S24CSBT; 9" JUNIPER, S49°E, 178.2 FT., SCRIBED-1/4S19 CSBT.
6	T18SR29E C 1/4 . S19 LS1026 1985	4-18 M.V. 18°30'E	COR. NOT PREVIOUSLY ESTAB- LISHED. REMONUMENT: SET 2 1/2"X30" ALUM. PIPE 24" IN GRND. WITH 3 1/4" ALUM. CAP MARKED AS SHOWN.	BT'S MARKED: 9" JUNIPER, S44°15'E, 10.7 FT., SCRIBED-C1/4S19BT; 18" JUNIPER, S51°15'W, 80.0 FT., SCRIBED- C1/4S19BT. RAISED STONE & EARTH MND. 2 FT. DIA. TO CAP.
7	T18SR29E C E 1/16 C S19 LS1026 1985	4-17 M.V. 18°30'E	COR. NOT PREVIOUSLY ESTAB- LISHED. REMONUMENT: SET 2 1/2"X30" ALUM. PIPE 24" IN GRND. WITH 3 1/4" ALUM. CAP MARKED AS SHOWN.	BT'S MARKED: 10" POND. PINE, N75°00'E, 38.3 FT., SCRIBED-CE1/16S19BT; 9" POND. PINE, S13°15'W, 11.3 FT., SCRIBED-CE1/16S19BT. RAISED STN. & EARTH MND. 2 FT. DIA. TO CAP.
8	T18SR29E 1/4 S19 S20 LS1026 1985	4-5&6 M.V. 18°30'E	NO EVIDENCE FND, CORNER VICIN- ITY CONTAINS MUCH SURFACE STN. NO MKD. STNS. NOR STN. MNDS. CONSIDERED ORIG. WHERE FND. COR. DETERMINED LOST & RE- ESTAB. BY SINGLE PROPORTION BETWEEN THE SEC. CORS. REMONUMENT: SET 2 1/2"X30" ALUM. PIPE 13" IN GRND. WITH 3 1/4" ALUM. CAP MARKED AS SHOWN.	BT'S MARKED: 12" POND. PINE, S74°30'E, 44.4 FT., SCRIBED-1/4S20BT; 10" POND. PINE, S57°30'W, 30.2 FT., SCRIBED-1/4S19BT. RAISED STONE MOUND 4 FT. DIAMETER TO CAP.
9	T18S R28ER29E S24 S19 S25 S30 1980 ORLS 598	4-13 M.V. 18°30'E	FOUND 2 1/2" BRASS CAP ON 1 1/4" GALV. IRON PIPE 9" ABOVE GROUND IN CENTER 3 FT. DIA. STONE MOUND.	FOUND ORIGINAL BT: 33" POND. PINE WITH V.S.-S24T18R28 ON UPPER BLAZE, HEALED LOWER BLAZE. BEARS N56°W, 42.1 FT. FOUND 1980 BT'S: 9" POND. PINE, S8°W, 39.0 FT., HEALED FACES; 12" POND. PINE, S42°E, 47.3 FT., HEALED FACES; 12" POND. PINE, N57°E, 61.5 FT., HEALED FACES.
10	T18SR29E 1 S19 4 S30 LS1026 1985	4-11 & 12 M.V. 18°30'E	FND. BASALT STN. 18"X14"X6" LYING FLAT ON GRND. WITH POSSIBLE TOOL MKS. BUT ILLEG- IBLE ON TOP FACE. FND. 3 OTHER STNS. IN SUNKEN MND. E. & N. OF COR. STN. BELIEVE SEVERAL STNS. SCATTERED ABOUT CAME FROM CORNER AREA BUT WERE DISTURBED BY PERSONS UN- KNOWN. OLD FENCE COR. N-W IS 4 FT. N. AND 5 FT. E. OF COR. STN. BELIEVE STN. THE ORIG. COR. AS IT IS PROPER SIZE, NEAR FENCE COR. REPRESENTING PROPERTY COR., REMNANTS OF STN. MND. REMAIN, CORNER IS HARMONIOUSLY RELATED TO SEC. CORS., PARTICULARLY S.E. COR. S.19. REMONUMENT: SET 2 1/2" X30" ALUM. PIPE 14" IN GRND. TO BEDROCK WITH 3 1/4" ALUM. CAP MARKED AS SHOWN.	BT'S MARKED: 10" PONDEROSA PINE, N53°00'W, 17.7 FT., SCRIBED-1/4S19BT; 10" PONDEROSA PINE, S6°30'W, 17.0 FT., SCRIBED-1/4S30BT. RAISED A STONE MOUND 4 FT. DIA. TO CAP.

RECORDATION
OFFICE OF COUNTY SURVEYOR,
COUNTY OF Grant,
STATE OF OREGON. I HEREBY
CERTIFY THAT THE WITHIN IN-
STRUMENT WAS FILED FOR RECORD
ON THE 15 DAY OF July,
1985.

Robert D. Bayett
COUNTY SURVEYOR

SURVEY FOR SUBDIVISION OF SECTION 19,
TOWNSHIP 18 SOUTH, RANGE 29 EAST, W.M.,
GRANT COUNTY, OREGON
MALHEUR NATIONAL FOREST
DON CADASTRAL SURVEY - BURNS RANGER DISTRICT
CONTRACT NO. 53-04H1-3-9357N

ARMSTRONG SURVEYING & ENGINEERING, INC.
378 EAST SECOND STREET
PRINEVILLE, OREGON 97754
503/447-7791

SHEET 3 OF 4

REGISTERED
PROFESSIONAL
LAND SURVEYOR

David B. Armstrong

7/9/85 OREGON
AUGUST 22, 1973
DAVID B. ARMSTRONG
1026

W.O.83-414E