

COR. NO.	CAP MARKINGS	FIELD BOOK-PAGE/DECL.	EVIDENCE FOUND	CORNER ACCESSORIES
11	T18SR29E S19 S20 S30 S29 LS1026 1985	7-17 & 18 M.V. 18°30'E	FOUND BASALT STN. 13"X13"X7" FIRMLY SET MKD. WITH 2 DISTINCT GROOVES S. FACE AND 5 DISTINCT GROOVES E. FACE. STN. SURROUNDED BY SMALL STN. MND. 2 FT. DIA. CONSISTING OF 5 OTHER STONES. REMONUMENT: SET 2 1/2"X30" ALUM. PIPE 26" IN GRND. WITH 3 1/4" ALUM. CAP MARKED AS SHOWN.	ORIGINAL BT'S FOUND: 23" POND. PINE, S41°30'E, 23.3 FT., V.S.-S29T18R29BT; 22" POND. PINE, S25°00'W, 14.6 FT., FACE NEARLY GROWN OVER - SCRIBING VISIBLE BUT NOT LEGIBLE. MARKED NEW BT'S: 14" DOUGLAS FIR, N47°00'W, 36.8 FT., SCRIBED-T18SR29ES19BT; 8" DOUG. FIR, N46°30'E, 11.4 FT., SCRIBED-T18SR29ES20BT. RAISED 2 1/2 FT. DIA. STONE MOUND TO CAP.

CORNER NOTES

BOOK AND PAGE NUMBERS REFER TO FIELD BOOK AND PAGE. ALL CORNER MONUMENTS SET ARE 2 1/2 INCH O.D. ALUMINUM PIPE 30 INCHES LONG WITH 3 1/4 INCH ALUMINUM CAP MARKED AS PER CORNER DIAGRAM. ALL BEARING TREES ARE SCRIBED AS PER B.L.M. MANUAL OF INSTRUCTIONS, 1973, WITH THE ADDITION OF A BRASS WASHER MARKED "AS&E LS1026" NAILED IN LOWER BLAZE. BEARINGS TO BEARING TREES ARE BY STAFF COMPASS USING DECLINATION AS NOTED, DISTANCES ARE MEASURED TO CENTER SIDE OF BEARING TREE. SEE ALSO ACCOMPANYING CERTIFIED RECORD OF LAND CORNER MONUMENTATION FOR ALL CORNERS SET OR MAINTAINED. THIS CORNER RECORD SHOULD BE CONSULTED FOR A MORE COMPLETE DESCRIPTION OF EVIDENCE FOUND AND MONUMENTATION OF CORNER.

SURVEYOR'S CERTIFICATION

I, DAVID B. ARMSTRONG, A REGISTERED PROFESSIONAL LAND SURVEYOR IN THE STATE OF OREGON, ON THE BASIS OF MY KNOWLEDGE, INFORMATION, AND BELIEF, CERTIFY THAT THIS PLAT, SURVEY NARRATIVE, AND CERTIFIED CORNER RECORDS AND/OR NOTES ARE A CORRECT REPRESENTATION OF A SURVEY PERFORMED DURING JUNE, 1984-MAY, 1985, AT THE REQUEST OF THE U.S.D.A., FOREST SERVICE, IN ACCORDANCE WITH STATUTES OF THE STATE OF OREGON AND ARTICLES OF CONTRACT NO. 53-04H1-3-9357N WITH ARMSTRONG SURVEYING & ENGINEERING, INC..

RECORDATION
OFFICE OF COUNTY SURVEYOR,
COUNTY OF Grant,
STATE OF OREGON. I HEREBY
CERTIFY THAT THE WITHIN IN-
STRUMENT WAS FILED FOR RECORD
ON THE 15 DAY OF July,
1985.
Robert D. Baggett
COUNTY SURVEYOR

SURVEY FOR SUBDIVISION OF SECTION 19,
TOWNSHIP 18 SOUTH, RANGE 29 EAST, W.M.,
GRANT COUNTY, OREGON
MALHEUR NATIONAL FOREST
DON CADASTRAL SURVEY - BURNS RANGER DISTRICT
CONTRACT NO. 53-04H1-3-9357N

ARMSTRONG SURVEYING & ENGINEERING, INC.
378 EAST SECOND STREET
PRINEVILLE, OREGON 97754
503/447-7791 SHEET 4 OF 4

REGISTERED
PROFESSIONAL
LAND SURVEYOR
David B. Armstrong
7/9/85 OREGON
AUGUST 22, 1973
DAVID B. ARMSTRONG
1026
W.O.83-414E